


# PROJECT REPORT



## VICINITY MAP

In San Bernardino County, On United States Route 395  
From 0.16 mi North Of Interstate Route 15 Junction  
To 1.80 mi South Of Desert Flower Road

*I have reviewed the right of way information contained in this Project Report and the R/W Data Sheet attached hereto, and find the data to be complete, current, and accurate:*

**BASEM MUALLEM** – ACTING DEPUTY DISTRICT DIRECTOR  
RIGHT OF WAY

APPROVAL  
RECOMMENDED:

For **DAVID BRICKER** – DEPUTY DISTRICT DIRECTOR  
ENVIRONMENTAL PLANNING

**JIM ROBINSON** – PROJECT MANAGER

GAM **CHRISTY CONNORS** – DEPUTY DISTRICT DIRECTOR DESIGN  
FOR


APPROVED:

**RAYMOND W. WOLFE, PHD** - DISTRICT DIRECTOR

12/31/09  
Date

08-SBd-395, PM R4.0/19.3  
08-236-0F6300  
HE-13(STIP)  
20.20.025.700

This Project Report has been prepared under the direction of the following registered civil engineer. The registered civil engineer attests to the technical information contained herein and the engineering data upon which recommendations, conclusions, and decisions are based.



REGISTERED CIVIL ENGINEER

12/21/09

DATE



SUPERVISING ENGINEER

12/21/09

DATE

## TABLE OF CONTENTS

<b>1. INTRODUCTION</b> .....	1
<b>2. RECOMMENDATION</b> .....	1
<b>3. BACKGROUND</b>	
A. Project History.....	1
B. Existing Facility.....	2
<b>4. NEED AND PURPOSE</b>	
A. Problems, Deficiencies, Justifications.....	2
B. Regional and System Planning.....	3
C. Traffic.....	3
<b>5. ALTERNATIVES</b>	
A. Viable Alternatives.....	5
B. Rejected Alternatives.....	7
<b>6. CONSIDERATIONS REQUIRING DISCUSSION</b>	
A. Hazardous Waste.....	8
B. Value Analysis.....	8
C. Resource Conservation.....	8
D. Right of Way Issues. ....	8
E. Environmental Issues.....	8
F. Air Quality Conformity.....	10
G. Title VI Considerations.....	10
H. Highway Planting ....	11
I. Non-Motorized and Pedestrian features, etc. ....	11
<b>7. OTHER CONSIDERATIONS AS APPROPRIATE</b>	
A. Public Hearing Process.....	12
B. Permits.....	12
C. Transportation Management Plan for Use During Construction.....	12
D. Stage Construction.....	13
E. System Planning.....	13
F. Pavement Life Cycle Cost Analysis.....	13
<b>8. PROGRAMMING</b> .....	14
<b>9. PROJECT REVIEWS</b> .....	14
<b>10. PROJECT PERSONNEL</b> .....	14
<b>11. LIST OF ATTACHMENTS</b> .....	15

# PROJECT REPORT

## 1. INTRODUCTION

It is proposed to improve the operational efficiency of United States Highway 395 (US-395) from 0.16 mi north of the junction of US-395 and Interstate 15(I-15) PM R4.0, in the City of Hesperia to PM 19.3, approximately 1.80 mi south of Desert Flower Road in the City of Adelanto, in San Bernardino County. This project was initiated at the request of the Cities of Hesperia, Victorville and Adelanto, in an effort to improve the operational efficiency of the facility by increasing the carrying capacity of the facility. The existing highway within the project limit varies from 2 to 4 lanes. Along the existing 2-lane segments passing opportunities are severely restricted due to the large volume of traffic and the high percentage of truck traffic.

This project is classified as a Category 4A project as defined in the Project Development Procedures Manual (7<sup>th</sup> Edition, Part 2, Chapter 8, Section 5) because it will substantially increase the traffic capacity of the highway. The total estimated construction cost including right of way and structures for the proposed alternative is \$109,215,000. Funding for the Project Approval and Environmental Document (PA/ED) phase of the project will be provided by San Bernardino Associated Government (SANBAG) under the terms of the approved cooperative agreement (No. 08-1250), dated May 4, 2005. Additional funding for subsequent phases of the project is anticipated from Federal, State, and local governments. This project is eligible for programming under the State Transportation Improvement Program (STIP) under the HE-13 (20.20.025.700) – Highway Widening Program. This project is included in the 2008 Regional Transportation Plan (RTP). There is strong support for the proposed improvements from local governments and there is no known opposition.

## 2. RECOMMENDATION

It is recommended that this Project be approved using the Preferred Alternative and that project proceed to the design phase.

## 3. BACKGROUND

### A. Project History

The District 8 Pre-Program Engineering Studies, via Project Initiation Proposal (PIP) number 2728, initiated the project. The PIP 2728 combined PIP 2659 and 2660 that recommended widening US-395 from Post Mile (PM) 3.98 to 19.30. It is proposed to combine both locations into a single project under one Expenditure Authorization to

facilitate the project development process and improve efficiency. A Project Study Report/Project Development Support was approved on August 1, 2005.

## **B. Existing Facility**

The segment of US-395 within District 08 is divided into five (5) segments as described in the 2002 Route Concept Report. This project report focuses on Segment one from Jct. I-15 to Jct. SR-18, Segment two Jct. SR-18 to El Mirage Rd., and a small portion of Segment three from El Mirage Rd. to Calleja Rd. Within the project limits, the existing facility is in general a two-lane road with some segments that have been widened at intersections and other locations to accommodate rapid urbanization along this corridor. The existing lanes are 12 feet wide and shoulder widths vary from five to eight feet. The structural section of the existing roadbed consists of asphalt concrete pavement. The horizontal alignment of the existing facility consists of long tangent sections with horizontal curves. The vertical alignment of the existing roadbed is essentially flat, except for a significant dip between Hollister Road and Phelan Rd. /Main St. There are two major bridge structures within the project limits. The California Aqueduct Bridge (Br. No. 54-0829) located at PM6.83 is a single span reinforced concrete box girder structure. The Joshua Wash Bridge (Br. No. 54-0524) located at PM14.58 is a double reinforced concrete box culvert.

## **4. NEED AND PURPOSE**

### **A. Problem, Deficiencies, Justification**

Within the project limits, US-395 is generally a two-lane conventional highway with one 12 ft-lane and shoulder that varies from five to eight feet in each direction. Large volumes of traffic with high percentages of truck traffic that circulate along these segments of US-395 restrict passing opportunities. Operating conditions within the project limits are expected to continue to deteriorate as traffic demand increases owing to growth and development currently taking place along the corridor. Without significant and timely improvements, regional and inter-regional travel along this corridor will be severely compromised.

Approaches to several major intersections have already been improved to provide exclusive left turn lanes; two lanes for through traffic, and dedicated right turn lanes. However, the unimproved segments between these intersections are still major impediments to the efficient flow of traffic.

Widening between the segments to accommodate 2 lanes in each direction with a continuous 14-foot wide median consisting of left turn pockets will increase the operational capacity and will enhance the operational efficiency of the corridor by improving passing opportunities.

**B. Regional and System Planning**

US-395 in San Bernardino County begins at the junction with Interstate 15 (I-15) (PM R3.98) in Hesperia and ends at the Kern County Line (PM 73.51). The route segment within District 08 is approximately 70 mi. US-395 is classified as a Rural Principal Arterial, and is included in the Surface Transportation Assistance Act (STAA) as a route for the movement of extra legal permits loads. It is also classified as a High Emphasis, Focus and Gateway route as part of the California Interregional Road System (IRRS), providing access to and links between economic centers, recreational areas, urban and rural regions. It is also part of the Strategic Highway Network (STRAHNET) serving the Naval Air Weapons Station at China Lake and Edwards Air Force Base. The proposed project is consistent with statewide, regional, and local planning goals, and is being coordinated with impacted governmental, regulatory and private agencies in the area to ensure consistency with their specific goals and objectives. The proposed improvements are consistent with the Route Concept Report.

**C. Traffic**

Current and Forecasted Traffic

The existing and projected traffic data for US-395 within the project limits are as shown in Table 1 below.

**Table 1**

LOCATION	ADT		DHV		Trucks (%)		Directional Split	
	2006	2035	2006	2035	2006	2035	2006	2035
PM R4.0/11.18	27,700	33,700	1,548	2,865	12	12	60/40	60/40
PM 11.18/19.36	16,800	25,800	822	3,241	10	10	60/40	60/40

Existing and projected LOS and Volume Capacity Ratios have been developed and analyzed to existing operating conditions and impact of the proposed improvements. This data is presented in Table 2.

**Table 2**

LOCATION	LOS			Volume Capacity Ratio (V/C)		
	2006	2035 (No-build)	2035 (Alt 2&3)	2006	2035 (No-build)	2035 (Alt 2&3)
PM R4.0/11.18	E	F	B	0.53	0.98	16.5
PM 11.18/19.36	C	F	C	0.28	1.11	18.6

At the current rate of growth, traffic is expected to increase by 30% by year 2035. As a result, levels of service are expected to deteriorate rapidly to breakdown conditions. The proposed widening improvements would restore the facility to its desirable level of service and would also enhance the overall operational safety of these segments along US-395.

Accident Rates

Accident data from the Traffic Accident Surveillance and Analysis System (TASAS) for US-395 for this project limits from January 1, 2006 through December 31, 2008 are shown in Table 3.

**Table 3**

LOCATION	ACTUAL RATES (Million vehicle miles)			AVERAGE RATES (Million vehicle miles)		
	F	F + I	TOT	F	F+I	TOT
PM R4.0/19.36	0.019	0.25	1.14	0.019	0.48	1.17

The accident data for the period from January 1, 2006 through December 31, 2008, indicates that the total accident rate within this segment was higher than average rates for similar type facilities. The accidents involved Rear End, Broadside, Sideswipe, Head On, Overturn and Hit Object due to excessive speed, failure to yield, and unsafe turning

movement. Providing additional capacity and median is expected to improve passing opportunities, minimize traffic conflicts, and reduce the number of accidents.

## 5. **ALTERNATIVES**

### **A. Viable Alternatives**

This Project Report assesses the three alternatives as follows:

- Alternative 1: No-Build.
- Alternative 2: Widening the highway on existing alignment.
- Alternative 3: Widening the highway on realigned alignment.

#### **Alternative 1 (rejected) - No-Build**

This alternative consists of no physical improvements or modification at this time. There are no capital costs associated with this alternative. Under this scenario, the existing operational deficiencies will not improve and could potentially result in an increase in the number of accidents. Also, with the No-Build alternative, maintenance costs can be expected to increase. Therefore, this is not an acceptable alternative.

#### **Alternative 2 (preferred) - Widening the highway on existing alignment**

The existing centerline alignment would be maintained and the roadbed would be widened approximately 22 feet in each direction. This alternative would provide two 12-ft lanes with 8-ft outside shoulders in each direction, and a 14-ft median with rumble strips. The median would provide a buffer between opposing traffic flows and the necessary pockets for left-turn maneuvers, thereby, enhancing the safety of the traveling public. A key highlight of this proposal features existing intersections previously widened, seamlessly matching this alternative's cross section with no further widening or realignment necessary. Right of way acquisitions and utility relocations would be necessary with this alternative but no exceptions to current design standards would be needed. This alternative would meet the projected traffic demands.

- **Proposed Engineering Features**

The existing single span California Aqueduct Bridge No. 54-0829 L/R and the Joshua Wash Bridge No. 54-0524 would also need to be widened to accommodate the proposed roadway improvements. In addition, the following five intersections are proposed for improvement: Holly Road/Hopland Street, Seneca Road, Air Base Road, Auburn Avenue and El Mirage Road.



- **Cost Estimate**

The total cost for the proposed improvements for this Alternative including Right of Way, as shown in Table 4, is estimated at approximately \$109,215,000 (see attachment D).

**Table 4 - Summary of Cost Estimate for Alternative 2**

<b>Item</b>	<b>Cost</b>
Total Roadway Items	\$96,968,000
Total Structures Items	\$1,966,000
Total Right of Way Items	\$10,281,000
<b>TOTAL</b>	<b>\$109,215,000</b>

- **Utility and Other Owner Involvement**

Based on an initial utility search within the project area listed on the Right of Way Data Sheet, the following utilities may be impacted:

Southern California Edison Company, Distribution/Transmission; Verizon; Sprint; Kinder Morgan (CalNev); SouthWest Gas; AT&T; L.A. Dept. Power & Water; San Bernardino Co Area 64; Baldy Mesa Co Water Dist; Charter Comm-High Desert & Hesperia; Victor Valley Wastewater Reclamation Authority; MCI (Verizon Business); San Bernardino Co Services; City of Adelanto; Hesperia Water; Time Warner Communications; City of Victorville; and Southern California Gas-Trans.

**Alternative 3 (rejected) - Widening the highway on realigned alignment**

It is proposed to realign US-395 at several locations between Hollister Road and Coronado Avenue. The roadbed would be widened approximately 22 feet in each direction. This alternative would provide two 12-ft lanes with 8-ft outside shoulders in each direction, and a 14-ft median with rumble strips. The median would provide a buffer between opposing traffic flows and the necessary pockets for left-turn maneuvers, thereby, enhancing the safety of the traveling public. Under this alternative, some of the existing segments of US-395 that had been widened to four lanes will not match the new alignment and will need to be reconstructed. Right of way acquisitions and utility relocations would be necessary with this alternative but no exceptions to current design standards would be needed. This alternative would meet the projected traffic demands.

- **Proposed Engineering Features**

The existing single span California Aqueduct Bridge No. 54-0829 L/R and the Joshua Wash Bridge No. 54-0524 would also need to be widened to accommodate the proposed roadway improvements. Additionally, the following five

intersections are proposed for improvement: Holy Road/Hopland Street, Seneca Road, Air Base Road, Auburn Avenue and El Mirage Road.

- **Cost Estimate**

The total cost for the proposed improvements for this Alternative including Right of Way, as shown in Table 5, is estimated at approximately \$122,866,000 (see attachment D).

**Table 5 - Summary of Cost Estimate for Alternative 3**

<b>Item</b>	<b>Cost</b>
Total Roadway Items	\$109,780,000
Total Structures Items	\$1,849,000
Total Right of Way Items	\$11,237,000
<b>TOTAL</b>	<b>\$122,866,000</b>

- **Utility and Other Owner Involvement**

Based on an initial utility search within the project area listed on the Right of Way Data Sheet, the following utilities may be impacted:

Southern California Edison Company, Distribution/Transmission; Verizon; Sprint; Kinder Morgan (CalNev); SouthWest Gas; AT&T; L.A. Dept. Power & Water; San Bernardino Co Area 64; Baldy Mesa Co Water Dist; Charter Comm-High Desert & Hesperia; Victor Valley Wastewater Reclamation Authority; MCI (Verizon Business); San Bernardino Co Services; City of Adelanto; Hesperia Water; Time Warner Communications; City of Victorville; and Southern California Gas-Trans.

## **B. Rejected Alternatives**

The Project Study Report had the similar alternatives as the Project Report. The No-Build alternative will not address the need to enhance the highway safety for the public on this section of the US-395. Therefore this alternative does not meet the need and purpose of this project.

Alternative 3 is widening the highway on realigned alignment. This alternative is a viable alternative, but is least desirable compared to Alternative 2, due to the potential cost increase, major impact to the existing traffic and longer construction period. Therefore, this is not an acceptable alternative

**6. CONSIDERATIONS REQUIRING DISCUSSION**

**A. Hazardous Waste**

An Initial Site Assessment (ISA) for hazardous waste was completed on May 11, 2009. The ISA determined there are no Aerially Deposited Lead (ADL) or hazardous waste concerns for this project. Therefore, no special provisions are required for ADL (See Attachment E).

If removal of yellow thermoplastic striping is necessary for restriping the roadway, some of the material removed may require testing for elevated levels of lead and chromium prior to complete removal and disposal.

**B. Value Analysis**

A Value Analysis Study (VA) was conducted for this project in May 2006. The VA Team developed 14 VA alternatives: Seven were accepted, one was conditionally accepted, and the remainder was rejected. The accepted VA alternatives propose the widening of the highway on one side only where right of way encroachment impacts can be avoided, including adjusting the right of way at Post Mile (PM) 7.38 to avoid the high tension line tower; eliminate the continuous two-way left-turn lane through controlled striping in favor of controlled left turns at intersections; reduce the cross section to no less than the right of way agreed to in the Memorandum of Understanding with impacted cities; use an open-graded asphalt pavement surface; coordinate signals to improve traffic flow; and encourage developers to construct soundwalls in lieu of Caltrans building them.

**C. Resource Conservation**

It is expected that existing Asphalt Concrete (AC) pavement materials would be recycled, and measures taken to minimize the consumption, destruction and disposal of nonrenewable resources.

**D. Right of Way Issues**

The build alternatives under consideration would require additional Right of Way and the relocation of utilities. See Attachment G – Right of Way Data Sheets for additional details.

**E. Environmental Issues**

Caltrans is the California Environmental Quality Act (CEQA) Lead Agency and the National Environmental Policy Act (NEPA) Lead Agency for this project.

As owner-operator of the State Highway System (SHS), the Department is the CEQA Lead Agency for all improvement projects on the SHS. Effective July 1, 2007, the

Department has been assigned environmental review and consultation responsibilities under NEPA pursuant to 23 U.S.C. 327. The environmental review, consultation, and any other action required in accordance with applicable Federal laws for this project is being, or has been, carried out by Caltrans under its assumption of responsibility pursuant to 23 U.S.C. 327. Accordingly, Caltrans is the lead agency under both the California Environmental Quality Act (CEQA) and the National Environmental Policy Act (NEPA).

For this project Caltrans determined an Initial Study (IS) to be the appropriate environmental documentation for CEQA compliance. Regarding NEPA compliance documentation, based on an examination of the project and the results of the supporting Technical Studies performed, Caltrans determined the project eligible to receive a Categorical Exclusion under Section 6005 of 23 U.S.C. 327.

The IS was prepared in accordance with Caltrans' environmental procedures as well as State environmental regulations. Following public circulation and final review of all applicable environmental documentation, Caltrans determined that the proposed project would not have a significant effect on the environment and adopted a Mitigated Negative Declaration (MND) for the IS on December 30, 2009. The Department's Categorical Exemption/Categorical Exclusion Determination Form was utilized to document compliance with NEPA requirements. The Determination Form for this project was signature approved on December 31, 2009.

#### Water Quality

Storm water discharge will be regulated as per the National Pollutant Discharge Elimination System (NPDES) Statewide Storm Water Permit for the State of California, Department of Transportation (NPDES No. CAS000003). A Storm Water Pollution Prevention Plan (SWPPP) will be required and the cost associated with it is included in the project cost estimate. Permanent and temporary Best Management Practices (BMPs) as required by the Regional Water Quality Control Board may need to be implemented to provide water pollution control.

#### Biological Resources

Impacts to biological resources including natural communities of concern, water bodies, and sensitive species are analyzed in the Natural Environment Study (NES). Avoidance and minimization measures will be implemented prior to and during construction to reduce impacts to Waters of the U.S., the federally and state threatened desert tortoise, and state threatened Mohave ground squirrel. A permanent desert tortoise exclusion fence will be placed at the proposed Right of Way along the entire project length, to prevent desert tortoise from crossing US 395. Mitigation agreements with the United States Fish and Wildlife Service (USFWS) and the California Department of Fish and Game (CDFG) will be finalized during the Plans, Specifications and Estimates (PS&E) phase of the project, and implemented as stipulated. 16.51 acres of disturbed habitat will be mitigated at a 3:1 ratio for project impacts to desert tortoise and Mohave ground squirrel habitat along the project site. Mitigation agreements are expected to be at a ratio between 1:1 and 3:1 depending on the quality of the habitat.

## **F. Air Quality Conformity**

The proposed project study area is located in the Mojave Desert Air Basin (MDAB). The MDAB is under jurisdiction of the Mojave Desert Air Quality Management District (MDAQMD). The portion of the MDAB where the project is located is in attainment for Carbon monoxide (CO), PM<sub>2.5</sub> and Nitrogen dioxide (NO<sub>2</sub>). The MDAB area is a federal non-attainment area for respirable particulate matter (PM<sub>10</sub>) and Ozone (O<sub>3</sub>).

The proposed project is included in the Southern California Association of Governments (SCAG) Final 2008 Regional Transportation Plan (RTP) Amendment # 1 and SCAG Final 2008 Regional Transportation Improvement Program (RTIP) Amendment # 08-01 under project identification number 200451 for the RTIP and project identification number 4M0802 for the RTP. Both the 2008 RTP Amendment #1 and Final 2008 RTIP Amendment # 08-01 were found to be conforming by Federal Highway Administration (FHWA) on January 14, 2009. The project design concept and scope as described in this Project Report is consistent with the project description in the current RTP and RTIP and the assumptions in the SCAG regional emissions analysis. As such, it can be concluded that the project's operational emissions, which include the ozone (O<sub>3</sub>) precursors reactive organic gases (ROG) and nitrogen oxides (NOX), meet regional transportation conformity determination requirements imposed by the U.S. Environmental Protection Agency (EPA) and the Mojave Desert Air Quality Management District (MDAQMD) and as such, the project would not exceed the motor vehicle emissions budget for the region; and meets planning and regional requirements to demonstrate federal conformity, and is consistent with local planning efforts.

It is anticipated from the performed project-level Air Quality Analysis that the selected alternative would neither cause or contribute to any new localized violation of federal 1-hour or 8 hour CO federal Ambient Standards, nor would increase or cause to exceed frequency of violation of PM<sub>10</sub> 24 hour's NAAQQS standards in the area affected by implementation of the project.

Particulate Matter interagency consultation was initiated with the Southern California Association of Government's Transportation Conformity Working Group (TCWG) at the June 24, 2008 meeting of TCWG. The project was determined to not be a Project of Air Quality Concern, with some additional information requested. The requested follow-up was confirmed to be acceptable via emails in August of 2008.

The required "Project-Level Conformity Determination Letter" from FHWA, for this project, was issued on December 1, 2009.

## **G. Title VI Considerations**

Implementation of either alternative will not result in any disproportionately high or adverse impacts on minority or low-income neighborhoods or communities. Caltrans policies demonstrate a commitment to Title VI of the Civil Rights Act, which provides

that no person in the United States shall, on the grounds of race, color, or national origin, be excluded from participation in, be denied the benefits of, or be subjected to, discrimination under any program or activity receiving federal financial assistance.

## **H. Highway Planting**

This project will not result in a substantial impact to the visual character of the landscape. Joshua trees (*Yucca Brevifolia*), the most vivid vegetation element in the landscape, and an important visual marker of the Joshua trees, are protected by the "California Desert Plant Protection Act", which requires a tag through the Department of Food and Agriculture if five or more trees are to be removed. In addition, Joshua trees are protected by Chapter 1333 of the Victorville Municipal Code, which prohibits the destruction or removal of Joshua trees without written consent from the Director of Parks and Recreation. All trees must be relocated to appropriate sites within State right of way to preserve the visual character of the landscape. Supplemental watering will also be required after transplanting takes place.

In addition, existing native vegetation within State right of way should be preserved as feasible during construction to maintain visual continuity from the edge of pavement, through State right of way, to the surrounding landscape. For the same reason, temporary impacts should be replanted with native plants from the Joshua tree woodland and creosote scrub associations. Erosion control must be applied to all slopes.

Retaining walls/noise barriers will have an impact on the rural character of Route 395. Vine planting and/or aesthetics will be used to minimize the wall's impact. These will prevent/minimize graffiti. A water source will be required for vine planting.

## **I. Non-Motorized and Pedestrian features, etc.**

Pedestrians, bicyclists, and persons with disabilities are users of the transportation facility. They should be able to use the facility safely. Non-motorized traveler considerations should be an integral part of this major widening project. Pursuant to Americans with Disabilities Act Guidelines, pedestrian facilities shall be graded to current guidelines. The engineer in charge needs to identify ADA deficiencies such as sidewalk obstructions, sidewalk gaps, detectable warning surface, dual curb ramps at each corner, level landing areas, crosswalk pavement condition, sidewalk cross slope, and others.

The segment of US-395 between Palmdale Road and Mojave Drive in the City of Adelanto has been designated (by SANBAG in their 2001 Non-Motorized Plan) as a Priority Class 2 or 3 Bikeway. However, additional studies are needed to determine bicycle travel demand, and the viability of US-395 as a bikeway. This issue would be the subject of a separate study.

**7. OTHER CONSIDERATIONS AS APPROPRIATE**

**A. Public Hearing Process**

A public information meeting was held in March 2009 to solicit public input. No Public Hearing or Open House was scheduled for this project during circulation of the Draft Initial Study with Proposed Mitigated Negative Declaration (DED).

The DED was circulated for public comment from September 5, 2009 through October 5, 2009. A Public Notice was published in the Daily Press on September 4, 2009. On that same date a Spanish notice was also published in the El Mojave newspaper announcing the “Notice of Intent to Adopt a Mitigated Negative Declaration Study results available/Changes proposed for US 395.” The DED was also made available for public review at the Victorville City Hall and the Department’s District 8 Office in San Bernardino.

No requests were received to hold a public meeting for the project.

**B. Permits**

Permits and approvals that may be required for the proposed project are as follows:

- Section 2081 Incidental Take Permit from the California Department Of Fish and Game for the incidental take of two threatened species, the desert tortoise and Mohave ground squirrel.
- 1602 Agreement for Streambed Alteration from the State Department of Fish and Game
- Section 404 permit from the U.S. Army Corps of Engineers
- Section 401 permit from the Regional Water Quality Control Board
- Additional permits for the material site and disposal site; and Bureau of Land Management (BLM) approval may also be required.
- Section 402 of the Clean Water Act (NPDES)
- NPDES and the Construction Statewide Permit. (Order No. 99-06-DWQ, NPDES, No. CAS000003 and CA000002)

**C. Transportation Management Plan for Use During Construction**

A Preliminary Transportation Management Plan (TMP) has been prepared during the Project Report Stage. An estimated cost for the TMP has been included in the cost estimate and includes the items for the Construction Zone Enhanced Enforcement Program (COZEPP), Portable Changeable Message Signs, Public Awareness Campaign and Lane Closure Charts that have been developed to minimize traffic impacts during construction and to ensure the safety of the traveling public (See Attachment I). During the design phase a more detailed plan will be provided

#### **D. Stage Construction**

Preliminary staging for both alternatives 2 and 3 is proposed as following:

Stage 1: Cold plane and overlay existing northbound shoulder.

Stage 2: Switch traffic to the east and widen the southbound.

Stage 3: Switch traffic to the west and widen the northbound.

Stage 4: Resurface existing pavement and construct ground-in rumble strips in the median.

A more detailed stage construction will be developed during design phase.

#### **E. System Planning**

The proposed improvements are consistent with the Route Concept Fact Sheet, dated January 2002, which calls for a 10-lane freeway as the ultimate concept facility for this corridor. The improvements are also consistent with statewide, regional, and local mobility goals. Coordination with impacted governmental, regulatory and local agencies in the project area will be maintained to ensure conformity with regional and local development plans. A Memorandum of Understanding (MOU) between The Department, the Cities of Victorville, Hesperia and Adelanto, the County of San Bernardino, and the San Bernardino Associated Governments (SANBAG), with an effective date of October 18, 2002, provides the guidance to the respective obligations, intentions and policies regarding new development along the corridor, and the acknowledgement of planning efforts for the existing and new facility.

#### **F. Pavement Life Cycle Cost Analysis (LCCA)**

Two pavement alternatives were chosen for the Life Cycle Cost Analysis (LCCA). Per HDM table 612.2, 20-year design life was considered.

Alternative Pavement 1. Hot mix Asphalt (HMA) (Flexible); 0.95 ft HMA/1.95 ft Aggregate Base (AB) Class 2, 20-year design life.

Alternative Pavement 2. Rubberized Hot mix Asphalt – Gap Graded (RHMA-G) (Flexible); 0.20 ft (RHMA-G) / 0.75 ft HMA/1.95 ft Aggregate Base (AB) Class 2, 20-year design life.

Based on the Traffic Index (TI) and LCCA Procedures Manual it was decided to compare the two flexible pavements. The analysis was performed using RealCost, Version 2.2.2 to obtain the deterministic result as specified in the LCCA Procedure Manual. Alternative Pavement 1 was chosen as the preferred alternative.



**8. PROGRAMMING**

Funding for this project will be from the Regional STIP and Measure I. This Project is proposed for funding in 2013/14 Fiscal Year. The total cost estimate including Right of Way is **\$109,215,000**. Any required updates to the RTIP and/or RTIP regarding project schedule and funding, pertaining to PA&ED, PS&E, acquisition of ROW or Construction are expected to be addressed in the required timeframe.

**9. REVIEWS**

<b>Name</b>	<b>Organization</b>	<b>Date</b>
Mr. Luis Betancourt	HQ Design Coordinator	May 15, 2008
Mr. Brian Frazer	HQ Design Reviewer	May 15, 2008
Mr. Alex Kennedy	HQ Traffic Operation Liaison	May 20, 2008

**10. PROJECT PERSONNEL**

<b><u>Name</u></b>	<b><u>Title and Branch</u></b>	<b><u>Telephone No.</u></b>
Ben Amiri	Office Chief Design "I"	(909) 383-6872
Juan Carlos Alvarez	Project Engineer Design "I"	(909) 383-4931
Jim Robinson	Project Manager	(909) 917-8839
Boniface Udotor	Office Chief Environmental Studies	(909) 388-1387
Mike Romo	Right of Way Planning & Management	(909) 383-6912
Kurt Heidelberg	Office Chief Environmental Planning & Management	(909) 383-7505
Stephen Hatt	Office Chief Right of Way Utilities	(909) 383-4582
Ray Desselle	Office Chief Landscape Architect	(909) 383-4529
Bruce Kean	Materials Engineer & IAST	(909) 383-4044


Bill Wasser & Larry Sartori	Office Chief Traffic Design	(909) 383-6887 (909) 383-6810
Howard NG	Office Chief Bridge Design Branch 20	(909) 598-6367

**11. ATTACHMENTS**

Attachment A Location Map  
Attachment B Typical Cross Sections  
Attachment C Bridge Advance Planning Study  
Attachment D Cost Estimate  
Attachment E Initial Site Assessment (ISA)  
Attachment F Initial Study with Mitigated Negative Declaration / NEPA Section 6005 CE  
Attachment G Right of Way Data Sheet  
Attachment H Storm Water Data Report (SWDR)  
Attachment I Project Category Assignment  
Attachment J Traffic Management Plan (TMP)  
Attachment K Project Initiation Proposal (PIP)

# **ATTACHMENT A**

## **Location Map**



# **ATTACHMENT B**

## **Typical Cross Sections**

STATE OF CALIFORNIA - DEPARTMENT OF TRANSPORTATION  
**Caltrans** DESIGN

PROJECT ENGINEER  
**J.C. ALVAREZ**

CALCULATED/DESIGNED BY  
 CHECKED BY

DATE REVISIONS

DESIGN DESIGNATION (US-395)

LOCATION 1 PM R4.00/11.18	
ADT (2004) = 24,500	ADT (2030) = 42,600
2030 DHV=3,830 D=65/35	T=12% V=70 MPH
LOCATION 2 PM 11.18/19.30	
ADT (2004) = 15,500	ADT (2030) = 36,600
2030 DHV=3,290 D=55/45	T=10% V=70 MPH



DIST	COUNTY	ROUTE	POST MILES TOTAL PROJECT	SHEET NO.	TOTAL SHEETS
08	SBd	US-395	R4.0/19.3	1	2

REGISTERED CIVIL ENGINEER

PLANS APPROVAL DATE

The State of California or its officers or agents shall not be responsible for the accuracy or completeness of electronic copies of this plan sheet.

To get to the Caltrans web site, go to: <http://www.dot.ca.gov>

**US-395**  
 FROM STA 269+00 TO 1049+00

**ALTERNATIVE 2**  
**TYPICAL CROSS SECTION**

NO SCALE X-1



USERNAME => jalvarez  
 DGN FILE => typ1ca1\_xsect\_A1+2\_3\_rev.dgn

CU 00000

EA 000000

DATE PLOTTED => 11-JAN-2010  
 TIME PLOTTED => 14:24

DATE REVISION BY  
DATE REVISION BY

CALCULATED/DESIGNED BY  
CHECKED BY

PROJECT ENGINEER  
**J.C. ALVAREZ**

STATE OF CALIFORNIA - DEPARTMENT OF TRANSPORTATION  
**DESIGN**

DESIGN DESIGNATION (US-395)			
LOCATION 1		PM R4.00/11.18	
ADT (2004) = 24,500	ADT (2030) = 42,600		
2030 DHV=3,830	D=65/35	T=12%	V=70 MPH
LOCATION 2		PM 11.18/19.30	
ADT (2004) = 15,500	ADT (2030) = 36,600		
2030 DHV=3,290	D=55/45	T=10%	V=70 MPH



DIST	COUNTY	ROUTE	POST MILES TOTAL PROJECT	SHEET NO.	TOTAL SHEETS
08	Sbd	US-395	R4.0/19.3	2	2

REGISTERED CIVIL ENGINEER

PLANS APPROVAL DATE

The State of California or its officers or agents shall not be responsible for the accuracy or completeness of electronic copies of this plan sheet.

To get to the Caltrans web site, go to: <http://www.dot.ca.gov>

**US-395**  
FROM STA 269+00 TO 1049+00

- \* CENTER LINE SHIFTED WEST AT THIS SEGMENTS
  - FROM STA 301+57 TO 309+42
  - FROM STA 450+67 TO 488+93
  - FROM STA 699+50 TO 971+78
  - FROM STA 997+44 TO 1030+94
- \*\* CENTER LINE SHIFTED EAST AT THIS SEGMENTS
  - FROM STA 309+42 TO 421+63
  - FROM STA 431+25 TO 441+29
  - FROM STA 593+50 TO 608+10
  - FROM STA 971+78 TO 997+44

**ALTERNATIVE 3**  
**TYPICAL CROSS SECTION**

NO SCALE **X-2**



USERNAME => jcalvarez  
DGN FILE => typcal\_xsect\_A1+2\_3\_rev.dgn

CU 00000

EA 000000

DATE PLOTTED => 11-JAN-2010  
TIME PLOTTED => 14:25  
00-00-00

# **ATTACHMENT C**

## **Bridge Advance Planning Study**



# Memorandum

*Flex your power!  
Be energy efficient!*

To: BEN AMIRI  
Office Chief  
Design I, MS 971  
District 8

Date: January 07, 2009

File: 08-SBd-58- 4.0/19.3  
California Aqueduct Bridge (Widen)  
Joshua Wash Bridge (Widen)  
08-236-0F630K

From: FEIRUZ ABERRA *FA*  
Technical Liaison Engineer  
Office of Bridge Design South 2  
Division of Engineering Services

Subject: Advance Planning Study Cost Estimate Update

Division of Engineering Services has updated Advance Planning Study cost estimate for the above referenced project.

The estimated construction costs, including 10% time related overhead, 10% mobilization and 25% contingencies, is as follows:

## Alternative 2:

Bridge Name	Bridge No.	Estimated Cost
California Aqueduct Bridge (widen both sides)	54-0829	\$1,431,000
Joshua Wash Bridge (widen both sides)	54-0524	\$535,000
Total Cost		\$1,966,000

## Alternative 3:

Bridge Name	Bridge No.	Estimated Cost
California Aqueduct Bridge (widen one side)	54-0829	\$1,340,000
Joshua Wash Bridge (widen one side)	54-0524	\$509,000
Total Cost		\$1,849,000

Please refer to the previous transmittal memo dated December 20, 2007 for design assumptions used to prepare the above cost estimate.

If you have any questions or if you need additional information regarding this cost estimate, please contact me at (909) 595-7275.

c: MBeauchamp  
CPeterson

Revised - December 3, 2007

RCVD BY: JTY

IN EST: 12/10/2008

OUT EST: 12/22/2008

BRIDGE: Joshua Wash Bridge Alternative 2 BR. No.: 54-0524

TYPE: Box Culvert Widening

DISTRICT: 8.00

CU:

RTE: 395.00

EA: 08-0F6300

CO: SBDO

LENGTH: 36.000 WIDTH: 36.330

PM: 14.58

AREA (SF)= 1380

DESIGN SECTION: 20.00

# OF STRUCTURES IN PROJECT : 1.00

EST. NO. 2

PRICES BY : WSS

COST INDEX: 388

PRICES CHECKED BY : Porter

DATE:

QUANTITIES BY :

DATE:

	CONTRACT ITEMS	TYPE	UNIT	QUANTITY	PRICE	AMOUNT
1	TEMPORARY RAILING		LF			
2	REMOVE CONCRETE		CY			
3	STRUCTURE EXCAVATION (BRIDGE)		CY	38	\$145.00	\$5,510.00
4	STRUCTURE EXCAVATION		CY			
5	STRUCTURE BACKFILL (BRIDGE)		CY	267	\$100.00	\$26,700.00
6	PERVIOUS BACKFILL MATERIAL		CY			
7	CIDH CONCRETE PILING		LF			
8	FURNISH PILING		LF			
9	DRIVE PILES		EA			
10	FURNISH PC/PS CONCRETE GIRDERS		EA			
11	ERECT PC/PS CONCRETE GIRDERS		EA			
12	STRUCTURAL CONCRETE, BRIDGE	class 1	CY	128	\$1,200.00	\$153,600.00
13	STRUCTURAL CONCRETE, BRIDGE FOOTING		CY			
14	STRUCTURAL CONCRETE, APPROACH SLAB		CY			
15	PRESTRESSING STEEL		LB			
16	BAR REINFORCING STEEL (BRIDGE)		LB	27,774	\$1.25	\$34,717.50
17	FURNISH STRUCTURAL STEEL		LB			
18	ERECT STRUCTURAL STEEL (INCL PAINT)		LB			
19	JOINT SEAL ASSEMBLY (MR = ) > 2"		LF			
20	JOINT SEAL (MR = ) 2" max		LF			
21	SLOPE PAVING		CY			
22	CONCRETE BARRIER		LF			
23	MISCELLANEOUS METAL (BRIDGE)		LB			
24	MISC METAL (RESTRAINER - TIE ROD)		LB			
25	DRILL AND BOND DOWEL		LF	2,599	\$50.00	\$129,950.00
26						
27						
28						
29						
30						

SUBTOTAL	\$350,478
TIME RELATED OVERHEAD	\$35,048
MOBILIZATION ( @ 10 % )	\$42,836
SUBTOTAL BRIDGE ITEMS	\$428,361
CONTINGENCIES (@ 25%)	\$107,090
BRIDGE TOTAL COST	\$535,452
COST PER SQ. FOOT	\$388.04
BRIDGE REMOVAL (CONTINGENCIES INCL.)	
WORK BY RAILROAD OR UTILITY FORCES	
GRAND TOTAL	\$535,452
BUDGET ESTIMATE AS OF 12/22/08	\$535,000

**ROUTING**

- DES SECTION
- OFFICE OF BRIDGE DESIGN - NORTH
- OFFICE OF BRIDGE DESIGN - CENTRAL
- OFFICE OF BRIDGE DESIGN - SOUTH
- OFFICE OF BRIDGE DESIGN - WEST
- OFFICE OF BRIDGE DESIGN SOUTHERN CALIFORNIA

COMMENTS:

**Escalated Budget Estimate to Midpoint of Construction \***

Escalation Rate per Year

5.5%

Years Beyond Midpoint	Escalated Budget Est.
1	\$564,000
2	\$595,000
3	\$628,000

Years Beyond Midpoint	Escalated Budget Est.
4	\$663,000
5	\$699,000

\* Escalated budget estimate is provided for information only. actual construction costs may vary. Escalated budget estimates provided do not replace Departmental policy to update cost estimates annually.

Revised - December 3, 2007

RCVD BY: JTJ

IN EST: 12/10/2008

OUT EST: 12/24/2008

BRIDGE: California Aqueduct Bridge (Widen) Alt 2

BR. No.: 54-0829R/L

DISTRICT: 08

TYPE: CIP PS Box Girder

RTE: 395

CU: 08-00

CO: SBd

EA: OF6300

PM: 6.83

LENGTH: 110.000 WIDTH: 39.000

AREA (SF)= 4290

DESIGN SECTION: 20

# OF STRUCTURES IN PROJECT : 2

EST. NO. 2

PRICES BY : WSS

COST INDEX: 388

PRICES CHECKED BY :

DATE:

QUANTITIES BY :

DATE:

	CONTRACT ITEMS	TYPE	UNIT	QUANTITY	PRICE	AMOUNT
1	TEMPORARY RAILING		LF			
2	STRUCTURE EXCAVATION (BRIDGE)		CY	252	\$100.00	\$25,200.00
3	STRUCTURE EXCAVATION		CY			
4	STRUCTURE BACKFILL (BRIDGE)		CY	194	\$95.00	\$18,430.00
5	PERVIOUS BACKFILL MATERIAL		CY			
6	CIDH CONCRETE PILING		LF			
7	FURNISH PILING		LF			
8	DRIVE PILES		EA			
9	FURNISH PC/PS CONCRETE GIRDERS		EA			
10	ERECT PC/PS CONCRETE GIRDERS		EA			
11	STRUCTURAL CONCRETE, BRIDGE		CY	382	\$850.00	\$324,700.00
12	STRUCTURAL CONCRETE, BRIDGE FOOTING		CY	246	\$825.00	\$202,950.00
13	STRUCTURAL CONCRETE, APPROACH SLAB	9D	CY	246	\$650.00	\$159,900.00
14	PRESTRESSING STEEL		LB	16,826	\$2.25	\$37,858.50
15	BAR REINFORCING STEEL (BRIDGE)		LB	51,648	\$1.25	\$64,560.00
16	FURNISH STRUCTURAL STEEL		LB	16,264	\$3.65	\$59,363.60
17	ERECT STRUCTURAL STEEL (INCL PAINT)		LB			
18	JOINT SEAL ASSEMBLY (MR = ) > 2"		LF			
19	JOINT SEAL (MR = ) 2" max		LF			
20	SLOPE PAVING		CY			
21	CONCRETE BARRIER	732.00	LF	340	\$90.00	\$30,600.00
22	MISCELLANEOUS METAL (BRIDGE)		LB			
23	MISC METAL (RESTRAINER - TIE ROD)		LB			
24						
25						
26						
27						
28						
29						
30	BRIDGE REMOVAL PORTION		LS	1	\$20,000.00	\$20,000.00

SUBTOTAL	\$923,562
TIME RELATED OVERHEAD	\$92,356
MOBILIZATION ( @ 10 % )	\$112,880
SUBTOTAL BRIDGE ITEMS	\$1,128,798
CONTINGENCIES (@ 25%)	\$282,200
BRIDGE TOTAL COST	\$1,410,998
COST PER SQ. FOOT	\$328.90
BRIDGE REMOVAL (CONTINGENCIES INCL.)	\$20,000
WORK BY RAILROAD OR UTILITY FORCES	
GRAND TOTAL	\$1,430,998
BUDGET ESTIMATE AS OF 12/24/08	\$1,431,000

**ROUTING**

- DES SECTION
- OFFICE OF BRIDGE DESIGN - NORTH
- OFFICE OF BRIDGE DESIGN - CENTRAL
- OFFICE OF BRIDGE DESIGN - SOUTH
- OFFICE OF BRIDGE DESIGN - WEST
- OFFICE OF BRIDGE DESIGN SOUTHERN CALIFORNIA

COMMENTS:

**Escalated Budget Estimate to Midpoint of Construction \***


Escalation Rate per Year

5.5%



Years Beyond Midpoint	Escalated Budget Est.
1	\$1,510,000
2	\$1,593,000
3	\$1,681,000

Years Beyond Midpoint	Escalated Budget Est.
4	\$1,773,000
5	\$1,871,000



\* Escalated budget estimate is provided for information only, actual construction costs may vary. Escalated budget estimates provided do not replace Departmental policy to update cost estimates annually.



Dist.	County	Route	Project No.
00	S.D.	25-390	14-74
Refer to the Standard Plans, as to Highway Design			



**NOTE:**  
 1. Match inverts of the new culvert to invert of existing culvert after strengthening.  
 2. For Reinforcement details, see "Standard Plans".



DATE OF ESTIMATE	12-15-07
BRIDGE REMOVAL	
STRUCTURE DEPTH	
LENGTH	36.000
WIDTH	38.350
AREA (SQ FT)	1350
COST/SQ FT INCLUDING MOBILIZATION & 25% CONTINGENCY	158.25
TOTAL COST	213,600

555, Dec 9A -12-24-08

ALTERNATIVE 2

DESIGNED BY MURRAY WOODS	DATE 05/26/07	<b>STRUCTURE                  DESIGN                  BRANCH</b> <b>20</b>	<b>PLANNING STUDY</b>	
DRAWN BY BOY FORTUNA	DATE 12/18/07		<b>JOSHUA WASH BRIDGE (WIDEN)</b>	
CHECKED BY J	DATE		BRIDGE NO. 54-0524	FILE NO.
APPROVED BY MURRAY W.	DATE 2/15/08		SCALE: AS SHOWN	DATE PLOTTED: 11-13-08

GENERAL PLAN ESTIMATE

x ADVANCE PLANNING ESTIMATE

Revised - December 3, 2007

RCVD BY: JTY

IN EST: 12/10/2008

OUT EST: 12/24/2008

BRIDGE: California Aqueduct Bridge (Widen) ALT 3

BR. No.: 54-0829

DISTRICT: 08

TYPE: CIP PS Box Girder

RTE: 395

CU: 08-00

CO: SBd

EA: 0F6300

PM: 6.83

LENGTH: 110.000 WIDTH: 41.500

AREA (SF)= 4565

DESIGN SECTION: 20

# OF STRUCTURES IN PROJECT : 2

EST. NO. 2

PRICES BY : WSS

COST INDEX: 388

PRICES CHECKED BY : DATE:

QUANTITIES BY : DATE:

	CONTRACT ITEMS	TYPE	UNIT	QUANTITY	PRICE	AMOUNT
1	TEMPORARY RAILING		LF			
2	STRUCTURE EXCAVATION (BRIDGE)		CY	269	\$100.00	\$26,900.00
3	STRUCTURE EXCAVATION		CY			
4	STRUCTURE BACKFILL (BRIDGE)		CY	207	\$95.00	\$19,665.00
5	PERVIOUS BACKFILL MATERIAL		CY			
6	CIDH CONCRETE PILING		LF			
7	FURNISH PILING		LF			
8	DRIVE PILES		EA			
9	FURNISH PC/PS CONCRETE GIRDERS		EA			
10	ERECT PC/PS CONCRETE GIRDERS		EA			
11	STRUCTURAL CONCRETE, BRIDGE		CY	400	\$850.00	\$340,000.00
12	STRUCTURAL CONCRETE, BRIDGE FOOTING		CY	128	\$825.00	\$105,600.00
13	STRUCTURAL CONCRETE, APPROACH SLAB	9D	CY	269	\$650.00	\$174,850.00
14	PRESTRESSING STEEL		LB	15,441	\$2.25	\$34,742.25
15	BAR REINFORCING STEEL (BRIDGE)		LB	54,959	\$1.25	\$68,698.75
16	FURNISH STRUCTURAL STEEL		LB	17,307	\$3.65	\$63,170.55
17	ERECT STRUCTURAL STEEL (INCL PAINT)		LB			
18	JOINT SEAL ASSEMBLY (MR = ) > 2"		LF			
19	JOINT SEAL (MR = ) 2" max		LF			
20	SLOPE PAVING		CY			
21	CONCRETE BARRIER	732	LF	340	\$90.00	\$30,600.00
22	MISCELLANEOUS METAL (BRIDGE)		LB			
23	MISC METAL (RESTRAINER - TIE ROD)		LB			
24						
25						
26						
27						
28						
29						
30	BRIDGE REMOVAL PORTION		LS	1	\$20,000.00	\$20,000.00

**ROUTING**

- DES SECTION
- OFFICE OF BRIDGE DESIGN - NORTH
- OFFICE OF BRIDGE DESIGN - CENTRAL
- OFFICE OF BRIDGE DESIGN - SOUTH
- OFFICE OF BRIDGE DESIGN - WEST
- OFFICE OF BRIDGE DESIGN SOUTHERN CALIFORNIA

COMMENTS:

SUBTOTAL	\$864,227
TIME RELATED OVERHEAD	\$86,423
MOBILIZATION ( @ 10 % )	\$105,628
SUBTOTAL BRIDGE ITEMS	\$1,056,277
CONTINGENCIES (@ 25%)	\$264,069
BRIDGE TOTAL COST	\$1,320,346
COST PER SQ. FOOT	\$289.23
BRIDGE REMOVAL (CONTINGENCIES INCL.)	\$20,000
WORK BY RAILROAD OR UTILITY FORCES	
GRAND TOTAL	\$1,340,346
BUDGET ESTIMATE AS OF 12/24/08	\$1,340,000

**Escalated Budget Estimate to Midpoint of Construction \***

Escalation Rate per Year

5.5%

\* Escalated budget estimate is provided for information only, actual construction costs may vary. Escalated budget estimates provided do not replace Departmental policy to update cost estimates annually.

Years Beyond Midpoint	Escalated Budget Est.
1	\$1,414,000
2	\$1,492,000
3	\$1,574,000

Years Beyond Midpoint	Escalated Budget Est.
4	\$1,661,000
5	\$1,752,000

Revised - December 3, 2007

RCVD BY: JTY

IN EST: 12/10/2008  
OUT EST: 12/22/2008

BRIDGE: Joshua Wash Bridge Alternative 3  
TYPE: Box Culvert Widening  
CU:  
EA: 08-0F6300

BR. No.: 54-0524

DISTRICT: 8.00  
RTE: 395.00  
CO: SBDO  
PM: 14.58

LENGTH: 36.000 WIDTH: 38.330 AREA (SF)= 1380

DESIGN SECTION: 20.00  
# OF STRUCTURES IN PROJECT : 1.00  
PRICES BY : WSS  
PRICES CHECKED BY :  
QUANTITIES BY :  
EST. NO. 2  
COST INDEX: 388  
DATE:

	CONTRACT ITEMS	TYPE	UNIT	QUANTITY	PRICE	AMOUNT
1	TEMPORARY RAILING		LF			
2	REMOVE CONCRETE		CY			
3	STRUCTURE EXCAVATION (BRIDGE)		CY	37	\$145.00	\$5,365.00
4	STRUCTURE EXCAVATION		CY			
5	STRUCTURE BACKFILL (BRIDGE)		CY	261	\$100.00	\$26,100.00
6	PERVIOUS BACKFILL MATERIAL		CY			
7	CIDH CONCRETE PILING		LF			
8	FURNISH PILING		LF			
9	DRIVE PILES		EA			
10	FURNISH PC/PS CONCRETE GIRDERS		EA			
11	ERECT PC/PS CONCRETE GIRDERS		EA			
12	STRUCTURAL CONCRETE, BRIDGE	class 1	CY	117	\$1,200.00	\$140,400.00
13	STRUCTURAL CONCRETE, BRIDGE FOOTING		CY			
14	STRUCTURAL CONCRETE, APPROACH SLAB		CY			
15	PRESTRESSING STEEL		LB			
16	BAR REINFORCING STEEL (BRIDGE)		LB	25,129	\$1.25	\$31,411.25
17	FURNISH STRUCTURAL STEEL		LB			
18	ERECT STRUCTURAL STEEL (INCL PAINT)		LB			
19	JOINT SEAL ASSEMBLY (MR = ) > 2"		LF			
20	JOINT SEAL (MR = ) 2" max		LF			
21	SLOPE PAVING		CY			
22	CONCRETE BARRIER		LF			
23	MISCELLANEOUS METAL (BRIDGE)		LB			
24	MISC METAL (RESTRAINER - TIE ROD)		LB			
25	DRILL AND BOND DOWEL		LF	2,599	\$50.00	\$129,950.00
26						
27						
28						
29						
30						

SUBTOTAL	\$333,226
TIME RELATED OVERHEAD	\$33,323
MOBILIZATION ( @ 10 % )	\$40,728
SUBTOTAL BRIDGE ITEMS	\$407,277
CONTINGENCIES (@ 25%)	\$101,819
BRIDGE TOTAL COST	\$509,096
COST PER SQ. FOOT	\$368.94
BRIDGE REMOVAL (CONTINGENCIES INCL.)	
WORK BY RAILROAD OR UTILITY FORCES	
GRAND TOTAL	\$509,096
BUDGET ESTIMATE AS OF 12/22/08	\$509,000

**ROUTING**

- DES SECTION
- OFFICE OF BRIDGE DESIGN - NORTH
- OFFICE OF BRIDGE DESIGN - CENTRAL
- OFFICE OF BRIDGE DESIGN - SOUTH
- OFFICE OF BRIDGE DESIGN - WEST
- OFFICE OF BRIDGE DESIGN SOUTHERN CALIFORNIA

COMMENTS:

**Escalated Budget Estimate to Midpoint of Construction \***

Escalation Rate per Year

5.5%


\* Escalated budget estimate is provided for information only, actual construction costs may vary. Escalated budget estimates provided do not replace Departmental policy to update cost estimates annually.

Years Beyond Midpoint	Escalated Budget Est.
1	\$537,000
2	\$567,000
3	\$598,000

Years Beyond Midpoint	Escalated Budget Est.
4	\$631,000
5	\$666,000


DATE	BY	CHKD	APP'D
01/13/00	10/1/99	E. S. J.	

PROJECT: CALIFORNIA AQUEDUCT BRIDGE  
SHEET NO. 20



**ELEVATION**  
1"=10'

**TYPICAL SECTION**  
1/2"=1'



**PLAN**  
1"=10'

- Existing Structure
- New Structure
- Bridge Removal Portion
- Direction of Traffic

DATE OF ESTIMATE	12-5-07
BRIDGE REMOVAL	
STRUCTURE LENGTH	
LENGTH	4,200
WIDTH	4,500
AREA SQ. FT.	18,900
COST (\$/SQ. FT. ESTIM.)	
COST ESTIMATION FOR CONTINGENCY	102,495
TOTAL COST	1,937,505

**2,184,000 FA**  
12-24-08

- NOTES:**
1. Remove Type 21 Bridge Paving and Overhang
  2. Bridge Paving Type 711
  3. Reconstruct Channel Concrete Slope Paving
  4. Structure Approach Type (A30)

**DESIGN ASSUMPTIONS:**  
1. Existing bridge available freeboard = 1.3ft  
After widening the freeboard ramp is the same

DESIGNED BY	DATE
DRAWN BY	CAT
CHECKED BY	CAT
APPROVED BY	DATE



**STRUCTURE DESIGN BRANCH**  
**20**

<b>ALTERNATIVE - 3</b>	
<b>PLANNING STUDY</b>	
<b>CALIFORNIA AQUEDUCT BRIDGE (WIDEN)</b>	
DESIGNED BY	DATE
CHECKED BY	DATE

THIS DRAWING IS THE PROPERTY OF THE STATE OF CALIFORNIA. IT IS LOANED TO YOU BY THE DIVISION OF STRUCTURES. IT IS NOT TO BE REPRODUCED OR TRANSMITTED IN ANY FORM OR BY ANY MEANS, ELECTRONIC OR MECHANICAL, INCLUDING PHOTOCOPYING, RECORDING, OR BY ANY INFORMATION STORAGE AND RETRIEVAL SYSTEM.




NO.	COUNTY	ROUTE	POST MILE
05	SB	US-395	14.55
Proj. No. 05-000004-01 05-000004-01-01			




**NOTE:**

- Match invert of the new culvert to invert of existing culvert after strengthening.
- For Reinforcement details, see "Standard Plans".



Strengthen top and bottom slabs with minimum 4" concrete and 4x4 - W4X4 weld wire fabric (typ).

**PLAN**  
1" = 20' 0"



DATE OF ESTIMATE: 2-15-07 - 12-24-08

BRIDGE REMOVAL = \_\_\_\_\_

STRUCTURE DEPTH = \_\_\_\_\_

LENGTH = 30.000

WIDTH = 48.330

AREA - SQ FT = 1380

COST/ SQ FT INCLUDING MOBILIZATION & 75% CONTINGENCY = 364.15

TOTAL COST = 509,000

**SECTION A-A**  
1" = 5'-0"

**ALTERNATIVE 3**

DESIGNED BY: Mohamed Mustosir	DATE: 01/26/07	<b>STRUCTURE DESIGN BRANCH</b> <b>20</b>	<b>PLANNING STUDY</b>	
DRAWN BY: Kiyonobu	DATE: 12/13/05		<b>JOSHUA WASH BRIDGE (WIDEN)</b>	
CHECKED BY:	DATE:		BRIDGE NO. 05-0004	CU 08
APPROVED: [Signature]	DATE: 12/13/05		SCALE: As Shown	24 OF 6300

08-SBd-395 PM R4.0/19.3  
08-236-0F6300  
Widen Highway and  
Improve Intersections  
HE-13 (STIP)  
20.20.025.700

# **ATTACHMENT D**

## **Cost Estimate**

**PROJECT COST ESTIMATE SUMMARY  
ALTERNATIVE 2**

<b>Type of Estimate :</b>	Project Report	<b>08-SBd-395 PM R4.0/19.3 Widen Highway to 4-Lanes and Median Left Turn Channelization 08-236-EA 0F6300</b>
<b>Program Code:</b>	HE-13	
<b>PIP Number : 2659 &amp; 2660</b>		<b>Alternative 2</b>

**PROJECT DESCRIPTION :** US-395 Improvements

**LIMITS :** From 0.16 mi North of I-15 at PM R4.06.41 in the City of Hesperia to PM 19.3, approximately 1.80 mi South of Desert Flower Road in the City of Adelanto in San Bernardino County.

**PROPOSED IMPROVEMENTS :** Improve safety and operational efficiency of the facility by increasing capacity and by providing a dedicated two way left turn lane.

**Alternative 2 :** Widen the highway from 2 to 4 lanes, a left-turn channelization with rumble strips in the median, and add standard shoulders.

<b>ROADWAY ITEMS</b>	\$	96,968,000
<b>STRUCTURE ITEMS</b>	\$	1,966,000
<b>SUBTOTAL CONSTRUCTION</b>	\$	98,934,000
<b>R/W &amp; UTILITY RELOCATION</b>	\$	10,280,813
<b>TOTAL PROJECT CAPITAL OUTLAY COST</b>	\$	<b>109,214,813</b>

**PROJECT COST ESTIMATE SUMMARY**

**08-SBd-395 PM R4.0/19.3  
Widen Highway to 4-Lanes and  
Median Left Turn Channelization  
08-236-EA 0F6300  
Alternative 2**

**I. ROADWAY ITEMS**

	<b>QUANTITY</b>	<b>UNIT</b>	<b>UNIT PRICE</b>	<b>UNIT COST</b>	<b>SECTION COST</b>
<b>SECTION 1. Earthwork</b>					
Roadway Excavation	200,300	CY	\$15	\$3,004,500	
Imported Borrow	8,000	CY	\$60	\$480,000	
Clearing & Grubbing	1	LS	\$400,000	\$400,000	
Develop Water Supply	1	LS	\$150,000	\$150,000	
					<b><u>Total Earthwork Section</u></b>
					<b>4,034,500</b>
<b>SECTION 2. Structural Section</b>					
Minor Concrete	0	CY	\$100	\$0	
HMA Hot Mix Asphalt (Type HS)	225,450	TON	\$90	\$20,290,500	
HMA Hot Mix Asphalt (Type A)	78,640	TON	\$110	\$8,650,400	
Aggregate Base (Class 2)	247,327	CY	\$60	\$14,839,620	
Cold Plane (0.50' Max)	229,260	SQY	\$10	\$2,292,600	
					<b><u>Total Structural Section</u></b>
					<b>\$46,073,120</b>
<b>SECTION 3. Drainage</b>					
Storm Drains	1	LS	\$0	\$0	
Project Drainage (x-drains, oversize, etc)	1	LS	\$1,500,000	\$1,500,000	
					<b><u>Total Drainage Section</u></b>
					<b>\$1,500,000</b>

**PROJECT COST ESTIMATE SUMMARY**

08-SBd-395 PM R4.0/19.3  
 Widen Highway to 4-Lanes and  
 Median Left Turn Channelization  
 08-236-EA 0F6300  
 Alternative 2

	QUANTITY	UNIT	UNIT PRICE	UNIT COST	SECTION COST
SECTION 4. Specialty Items					
Desert Tortoise Exclusion Fencing	161,417	FT	\$12	\$1,937,004	
Environment Mitigation	1	LS	\$3,842,730	\$3,842,730	
Sound Walls	1	LS	\$1,134,600	\$1,134,600	
Vine Planting	1	LS	\$391,000	\$391,000	
Wall Aesthetics	1	LS	\$828,300	\$828,300	
SWPPP	1	LS	\$1,500,000	\$1,500,000	
Erosion Control	67	Acres	\$4,500	\$301,500	
			<b>Total Specialty Items</b>	<b>\$9,935,134</b>	
SECTION 5. Traffic Items					
Traffic Signals	7	EA	\$280,000	\$1,960,000	
Traffic Signals Modification	1	LS	\$620,000	\$620,000	
Construction Area Signs	1	LS	\$10,000	\$10,000	
Traffic Control System	1	LS	\$300,000	\$300,000	
Temporary Traffic Stripe (Paint)	501200	LF	\$0.75	\$375,900	
Temporary Pavement Marker	12600	EA	\$5	\$63,000	
Portable Changeable Message Signs	2	EA	\$7,000	\$14,000	
Temporary Railing (Type K)	138000	LF	\$30	\$4,140,000	
Remove Yellow Thermoplastic Traffic Stripe	89000	LF	\$2	\$178,000	
Remove Thermoplastic Traffic Stripe	153300	LF	\$0.70	\$107,310	
Remove Thermoplastic Pavement Marking	2000	SQFT	\$2	\$4,000	
Remove Pavement Marker	5000	EA	\$2	\$10,000	
Remove Channelizers	25	EA	\$20	\$500	
Relocate Roadside Sign-One Post	131	EA	\$350	\$45,850	
Relocate Roadside Sign-Two Post	58	EA	\$550	\$31,900	
Lead Compliance Plan	1	LS	\$7,000	\$7,000	
Thermoplastic Pavement Marking	16000	SQFT	\$4.30	\$68,800	
Thermoplastic Traffic Stripe (Sprayable)	471000	LF	\$0.30	\$141,300	
Pavement Marker (Non-Reflective)	12480	EA	\$2.50	\$31,200	
Pavement Marker (Retroreflective)	11700	EA	\$4.50	\$52,650	
Environmental Lead Testing and Disposal	1	LS	\$7,000	\$7,000	
Traffic Management Plan	1	LS	\$1,267,620	\$1,267,620	
Maintain Traffic and Flagging	1	LS	\$60,000	\$60,000	
			<b>Total Traffic Items</b>	<b>\$9,496,030</b>	

<b>SUBTOTAL SECTIONS 1-5</b>	<b>71,038,784.00</b>
------------------------------	----------------------

**PROJECT COST ESTIMATE SUMMARY**

**08-SBd-395 PM R4.0/19.3  
Widen Highway to 4-Lanes and  
Median Left Turn Channelization  
08-236-EA 0F6300  
Alternative 2**

					<b>UNIT COST</b>	<b>SECTION COST</b>
SECTION 6. Minor Items						
Subtotal Sections 1-5	\$71,038,784	x		5%	\$3,551,939	
						<b>TOTAL MINOR ITEMS</b>
						\$3,551,939
SECTION 7. Roadway Mobilization						
Subtotal Sections 1-5	\$71,038,784					
Minor Items	\$3,551,939					
	<b>SUM</b>		x	10%	\$7,459,072	
						<b>TOTAL ROADWAY MOBILIZATION</b>
						\$7,459,072
SECTION 8. Roadway Additions						
Supplemental						
Subtotal Sections 1-5	\$71,038,784					
Minor Items	\$3,551,939					
	<b>SUM</b>		x	5%	\$3,729,536	
Contingencies						
Subtotal Sections 1-5	\$71,038,784					
Minor Items	\$3,551,939					
	<b>SUM</b>		x	15%	\$11,188,608	
						<b>TOTAL ROADWAY ADDITIONALS</b>
						\$14,918,145
						<b>TOTAL ROADWAY ITEMS</b>
						\$96,967,940
						<b>(Total of Sections 1-8)</b>
						<b>ROUND OFF TO :</b>
						<b>\$96,968,000</b>

Estimate Prepared By : J.C. Alvarez

Phone # 383-4931

Date: 05/28/2009

Estimate Checked By : Refaat Elsherif

Phone # 383-6891

Date: 05/29/2009

**PROJECT COST ESTIMATE SUMMARY**

08-SBd-395 PM R4.0/19.3  
Widen Highway to 4-Lanes and  
Median Left Turn Channelization  
08-236-EA 0F6300  
**Alternative 2**

**II. STRUCTURES ITEMS**

	No.1	No.2		
Bridge Name	California Aqueduct Br No. 54-829	Joshua Wash Br No 54-0524		
Structure Type				
Width in feet-out to out	39	39		
Span Length in feet	110	35		
Total Area in square feet	4290	1380		
Footing Type (pile/spread)	Spread	Spread		
Cost Per square feet (INCL. 10% MOBILIZATION AND 25% CONTINGENCY)	\$329	\$388		
<b>SUBTOTAL FOR STRUCTURE</b>	<b>\$1,430,998</b>	<b>\$535,452</b>		
Related Ramps	\$0	\$0		
Railroad Related Cost	\$0	\$0		
Subtotal	\$1,430,998	\$535,452		
Remove old Bridge	\$0	\$0		
<b>TOTAL COST FOR STRUCTURE</b>	<b>\$1,431,000</b>	<b>\$535,000</b>		
	<b>TOTAL STRUCTURES ITEMS</b>		<b>\$1,966,000</b>	

**COMMENTS:**

<b>ROUND OFF TO :</b>	<b>\$1,966,000</b>
-----------------------	--------------------

Estimate Prepared By : Howard NG (Bridge Design)

Phone # (909) 598-6367

Date: 12/22/2008

**PROJECT COST ESTIMATE SUMMARY**

**08-SBd-395 PM R4.0/19.3  
Widen Highway to 4-Lanes and  
Median Left Turn Channelization  
08-236-EA 0F6300  
Alternative 2**

**III. RIGHT OF WAY**

Right of Way estimates should consider the probable highest and best use and type and intent of improvements at the time of acquisition. Assume acquisition including utility relocation occurs at the right of way certification milestone as shown in the Funding and Scheduling Section of the PSR. For further guidance see Chapter I, Caltrans, Right of Way Procedural Handbook.

	Current Value	Escalated Rate	Escalated Value
Acquisition, including Excess Lands, Damages and Goodwill	\$4,191,151	5%	\$5,094,370
Utility Relocation (State share)	\$4,545,559	5%	\$5,525,155
Clearance/Demolition	\$0	0%	\$0
RAP	\$0	0%	\$0
Title and Escrow Fees	\$220,500	5%	\$268,019
Condemnation Costs	\$1,323,603	5%	\$1,608,848
<b>TOTAL RIGHT OF WAY (CURRENT VALUE) :</b>	<b>\$10,280,813</b>		
<b>TOTAL ESCALATED VALUE :</b>			<b>\$12,496,393</b>

**ROUND OFF TO : \$10,280,813**

**Estimate Prepared By : Michael S. Romo**

**Phone # 383-4582**

**Date: 04/28/2009**



**PROJECT COST ESTIMATE SUMMARY  
ALTERNATIVE 3**

**Type of Estimate :** Project Report **08-SBd-395 PM R4.0/19.3  
Widen Highway to 4-Lanes and  
Median Left Turn Channelization  
08-236-EA 0F6300  
Alternative 3**

**Program Code:** HE-13

**PIP Number : 2659 & 2660**


**PROJECT DESCRIPTION :** US-395 Improvements

**LIMITS :** From 0.16 mi North of I-15 at PM R4.06.41 in the City of Hesperia to PM 19.3, approximately 1.80 mi South of Desert Flower Road in the City of Adelanto in San Bernardino County.

**PROPOSED IMPROVEMENTS :** Improve safety and operational efficiency of the facility by increasing capacity and by providing a dedicated two way left turn lane.

**Alternative 3 :** Widen the highway from 2 to 4 lanes, a left-turn channelization with rumble strips in the median, add standard shoulders and realign the centerline to minimize right of way impact.

<b>ROADWAY ITEMS</b>	<b>\$ 109,780,000</b>
<b>STRUCTURE ITEMS</b>	<b>\$ 1,849,000</b>
<b>SUBTOTAL CONSTRUCTION</b>	<b>\$ 111,629,000</b>
<b>R/W &amp; UTILITY RELOCATION</b>	<b>\$ 11,236,628</b>
<b>TOTAL PROJECT CAPITAL OUTLAY COST</b>	<b>\$ 122,865,628</b>



**PRELIMINARY PROJECT COST ESTIMATE SUMMARY**

**08-SBd-395 PM R4.0/19.3  
Widen Highway to 4-Lanes and  
Median Left Turn Channelization  
08-236-EA 0F6300  
Alternative 3**

<b>I. ROADWAY ITEMS</b>	<b>QUANTITY</b>	<b>UNIT</b>	<b>UNIT PRICE</b>	<b>UNIT COST</b>	<b>SECTION COST</b>
<b>SECTION 1. Earthwork</b>					
Roadway Excavation	400,150	CY	\$15	\$6,002,250	
Imported Borrow	-	CY	\$10	\$0	
Clearing & Grubbing	1	LS	\$400,000	\$400,000	
Develop Water Supply	1	LS	\$150,000	\$150,000	
					<b><u>Total Earthwork Section</u></b>
					<b>6,402,250</b>
<b>SECTION 2. Structural Section</b>					
Minor Concrete	0	CY	\$100	\$0	
HMA Hot Mix Asphalt (Type HS)	251,100	TON	\$90	\$22,599,000	
HMA Hot Mix Asphalt (Type A)	95,100	TON	\$110	\$10,461,000	
Aggregate Base (Class 2)	275,500	CY	\$60	\$16,530,000	
Cold Plane (0.50' Max)	277,200	SQY	\$10	\$2,772,000	
					<b><u>Total Structural Section</u></b>
					<b>\$52,362,000</b>
<b>SECTION 3. Drainage</b>					
Storm Drains	1	LS	\$0	\$0	
Project Drainage (x-drains, oversize, etc)	1	LS	\$1,500,000	\$1,500,000	
					<b><u>Total Drainage Section</u></b>
					<b>\$1,500,000</b>

**PRELIMINARY PROJECT COST ESTIMATE SUMMARY**

08-SBd-395 PM R4.0/19.3  
 Widen Highway to 4-Lanes and  
 Median Left Turn Channelization  
 08-236-EA 0F6300  
 Alternative 3

	QUANTITY	UNIT	UNIT PRICE	UNIT COST	SECTION COST
SECTION 4. Specialty Items					
Desert Tortoise Exclusion Fencing	161,417	FT	\$12	\$1,937,004	
Environment Mitigation	1	LS	\$3,705,375	\$3,705,375	
Sound Wall	1	LS	\$1,134,600	\$1,134,600	
Vine Planting	1	LS	\$424,000	\$424,000	
Wall Aesthetics	1	LS	\$861,300	\$861,300	
SWPPP	1	LS	\$1,500,000	\$1,500,000	
Erosion Control	78	Acres	\$4,500	\$351,000	
			<b>Total Specialty Items</b>		<b>\$9,913,279</b>
SECTION 5. Traffic Items					
Traffic Signals	7	EA	\$280,000	\$1,960,000	
Traffic Signals Modification	1	LS	\$620,000	\$620,000	
Construction Area Signs	1	LS	\$10,000	\$10,000	
Traffic Control System	1	LS	\$300,000	\$300,000	
Temporary Traffic Stripe (Paint)	600000	LF	\$0.75	\$450,000	
Temporary Pavement Marker	15500	EA	\$5	\$77,500	
Portable Changeable Message Signs	2	EA	\$7,000	\$14,000	
Temporary Railing (Type K)	160000	LF	\$30	\$4,800,000	
Remove Yellow Thermoplastic Traffic Stripe	89000	LF	\$2	\$178,000	
Remove Thermoplastic Traffic Stripe	157300	LF	\$0.70	\$110,110	
Remove Thermoplastic Pavement Marking	2000	SQFT	\$2	\$4,000	
Remove Pavement Marker	5000	EA	\$2	\$10,000	
Remove Channelizers	25	EA	\$20	\$500	
Relocate Roadside Sign-One Post	131	EA	\$350	\$45,850	
Relocate Roadside Sign-Two Post	58	EA	\$550	\$31,900	
Lead Compliance Plan	1	LS	\$7,000	\$7,000	
Thermoplastic Pavement Marking	16000	SQFT	\$4.30	\$68,800	
Thermoplastic Traffic Stripe (Sprayable)	471000	LF	\$0.30	\$141,300	
Pavement Marker (Non-Reflective)	12480	EA	\$2.50	\$31,200	
Pavement Marker (Retroreflective)	11700	EA	\$4.50	\$52,650	
Environmental Lead Testing and Disposal	1	LS	\$7,000	\$7,000	
Traffic Management Plan	1	LS	\$1,267,620	\$1,267,620	
Maintain Traffic and Flagging	1	LS	\$60,000	\$60,000	
			<b>Total Traffic Items</b>		<b>\$10,247,430</b>
<b>SUBTOTAL SECTIONS 1-5</b>					<b>\$80,424,959</b>

**PRELIMINARY PROJECT COST ESTIMATE SUMMARY**

08-SBd-395 PM R4.0/19.3  
 Widen Highway to 4-Lanes and  
 Median Left Turn Channelization  
 08-236-EA 0F6300  
 Alternative 3

					<b>UNIT COST</b>	<b>SECTION COST</b>
SECTION 6. Minor Items						
Subtotal Sections 1-5	\$80,424,959	x	5%		\$4,021,248	
						<b>TOTAL MINOR ITEMS</b>
						\$4,021,248
SECTION 7. Roadway Mobilization						
Subtotal Sections 1-5	\$80,424,959					
Minor Items	\$4,021,248					
	<b>SUM</b>	x	10%		\$8,444,621	
						<b>TOTAL ROADWAY MOBILIZATION</b>
						\$8,444,621
SECTION 8. Roadway Additions						
Supplemental						
Subtotal Sections 1-5	\$80,424,959					
Minor Items	\$4,021,248					
	<b>SUM</b>	x	5%		\$4,222,310	
Contingencies						
Subtotal Sections 1-5	\$80,424,959					
Minor Items	\$4,021,248					
	<b>SUM</b>	x	15%		\$12,666,931	
						<b>TOTAL ROADWAY ADDITIONALS</b>
						\$16,889,241
						<b>TOTAL ROADWAY ITEMS</b>
						\$109,780,069
						<b>(Total of Sections 1-8)</b>
						<b>ROUND OFF TO :</b>
						<b>\$109,780,000</b>

Estimate Prepared By : J.C. Alvarez

Phone # 383-4931

Date: 05/28/2009

Estimate Checked By : Refaat Elsherif

Phone # 383-6891

Date: 05/29/2009

**PRELIMINARY PROJECT COST ESTIMATE SUMMARY**

**08-SBd-395 PM R4.0/19.3  
Widen Highway to 4-Lanes and  
Median Left Turn Channelization  
08-236-EA 0F6300  
Alternative 3**

**II. STRUCTURES ITEMS**

	No.1	No.2		
Bridge Name	California Aqueduct Br No. 54-829	Joshua Wash Br No 54-0524		
Structure Type				
Width in feet-out to out	41.5	38.33		
Span Length in feet	110	36		
Total Area in square feet	4565	1380		
Footing Type (pile/spread)	Spread	Spread		
Cost Per square feet (INCL. 10% MOBILIZATION AND 25% CONTINGENCY)	\$289	\$369		
<b>SUBTOTAL FOR STRUCTURE</b>	\$1,340,346	\$509,096		
Related Ramps	\$0	\$0		
Railroad Related Cost	\$0	\$0		
Subtotal	\$1,340,346	\$509,096		
Remove old Bridge	\$0	\$0		
<b>TOTAL COST FOR STRUCTURE</b>	\$1,340,000	\$509,000		
	<b>TOTAL STRUCTURES ITEMS</b>		<b>\$1,849,000</b>	

**COMMENTS:**

<b>ROUND OFF TO :</b>	<b>\$1,849,000</b>
-----------------------	--------------------

**Estimate Prepared By :Howard NG (Bridge Design) Phone # (909) 598-6367 Date: 12/22/2008**

!::

**PRELIMINARY PROJECT COST ESTIMATE SUMMARY**

**08-SBd-395 PM R4.0/19.3  
Widen Highway to 4-Lanes and  
Median Left Turn Channelization  
08-236-EA 0F6300  
Alternative 3**

**III. RIGHT OF WAY**

Right of Way estimates should consider the probable highest and best use and type and intent of improvements at the time of acquisition. Assume acquisition including utility relocation occurs at the right of way certification milestone as shown in the Funding and Scheduling Section of the PSR. For further guidance see Chapter I, Caltrans, Right of Way Procedural Handbook.

	Current Value	Escalated Rate	Escalated Value
Acquisition, including Excess Lands, Damages and Goodwill	\$3,984,003	5%	\$4,842,581
Utility Relocation (State share)	\$5,776,624	5%	\$7,021,523
Clearance/Demolition	\$0	0%	\$0
RAP	\$0	0%	\$0
Title and Escrow Fees	\$216,000	5%	\$262,549
Condemnation Costs	\$1,260,001	5%	\$1,531,539
<b>TOTAL RIGHT OF WAY (CURRENT VALUE) :</b>	<b>\$11,236,628</b>		
<b>TOTAL ESCALATED VALUE :</b>			<b>\$13,658,192</b>

**ROUND OFF TO : \$11,236,628**

**Estimate Prepared By : Michael S. Romo**

**Phone # 383-4582**

**Date: 04/28/2009**

08-SBd-395 PM R4.0/19.3  
08-236-0F6300  
Widen Highway and  
Improve Intersections  
HE-13 (STIP)  
20.20.025.700

# **ATTACHMENT E**

## **Initial Site Assessment (ISA)**

# INITIAL SITE ASSESSMENT (ISA) CHECKLIST

DATE: 6/1/09

**PROJECT INFORMATION**

District 08 County SBd Route 395 Post Mile R4.0/19.36 E.A. 0F630

Description of Work: Widen the highway from two to four lanes, left-turn channelization with rumble strips in the median.

Project Engineer Juan Alvarez Telephone 909-383-4931  
 Environmental Coordinator Debbie Hudson Telephone 909-383-1002

DATE ISA NEEDED \_\_\_\_\_  
 \_\_\_\_\_

Attach the project location map and an aerial photo to this checklist to show the location of proposed R/W and all known and/or potential hazardous waste sites.

1. Project Features: New R/W? **YES** Excavation? **YES** Railroad Involvement? **NO**  
 Structure Demolition/Modification? **YES** Utility Relocation? **TBD**
2. Project Setting: Rural - **YES** Urban - \_\_\_\_\_  
 Current Land Uses: existing state highway facility  
 Adjacent Land Uses: commercial, industrial, residential  
 (Industrial light industry, commercial, agriculture, residential, other)
3. Check Federal, State, and local environmental and health regulatory agency records as necessary to see if any known hazardous waste site is in or near the project area. If a known site is identified, show its location on the attached map and attach additional sheets as needed to provide all information available pertinent to the proposed project. IS PROJECT
4. AFFECTING SITES LISTED ON CORTESE LIST? **NO** IF YES, DESCRIBE SITE: \_\_\_\_\_
5. Conduct Field Inspection Initial Site Assessment (Phase 1) by Stantec Date 6/24/08

Storage Structures/Pipelines:	Contamination: (spills, leaks, illegal dumping, etc)	Hazardous Materials: (asbestos, lead, etc.)
UST's <u>NO</u>	Surface Staining <u>NO</u>	Buildings <u>NO</u>
Surface tanks <u>NO</u>	Oil Sheen <u>NO</u>	Sprayed-on <u>NO</u>
Sumps <u>NO</u> Ponds <u>NO</u>	Odors <u>NO</u>	Fireproofing <u>NO</u>
Drums <u>NO</u> Basins <u>NO</u>	Vegetation damage <u>NO</u>	Pipe Wrap <u>NO</u>
Transformers <u>NO</u>	Other _____	Friable Tile <u>NO</u>
Landfill <u>NO</u>		Acoustical <u>NO</u>
Other _____		Plaster _____
		Serpentine <u>NO</u>
		Paint <u>YES</u> Other _____

Other comments and/or observations: Initial Site Assessment Report dated June 25, 2008 provides recommendations for preliminary site investigations for two parcels. Once the permits to enter are received we will proceed with the investigations. If contamination is detected at either parcels, the owners will be asked to cleanup the site or the cost of cleanup may be deducted from the appraisal. The final report will be provided to the project engineer. Include special provisions for aerially deposited lead, treated wood waste and remove yellow thermoplastic traffic stripe and pavement marking if needed.

**ISA DETERMINATION:**

Does the project have potential hazardous waste involvement? LOW RISK  
 If there is known or potential hazardous waste involvement, is additional ISA work needed before task orders can be prepared for the Preliminary Site Investigation? **NO** If yes, explain, and give estimate of additional time required:

ISA CONDUCTED BY: Rosanna Roa DATE: 6/1/09  
 ROSANNA ROA, ENV. ENG. MS-824  
 DISTRICT 08 HAZARDOUS WASTE COORDINATOR  
 (909) 383-5917




# **ATTACHMENT F**

## **Initial Study with Mitigated Negative Declaration/ NEPA Section 6005 CE**

# **US 395 Widening of Existing US 395 Project**

SAN BERNARDINO COUNTY, CALIFORNIA  
DISTRICT 08-SBd-US 395 PM R4.0/19.3  
EA 08-0F6300

## **Initial Study with Mitigated Negative Declaration**



**Prepared by the  
State of California Department of Transportation**



**December 2009**

SCH # 2009081105  
08-SBd-395-  
PM R4.0/19.3  
08-0F6300


WIDEN UNITED STATES 395 (US 395) FROM TWO TO FOUR LANES IN EACH  
DIRECTION AND INSTALL LEFT TURN CHANNELIZATION FROM INTERSTATE 15  
(I-15) POSTMILE 4.0 TO 1.8 MILES SOUTH OF DESERT FLOWER ROAD, POST  
MILE 19.3, IN THE COUNTY OF SAN BERNARDINO

### **INITIAL STUDY with Mitigated Negative Declaration**

Submitted Pursuant to: (State) Division 13, California Public Resources Code

THE STATE OF CALIFORNIA  
Department of Transportation

12/30/09  
Date of Approval

  
David Bricker  
Deputy District Director  
District 8 Division of Environmental Planning  
California Department of Transportation

# Mitigated Negative Declaration

Pursuant to: Division 13, Public Resources Code

## Project Description

The California Department of Transportation plans to widen a portion of United States Highway 395 (US 395) located in the County of San Bernardino, from two to four lanes in each direction and install left turn channelization from Interstate 15 (I-15), post mile 4.0, to 1.8 miles south of Desert Flower Rd, post mile 19.3.

## Determination

The Department has prepared an Initial Study for this project, and following public review, has determined from this study that the proposed project would not have a significant effect on the environment for the following reasons:

The proposed project would have no effect on agricultural resources, cultural resources, mineral resources, population and housing, public services, or recreation facilities.

In addition, the proposed project would have no significant effect on: aesthetics, air quality, geology and soils, hydrology and water quality.

The proposed project would have no significantly adverse effect on biological resources and Noise because the following mitigation measures would reduce potential effects to insignificance

- 16.51 acres of disturbed habitat will be mitigated at a 3:1 ratio for project impacts to desert tortoise and Mohave ground squirrel habitat along the project site. Mitigation agreements are expected to be at a ratio between 1:1 and 3:1 depending on the quality of the habitat.
- Construction of two soundwalls is planned to address noise impacts within the project area.

  
\_\_\_\_\_  
David Bricker  
Deputy District Director  
District 8 Division of Environmental Planning  
California Department of Transportation

12/30/09  
Date

**CATEGORICAL EXEMPTION/ CATEGORICAL EXCLUSION DETERMINATION FORM**

**08—SBd--395**

**R4.0 / 19.3**

**08—0F6300**

**NA**

Dist.-Co.-Rte. (or Local Agency)

P./M/P.M.

E.A. (State project)

Federal-Aid Project No. (Local project)/ Proj. No.

**PROJECT DESCRIPTION:**

(Briefly describe project, purpose, location, limits, right-of-way requirements, and activities involved.)

The California Department of Transportation (Department), plans to widen a portion of United States Highway 395 (US 395) from two to four lanes in each direction and install left turn channelization, from Interstate 15 (I-15) (post mile R4.0), to 1.8 miles south of Desert Flower Rd. (post mile 19.3). The project is expected to require acquisition of "sliver" portions of right of way, however no residential or business relocations are expected. The project is located in the County of San Bernardino. This project was initiated at the request of the Cities of Hesperia, Victorville, and Adelanto.

**CEQA COMPLIANCE** (for State Projects only)

Based on an examination of this proposal, supporting information, and the following statements (See 14 CCR 15300 et seq.):

- If this project falls within exempt class 3, 4, 5, 6 or 11, it does not impact an environmental resource of hazardous or critical concern where designated, precisely mapped and officially adopted pursuant to law.
- There will not be a significant cumulative effect by this project and successive projects of the same type in the same place, over time.
- There is not a reasonable possibility that the project will have a significant effect on the environment due to unusual circumstances.
- This project does not damage a scenic resource within an officially designated state scenic highway.
- This project is not located on a site included on any list compiled pursuant to Govt. Code § 65962.5 ("Cortese List").
- This project does not cause a substantial adverse change in the significance of a historical resource.

**CALTRANS CEQA DETERMINATION** (Check one)

**Exempt by Statute.** (PRC 21080[b]; 14 CCR 15260 et seq.)

Based on an examination of this proposal, supporting information, and the above statements, the project is:

**Categorically Exempt. Class** \_\_\_\_\_. (PRC 21084; 14 CCR 15300 et seq.)

**Categorically Exempt. General Rule exemption.** [This project does not fall within an exempt class, but it can be seen with certainty that there is no possibility that the activity may have a significant effect on the environment (CCR 15061[b][3])]

**NA**

**NA**

Print Name: Environmental Branch Chief

Print Name: Project Manager/DLA Engineer

Signature

Date

Signature

Date

**NEPA COMPLIANCE**

In accordance with 23 CFR 771.117, and based on an examination of this proposal and supporting information, the State has determined that this project:

- does not individually or cumulatively have a significant impact on the environment as defined by NEPA and is excluded from the requirements to prepare an Environmental Assessment (EA) or Environmental Impact Statement (EIS), and
- has considered unusual circumstances pursuant to 23 CFR 771.117(b) (<http://www.fhwa.dot.gov/hep/23cfr771.htm> - sec.771.117).

In non-attainment or maintenance areas for Federal air quality standards, the project is either exempt from all conformity requirements, or conformity analysis has been completed pursuant to 42 USC 7506(c) and 40 CFR 93.

**CALTRANS NEPA DETERMINATION** (Check one)

**Section 6004:** The State has been assigned, and hereby certifies that it has carried out, the responsibility to make this determination pursuant to Chapter 3 of Title 23, United States Code, Section 326 and a Memorandum of Understanding (MOU) dated June 7, 2007, executed between the FHWA and the State. The State has determined that the project is a Categorical Exclusion under:

- 23 CFR 771.117(c): activity (c) ()
- 23 CFR 771.117(d): activity (d) ()
- Activity listed in the MOU between FHWA and the State

**Section 6005:** Based on an examination of this proposal and supporting information, the State has determined that the project is a CE under Section 6005 of 23 U.S.C. 327.

James Shankel


Jamal Elsaleh

Print Name: Environmental Branch Chief

Print Name: Project Manager/DLA Engineer



12-31-2009



12/31/09

Signature

Date

Signature

Date

Briefly list environmental commitments on continuation sheet. Reference additional information, as appropriate (e.g., air quality studies, documentation of conformity exemption, FHWA conformity determination if Section 6005 project; §106 commitments; §4(f); §7 results; Wetlands Finding; Floodplain Finding; additional studies; and design conditions). **Revised September 15, 2008**

# **ATTACHMENT G**

## **Right of Way Data Sheet**

Date: April 28, 2009

08-SBd – 395- PM R 4.0 / 19.36  
Project Description: Widen from 2 Lanes to 4  
Lanes & Median Left-Turn Channelization with  
Rumble Strips  
**ALTERNATIVE 2 UPDATE**  
**EA: 0F6300**

To: BEN AMIRI

From: MICHAEL S. ROMO  
R/W Project Delivery

Subject: Current Estimated Right of Way Costs

We have completed an updated ROW data sheet for estimate of the right of way costs for the above-referenced project based on maps we received from you March 3, 2009 and the following assumptions and limiting conditions:

- 1. The mapping did not provide sufficient detail to determine the limits of the right of way required.
- 2. The transportation facilities have not been sufficiently designed so that the estimator could determine the damages to any of the remainder parcels affected by the project.
- 3. Additional right of way requirements are anticipated, but are not defined due to the preliminary nature of the early design requirements.
- 4. We have determined there are no right of way functional involvement in the proposed project at this time, as designed.

Right of Way Lead Time will require a minimum of 23 months after we begin receiving final right of way requirements (PYPSCAN node No. 224), necessary environmental clearance has been obtained, and freeway agreements have been approved. From the date of receipt of final right of way requirements (PYPSCAN node No. 225), we will require a minimum of 12 months prior to the date of certification of the project. Either of these actions may reflect adversely on the District's other programs or our public image generally.

\*TOTAL PROJECT HOURS FOR R/W: 57,260

\*NOTE: THESE HOURS ARE PRELIMINARY BASED ON THE INFORMATION PROVIDED WITH THE DATA SHEET REQUEST. HOURS ARE SUBJECT TO CHANGE AS NEW INFORMATION IS PROVIDED.

Attachments:

- Right of Way Data Sheet
- Utility Information Sheet
- Railroad Information Sheet

EVNT RW	4/28
COST RW1 - 6	4/28
TEXT TI	4/28
SCAN	4/28
CLASS	_____
AGRE	_____
TPRC	_____

Date: April 28, 2009

08-SBd -- 395- PM R 4.0 / 19.36  
 Project Description: Widen from 2 Lanes to 4  
 Lanes & Median Left-Turn Channelization with  
 Rumble Strips  
**ALTERNATIVE 2 UPDATE**  
**EA: 0F6300**

**Subject: Updated Request for ROW data sheet.**

1. Right of Way Cost Estimate:

	Value
A. Acquisition, including Excess Lands Damages, Goodwill, Major Rehabilitation, and Environmental Permits to Enter	\$ 4,191,151.00
B. Acquisition of Offsite Mitigation. <b>None Requested.</b>	\$ 0.00
C. Utility Relocation (State share)	\$ 4,545,559.04
D. RAP	\$ 0.00
E. Clearance/Demolition	\$ 0.00
F. Title and Escrow Fees	\$ 220,500.00
G. Project Permit Fees	\$ 0.00
H. Condemnation Costs	\$ 1,323,603.00
<b>I. Total R/W Estimate:</b>	<b><u>\$ 10,280,813.04</u></b>
J. Construction Contract Work	\$ 0.00

1a. Real Property Services:

A. Routine Maintenance (Object Code 058)	\$ 0.00
B. Advertising Costs (Object Code 039)	\$ 0.00
C. Utility Costs (Object Code 002)	\$ 0.00
D. Total Real Property Services Estimate:	<u>\$ 0.00</u>

2. Anticipated Pypscan Date of Right of Way Certification 7/2012

3. Parcel Data:

Type	Dual/Appr	Utility Involvement	RR Involvement	<b>NO</b>
X _____	_____	U4-1 <u>6</u>	C&M Agrmt	<u>0</u>
A _____	_____	-2 <u>6</u>	Svc Contract	<u>0</u>
B <u>150</u>	_____	-3 _____	OE Clearances	<u>0</u>
C _____	_____	-4 _____	Clauses	<u>0</u>
			LIC / RE	<u>0</u>
D _____	_____	U5-7 _____	Government Lands	<b>NO</b>
E <u>xxxx</u>	_____	-8 <u>12</u>	Number of Parcels	_____
F <u>xxxx</u>	_____	-9 <u>24</u>		
			Misc. R/W Work	<u>0</u>
			RAP Displ	<u>0</u>
			Clear/Demo	<u>0</u>
			Const Permits	<u>0</u>
			Condemnation	<u>38</u>
			Permits to Enter-ENV	<u>0</u>
Total <u>150</u>				

Areas: Right of Way: S.F. 714,882  
 Excess: S.F. 0  
 No. Excess Land Parcels: 0



Date: April 28, 2009

08-SBd – 395- PM R 4.0 / 19.36  
Project Description: Widen from 2 Lanes to 4  
Lanes & Median Left-Turn Channelization with  
Rumble Strips  
ALTERNATIVE 2 UPDATE  
EA: 0F6300

4. Are there major items of construction contract work?

Yes \_\_\_ No X (If yes, explain.)

5. Provide a general description of the right of way and excess lands required (zoning, use, major improvements, critical or sensitive parcels, etc.). **No right of way required.**\_\_\_\_\_

Type and Number of Parcels: Fee 150  
Partial 150  
Full \_\_\_\_\_  
Easements \_\_\_\_\_  
Temporary \_\_\_\_\_  
Permanent \_\_\_\_\_

6. Is there an effect on assessed valuation?

Yes \_\_\_ Not Significant \_\_\_ No X (If yes, explain.)

7. Are utility facilities or rights of way affected?

Yes  No  (If "Yes," attach Utility Information Sheet, Exhibit 4-EX-5.)

The following checked items may seriously impact lead time for utility relocation:

- Longitudinal policy conflict(s)
  - Environmental concerns impacting acquisition of potential easements
  - Power lines operating in excess of 50 KV and substations
- (See attached Exhibit 4-EX-5 for explanation.)

8. Are railroad facilities or rights of way affected? Yes \_\_\_ No X

(If yes, attach Railroad Information Sheet, Exhibit 4-EX-6.)

9. Were any previously unidentified sites with hazardous waste and/or material

found? Yes \_\_\_ None Evident X (If yes, attach memorandum per Procedural Handbook Chapter 4, Section 4.01.10.00.)

10. Are RAP displacements required? Yes \_\_\_ No X (If yes, provide the following information.)

No. of single family \_\_\_\_\_ No. of business/nonprofit \_\_\_\_\_

No. of multi-family \_\_\_\_\_ No. of farms \_\_\_\_\_

Based on Draft/Final Relocation Impact Statement/Study dated \_\_\_\_\_, it is anticipated that sufficient replacement housing (will/will not) be available without Last Resort Housing.

11. Are there material borrow and/or disposal sites required?

Yes \_\_\_ No X (If yes, explain.)

12. Are there potential relinquishments and/or abandonments?

Yes \_\_\_ No X (If yes, explain.)

13. Are there existing and/or potential Airspace sites?

Yes \_\_\_ No X (If yes, explain.)

14. Indicate the anticipated Right of Way schedule and lead time requirements.

(Discuss if District proposes less than PMCS lead time and/or if significant pressures for project advancement are anticipate

PYPSCAN lead time (from Maps to R/W to project certification) 23 months.

Date: April 28, 2009

08-SBd – 395- PM R 4.0 / 19.36  
Project Description: Widen from 2 Lanes to 4  
Lanes & Median Left-Turn Channelization with  
Rumble Strips  
ALTERNATIVE 2 UPDATE  
EA: 0F6300

15. Is it anticipated that all Right of Way work will be performed by CALTRANS staff?  
Yes  No  (If no, discuss.)

Evaluations prepared by:

Right of Way:

Name

Lawrence Kelly  
LAWRENCE KELLY

Date

4-29-09

Railroad:

Name

Margie Smith  
for BETTY BOBOSIK

Date

4-29-09

Utilities:

Name

Ruth E. Williams  
RUTH E. WILLIAMS

Date

4-29-09

Government Lands:

Name

John W. Dixon  
JOHN W. DIXON

Date

APR 29 2009

Property Management:

Name

Jackie Williams  
JACKIE WILLIAMS

Date

5-4-09

Reviewed By:

Michael S. Romo

MICHAEL S. ROMO  
Senior Right of Way Agent  
Project Coordinator  
San Bernardino  
Right of Way, District 8

I have personally reviewed this Right of Way Data Sheet and all supporting information. I certify that the probable Highest and Best Use, estimated values, escalation rates, and assumptions are reasonable and proper subject to the limiting conditions set forth, and I find this Data Sheet complete and current.

Kathy Casey  
for LINDY K. LEE  
Right of Way Project Delivery Manager  
District 08, San Bernardino

Date 5-12-09

cc: Program Manager  
Project Manager

08-SBd-395-PM R4.0/19.36

Project Description: Widen from 2 lanes to 4 lanes & median left turn channelization  
With rumble strips  
Alternative 2 Update  
E.A. 0F6300

**This utility estimate was prepared using "project specific" data and unit values. This information is not to be utilized for the updating or preparation of any other Right of Way Cost Report or Utility Information Sheet.**

#### UTILITY INFORMATION SHEET

1. Name of utility companies involved in project:

Southern California Edison Company, Distribution/Transmission; Verizon; Sprint; Kinder Morgan (CalNev); SouthWest Gas; AT&T; L.A. Dept. Power & Water; San Bernardino Co Area 64; Baldy Mesa Co Water Dist; Charter Comm-High Desert & Hesperia; Victor Valley Wastewater Reclamation Authority; MCI (Verizon Business); San Bernardino Co Services; City of Adelanto; Hesperia Water; Time Warner Communications; City of Victorville; Level 3; Broadwing; State of Calif Dept Wtr Resources, SCG-Trans

2. Types of facilities and agreements required:

Phone, Water, Electric, Fiber Optics, fire hydrants; water valves; telecomm; gas; petroleum pipeline; CATV; Sewer

Notice to Owner, Utility Agreement, Pos Loc Agreements,

3. Is any facility a longitudinal encroachment in existing or proposed access controlled right of way? Explain.

No

Disposition of longitudinal encroachment(s):

Yes Relocation required.

       Exception to policy needed.

Yes Other. Explain. Possible positive location

- 4.

Additional information concerning utility involvement on this project, i.e., long lead time materials, growing or species seasons, customer service seasons (no transmission tower relocations in summer).

Along SR 395 it appears that there are approximately 90 Edison poles that will need to be relocated. Of these poles 9 are riser poles, & 7 poles have transformers on them. At the Aqueduct there are two poles that will need to be relocated and Verizon crosses SR 395 south of the Aqueduct. North of the Aqueduct Verizon runs northerly At Sycamore St there are two fire hydrants on the west side, underground telephone and fiber optic and approximately 100' north at Sierral Rd on either side of SR 395 there are two more fire hydrants just outside existing right of way. At Luna intersection there are some poles at the bus turnout the will need to be relocated and there are poles that have sand barrels and guard rails that may be in conflict. At Seneca Rd SouthWest Gas has two Reg Stations one on the west side and the other on the east side. They are approximately 40' from ETW. On east side there are 6 telephone poles northerly. At Mojave there are OH Edison lines on the west side & UG high pressure gas lines on the east side and water lines, too. Northerly, just past the bus pullout there are two fire hydrants; one on the east side and one on the west side. 0.01 mi from Cactus IC Kinder Morgan Petroleum pipeline crosses from the west side of SR 395 to the east side and continues northerly. At Cactus IC there is another SouthWest Reg Station on the north west side. SouthWest Gas continues northerly. At El Mirage, Kinder Morgan has a pipeline that runs on the west side and has already been potholed for work that was done on that intersection a couple of years ago. Also Level 3, GST, Sprint, AT&T & Broadwing (fiber optic ) lines are on both the east and west side of that intersection & they will probably have to be potholed due to the shoulder work planned for that area.

Should the scope of this project change to require more right of way, Design will have to provide the Right of Way Utility Coordinator (UC) with geometric base maps and a written request for utility verification [see Design Task D282 (220.D)]. The UC will then contact all appropriate Utility Owners (UO's) for verifications and corrections. The UC will then provide Design with the updated information and/or UO As-Builts and Design can then prepare accurate utility location maps or U-Sheets. Design will then determine all utility conflicts that require positive location and/or relocation [see Design Task D283 (220.D)].

5. PMCS Input Information

Total estimated cost of State's obligation for utility relocation on this project:

(Phase 9 funding) \$ 4,545,559.04

Note: Total estimated cost to include any Department obligation to relocate longitudinal encroachments in access controlled right of way and acquire any necessary utility easements.

Utility Involvement			
U4-1	<u>6</u>	U5-7	<u>    </u>
-2	<u>6</u>	-8	<u>12</u>
-3	<u>    </u>	-9	<u>24</u>
-4	<u>    </u>		

Prepared By: *Ruth E Williams*  
**RUTH E WILLIAMS**  
Right of Way Utility Estimator

Date: June 2, 2009

Date: April 28, 2009

08-SBd -- 395- PM R 4.0 / 19.36  
Project Description: Widen from 2 Lanes to 4  
Lanes & Median Left-Turn Channelization with  
Rumble Strips  
ALTERNATIVE 2 UPDATE  
EA: 0F6300

RAILROAD AND GOVERNMENT LANDS INFORMATION SHEET

1. Describe railroad facilities or rights of way affected.

None

2. When branch lines or spurs are affected, would acquisition and/or payment of damages to businesses and/or industries served by the railroad facility be more cost effective than construction of a facility to perpetuate the rail service? Yes \_\_\_ No X (If yes, explain.)

3. Discuss types of agreements and rights required from the railroads. Are grade crossings requiring service contracts, or grade separations requiring construction and maintenance agreements involved?

None

4. Remarks (non-operating railroad right of way involved?):

N/A

5. Is Government Lands involved? Yes \_\_\_ No X

If yes, number of parcels 0  
Agency Name and Explanation:

6. PMCS Input Information

RR Involvement	<u>NO</u>
C&M Agreement	<u>0</u>
OE Clearances	<u>0</u>
Clauses	<u>0</u>
LIC/RE	<u>0</u>
Government Lands	<u>NO</u>
Number parcels	<u>0</u>

Prepared By: Margie Smith  
for BETTY BOBOSIK  
Right of Way Railroad Coordinator

Date: 4-29-09

Prepared By: [Signature]  
JOHN W. DIXON  
Right of Way Government Lands Coordinator

Date: APR 29 2009

Date: April 28, 2009


08-SBd – 395- PM R 4.0 / 19.36  
Project Description: Widen from 2 Lanes to 4  
Lanes & Median Left-Turn Channelization with  
Rumble Strips  
**ALTERNATIVE 2 UPDATE**  
**EA: 0F6300**

PROPERTY MANAGEMENT/EXCESS LAND INFORMATIONAL SHEET  
NUMBER OF

<u>WBS CODE</u>	<u>WBS ACTIVITY</u>	<u>PARCELS</u>	<u>HOURS</u>	<u>COST</u>
	<u>PROPERTY MANAGEMENT</u>	<u>NOT APPLICABLE</u>		
195.40.05	Fair Market Rent Determinations (Residential)	_____	_____	_____
195.40.10	Fair Market Rent Determinations (Non-Residential)	_____	_____	_____
195.40.15	Regular Rental Property Management	<u>150</u>	<u>200</u>	_____
195.40.20	Property Maintenance and Rehabilitation (Rental Property)	_____	_____	_____
195.40.25	Property Maintenance and Rehabilitation (Non-Rental Property)	<u>150</u>	<u>200</u>	_____
195.40.30	Hazardous Waste and Hazardous Materials	_____	_____	_____
195.40.35	Transfer of Property to Clearance Status	_____	_____	_____
270.25.03	Secure Lease for Resident Engineer's Office Space or Trailer	<u>1</u>	<u>500</u>	_____
	Subtotal		<u>900</u>	_____
	<u>EXCESS LAND</u>	<u>NOT APPLICABLE</u> <u>X</u>		
195.45.05	Excess Land Inventory	_____	_____	_____
195.45.10	Excess Land Appraisal and Public Sale Estimate	_____	_____	_____
195.45.15	Excess land Inventory ("Roberti Bill)	_____	_____	_____
195.45.20	Excess Land Sales to \$15,000	_____	_____	_____
195.45.25	Excess Land Sales from \$15,001 to \$500,000	_____	_____	_____
195.45.30	Excess Land Sales over \$500,000	_____	_____	_____
195.45.35	CTC and AAC Coordination	_____	_____	_____
	Subtotal		_____	_____

TOTAL HOURS (ONLY) 900

Date: 5-4-09

  
\_\_\_\_\_  
JACKIE WILLIAMS  
Property Management  
Excess Land

Date: April 28, 2009

08-SBd - 395- PM R 4.0 / 19.36  
Project Description: Widen from 2 Lanes to 4  
Lanes & Median Left-Turn Channelization with  
Rumble Strips  
ALTERNATIVE 3 UPDATE  
EA: 0F6300

To: BEN AMIRI

From: MICHAEL S. ROMO  
R/W Project Delivery

Subject: Current Estimated Right of Way Costs

We have completed an updated ROW data sheet for estimate of the right of way costs for the above-referenced project based on maps we received from you March 3, 2009 and the following assumptions and limiting conditions:

- 1. The mapping did not provide sufficient detail to determine the limits of the right of way required.
- 2. The transportation facilities have not been sufficiently designed so that the estimator could determine the damages to any of the remainder parcels affected by the project.
- 3. Additional right of way requirements are anticipated, but are not defined due to the preliminary nature of the early design requirements.
- 4. We have determined there are no right of way functional involvement in the proposed project at this time, as designed.

Right of Way Lead Time will require a minimum of 23 months after we begin receiving final right of way requirements (PYPSCAN node No. 224), necessary environmental clearance has been obtained, and freeway agreements have been approved. From the date of receipt of final right of way requirements (PYPSCAN node No. 225), we will require a minimum of 12 months prior to the date of certification of the project. Either of these actions may reflect adversely on the District's other programs or our public image generally.

\*TOTAL PROJECT HOURS FOR R/W: 55,496

\*NOTE: THESE HOURS ARE PRELIMINARY BASED ON THE INFORMATION PROVIDED WITH THE DATA SHEET REQUEST. HOURS ARE SUBJECT TO CHANGE AS NEW INFORMATION IS PROVIDED.

Attachments:

- Right of Way Data Sheet
- Utility Information Sheet
- Railroad Information Sheet

EVNT RW	4/28
COST RW1 - 6	4/28
TEXT TI	4/28
SCAN	4/28
CLASS	_____
AGRE	_____
TPRC	_____

Date: April 28, 2009

08-SBd - 395- PM R 4.0 / 19.36  
 Project Description: Widen from 2 Lanes to 4  
 Lanes & Median Left-Turn Channelization with  
 Rumble Strips  
**ALTERNATIVE 3 UPDATE**  
**EA: 0F6300**

**Subject: Updated Request for ROW data sheet.**

1. Right of Way Cost Estimate:

	Value
A. Acquisition, including Excess Lands Damages, Goodwill, Major Rehabilitation, and Environmental Permits to Enter	\$ 3,984,003.00
B. Acquisition of Offsite Mitigation. <b>None Requested.</b>	\$ 0.00
C. Utility Relocation (State share)	\$ 5,776,624.00
D. RAP	\$ 0.00
E. Clearance/Demolition	\$ 0.00
F. Title and Escrow Fees	\$ 216,000.00
G. Project Permit Fees	\$ 0.00
H. Condemnation Costs	\$ 1,260,001.00
I. <b>Total R/W Estimate:</b>	<b><u>\$ 11,236,628.00</u></b>
J. Construction Contract Work	\$ 0.00

1a. Real Property Services:

A. Routine Maintenance (Object Code 058)	\$ 0.00
B. Advertising Costs (Object Code 039)	\$ 0.00
C. Utility Costs (Object Code 002)	\$ 0.00
D. Total Real Property Services Estimate:	<u>\$ 0.00</u>

2. Anticipated Pypscan Date of Right of Way Certification 7/2012

3. Parcel Data:

Type	Dual/Appr	Utility Involvement	RR Involvement	<b>NO</b>
X _____	_____	U4-1 <u>6</u>	C&M Agrmt	<u>0</u>
A _____	_____	-2 <u>6</u>	Svc Contract	<u>0</u>
B <u>145</u>	_____	-3 _____	OE Clearances	<u>0</u>
C _____	_____	-4 _____	Clauses	<u>0</u>
			LIC / RE	<u>0</u>
D _____	_____	U5-7 _____	Government Lands	<b>NO</b>
E <u>xxxx</u>		-8 <u>12</u>	Number of Parcels	_____
F <u>xxxx</u>		-9 <u>24</u>		
			Misc. R/W Work	<u>0</u>
			RAP Displ	<u>0</u>
			Clear/Demo	<u>0</u>
			Const Permits	<u>0</u>
			Condemnation	<u>37</u>
			Permits to Enter-ENV	<u>0</u>
Total <u>145</u>				

Areas: Right of Way: S.F. 616,734  
 Excess: S.F. 0  
 No. Excess Land Parcels: 0



Date: April 28, 2009

08-SBd - 395- PM R 4.0 / 19.36  
Project Description: Widen from 2 Lanes to 4  
Lanes & Median Left-Turn Channelization with  
Rumble Strips  
ALTERNATIVE 3 UPDATE  
EA: 0F6300

4. Are there major items of construction contract work?

Yes \_\_\_ No X (If yes, explain.)

5. Provide a general description of the right of way and excess lands required (zoning, use, major improvements, critical or sensitive parcels, etc.). **No right of way required.** \_\_\_\_\_

Type and Number of Parcels: Fee 145  
Partial 145  
Full \_\_\_\_\_  
Easements \_\_\_\_\_  
Temporary \_\_\_\_\_  
Permanent \_\_\_\_\_

6. Is there an effect on assessed valuation?

Yes \_\_\_ Not Significant \_\_\_ No X (If yes, explain.)

7. Are utility facilities or rights of way affected?

Yes  No  (If "Yes," attach Utility Information Sheet, Exhibit 4-EX-5.)

The following checked items may seriously impact lead time for utility relocation:

- Longitudinal policy conflict(s)
  - Environmental concerns impacting acquisition of potential easements
  - Power lines operating in excess of 50 KV and substations
- (See attached Exhibit 4-EX-5 for explanation.)

8. Are railroad facilities or rights of way affected? Yes \_\_\_ No X  
(If yes, attach Railroad Information Sheet, Exhibit 4-EX-6.)

9. Were any previously unidentified sites with hazardous waste and/or material found? Yes \_\_\_ None Evident X (If yes, attach memorandum per Procedural Handbook Chapter 4, Section 4.01.10.00.)

10. Are RAP displacements required? Yes \_\_\_ No X (If yes, provide the following information.)

No. of single family \_\_\_\_\_ No. of business/nonprofit \_\_\_\_\_

No. of multi-family \_\_\_\_\_ No. of farms \_\_\_\_\_

Based on Draft/Final Relocation Impact Statement/Study dated \_\_\_\_\_, it is anticipated that sufficient replacement housing (will/will not) be available without Last Resort Housing.

11. Are there material borrow and/or disposal sites required?

Yes \_\_\_ No X (If yes, explain.)

12. Are there potential relinquishments and/or abandonments?

Yes \_\_\_ No X (If yes, explain.)

13. Are there existing and/or potential Airspace sites?

Yes \_\_\_ No X (If yes, explain.)

14. Indicate the anticipated Right of Way schedule and lead time requirements.

(Discuss if District proposes less than PMCS lead time and/or if significant pressures for project advancement are anticipate

PYPSCAN lead time (from Maps to R/W to project certification) 23 months.

Date: April 28, 2009

08-SBd - 395- PM R 4.0 / 19.36

Project Description: Widen from 2 Lanes to 4  
Lanes & Median Left-Turn Channelization with  
Rumble Strips

ALTERNATIVE 3 UPDATE

EA: 0F6300

15. Is it anticipated that all Right of Way work will be performed by CALTRANS staff?  
Yes  No  (If no, discuss.)

Evaluations prepared by:

Right of Way:

Name

Lawrence Kelly  
LAWRENCE KELLY

Date

4/29/09

Railroad:

Name

Margie Smith  
for BETTY BOBOSIK

Date

4-29-09

Utilities:

Name

Ruth E. Williams  
RUTH E. WILLIAMS

Date

4-29-09

Government Lands:

Name

John W. Dixon  
JOHN W. DIXON

Date

APR 29 2009

Property Management:

Name

Jackie Williams  
JACKIE WILLIAMS

Date

5-4-09

Reviewed By:

Michael S. Romo

MICHAEL S. ROMO

Senior Right of Way Agent

Project Coordinator

San Bernardino Office

Right of Way, District 8

I have personally reviewed this Right of Way Data Sheet and all supporting information. I certify that the probable Highest and Best Use, estimated values, escalation rates, and assumptions are reasonable and proper subject to the limiting conditions set forth, and I find this Data Sheet complete and current.

Lindy K. Lee  
LINDY K. LEE

Right of Way Project Delivery Manager

District 08, San Bernardino

Date 5-12-09

cc: Program Manager  
Project Manager

08-SBd-395-PM R4.0/19.36

Project Description: Widen from 2 lanes to 4 lanes & median left turn channelization  
With rumble strips  
Alternative 3 Update  
E.A. 0F6300

**This utility estimate was prepared using "project specific" data and unit values. This information is not to be utilized for the updating or preparation of any other Right of Way Cost Report or Utility Information Sheet.**

#### UTILITY INFORMATION SHEET

1. Name of utility companies involved in project:

Southern California Edison Company, Distribution/Transmission; Verizon; Sprint; Kinder Morgan (CalNev); SouthWest Gas; AT&T; L.A. Dept. Power & Water; San Bernardino Co Area 64; Baldy Mesa Co Water Dist; Charter Comm-High Desert & Hesperia; Victor Valley Wastewater Reclamation Authority; MCI (Verizon Business); San Bernardino Co Services; City of Adelanto; Hesperia Water; Time Warner Communications; City of Victorville; Level 3; Broadwing; State of Calif Dept Wtr Resources, SCG-Trans

2. Types of facilities and agreements required:

Phone, Water, Electric, Fiber Optics, fire hydrants; water valves; telecomm; gas; petroleum pipeline; CATV; Sewer

Notice to Owner, Utility Agreement, Pos Loc Agreements,

3. Is any facility a longitudinal encroachment in existing or proposed access controlled right of way? Explain.  
No

Disposition of longitudinal encroachment(s):

Yes Relocation required.

       Exception to policy needed.

Yes Other. Explain. Possible positive location

- 4.

Additional information concerning utility involvement on this project, i.e., long lead time materials, growing or species seasons, customer service seasons (no transmission tower relocations in summer).

Along SR 395 it appears that there are 101 Edison poles that will need to be relocated. Of these poles 9 are riser poles, & 7 poles have transformers on them. At the Aqueduct there are two poles that will need to be relocated and Verizon crosses SR 395 south of the Aqueduct. North of the Aqueduct Verizon runs northerly and on the west side there are two large water tanks and the water line crosses SR 395. At the DWP towers Verizon has a pedestal approximately 20' from ETW. At Goss Rd (or Eucalyptus St) there is a pole that will need to be moved to the south due to the curb alignment. At Sycamore St there is two fire hydrants on the west side, on the east side a pole in the curb return and underground telephone and fiber optic and approximately 100' on either side of SR 395 there are two more fire hydrants just outside existing right of way. At Bear Valley intersection there are UG utilities such as SouthWest Gas, fiber optic, phone, water, Kinder Morgan petroleum pipeline. Just north of Eagle Ranch Rd. on the east side is SouthWest Gas reg station. At Luna intersection there is a pole at the bus turnout the will need to be relocated and there are poles that have sand barrels and guard rails that will also need to be relocated. On the east side UG gas & UG TWTC(Time Warner Telecom). At Palmdale/Rte 18 there are UG & OH utilities At Seneca Rd SouthWest Gas has two more Reg Stations one on the west side and the other on the east side. They are approximately 40' from ETW. On east side there are 6 telephone poles. At Mojave there are OH Edison lines on the west side & UG high pressure gas lines on the east side and water lines, too. Northerly, just past the bus pullout there are two fire hydrants; one on the east side and one on the west side. 0.01 mi from Cactus IC Kinder Morgan Petroleum pipeline crosses from the west side of SR 395 to the east side and continues northerly. At Cactus IC there is another SouthWest Reg Station on the north west side. SouthWest Gas continues northerly down the location that's marked for removal of existing pavement. At Rancho Rd. there is a pole on the west side that is 8' off the curb. At El Mirage, Kinder Morgan has a pipeline that runs on the west side and has already been potholed for work that was done on that intersection a couple of years ago. Also Level 3, GST, Sprint, AT&T & Broadwing (fiber optic ) lines are on both the east and west side of that intersection they will probably have to be potholed due to the shoulder work planned for that area.

Should the scope of this project change to require more right of way, Design will have to provide the Right of Way Utility Coordinator (UC) with geometric base maps and a written request for utility verification [see

Design Task D282 (220.D)]. The UC will then contact all appropriate Utility Owners (UO's) for verifications and corrections. The UC will then provide Design with the updated information and/or UO As-Builts and Design can then prepare accurate utility location maps or U-Sheets. Design will then determine all utility conflicts that require positive location and/or relocation [see Design Task D283 (220.D)].

5. PMCS Input Information

Total estimated cost of State's obligation for utility relocation on this project:

(Phase 9 funding) \$ 5,776,624.00

Note: Total estimated cost to include any Department obligation to relocate longitudinal encroachments in access controlled right of way and acquire any necessary utility easements.

Utility Involvement	
U4-1	<u>6</u>
-2	<u>6</u>
-3	<u>    </u>
-4	<u>    </u>
U5-7	<u>    </u>
-8	<u>12</u>
-9	<u>24</u>

Prepared By: Ruth E. Williams  
**RUTH E WILLIAMS**  
Right of Way Utility Estimator

Date: June 2, 2009

Date: April 28, 2009

08-SBd - 395- PM R 4.0 / 19.36  
Project Description: Widen from 2 Lanes to 4  
Lanes & Median Left-Turn Channelization with  
Rumble Strips  
**ALTERNATIVE 3 UPDATE**  
**EA: 0F6300**

RAILROAD AND GOVERNMENT LANDS INFORMATION SHEET

1. Describe railroad facilities or rights of way affected.

**None**

2. When branch lines or spurs are affected, would acquisition and/or payment of damages to businesses and/or industries served by the railroad facility be more cost effective than construction of a facility to perpetuate the rail service? Yes \_\_\_ No X (If yes, explain.)

3. Discuss types of agreements and rights required from the railroads. Are grade crossings requiring service contracts, or grade separations requiring construction and maintenance agreements involved?

**None**

4. Remarks (non-operating railroad right of way involved?):

**N/A**

5. Is Government Lands involved? Yes \_\_\_ No X

If yes, number of parcels \_\_\_\_\_  
Agency Name and Explanation:

6. PMCS Input Information

RR Involvement	<u>NO</u>
C&M Agreement	<u>0</u>
OE Clearances	<u>0</u>
Clauses	<u>0</u>
LIC/RE	<u>0</u>
Government Lands	<u>NO</u>
Number parcels	_____

Prepared By: Margie Smith  
for BETTY BOBOSIK  
Right of Way Railroad Coordinator

Date: 4-29-09

Prepared By: John W. Dixon  
JOHN W. DIXON  
Right of Way Government Lands Coordinator

Date: APR 29 2009

Date: April 28, 2009


08-SBd - 395- PM R 4.0 / 19.36  
Project Description: Widen from 2 Lanes to 4  
Lanes & Median Left-Turn Channelization with  
Rumble Strips  
ALTERNATIVE 3 UPDATE  
EA: 0F6300

PROPERTY MANAGEMENT/EXCESS LAND INFORMATIONAL SHEET  
NUMBER OF

<u>WBS CODE</u>	<u>WBS ACTIVITY</u>	<u>PARCELS</u>	<u>HOURS</u>	<u>COST</u>
	<u>PROPERTY MANAGEMENT</u>		<u>NOT APPLICABLE</u>	
195.40.05	Fair Market Rent Determinations (Residential)			
195.40.10	Fair Market Rent Determinations (Non-Residential)			
195.40.15	Regular Rental Property Management	<u>145</u>	<u>200</u>	
195.40.20	Property Maintenance and Rehabilitation (Rental Property)			
195.40.25	Property Maintenance and Rehabilitation (Non-Rental Property)	<u>145</u>	<u>200</u>	
195.40.30	Hazardous Waste and Hazardous Materials			
195.40.35	Transfer of Property to Clearance Status			
270.25.03	Secure Lease for Resident Engineer's Office Space or Trailer	<u>1</u>	<u>500</u>	
	Subtotal		<u>900</u>	
	<u>EXCESS LAND</u>		<u>NOT APPLICABLE</u>	<u>X</u>
195.45.05	Excess Land Inventory			
195.45.10	Excess Land Appraisal and Public Sale Estimate			
195.45.15	Excess land Inventory ("Roberti Bill)			
195.45.20	Excess Land Sales to \$15,000			
195.45.25	Excess Land Sales from \$15,001 to \$500,000			
195.45.30	Excess Land Sales over \$500,000			
195.45.35	CTC and AAC Coordination			
	Subtotal			

TOTAL HOURS (ONLY) 900

Date: 5-4-09

  
\_\_\_\_\_  
JACKIE WILLIAMS  
Property Management  
Excess Land

08-SBd-395 PM R4.0/19.3  
08-236-0F6300  
Widen Highway and  
Improve Intersections  
HE-13 (STIP)  
20.20.025.700

# **ATTACHMENT H**

## **Storm Water Data Report (SWDR)**

Long Form - Storm Water Data Report



Dist-County-Route: 08-SBd-395  
 Post Mile (Kilometer Post) Limits: R4.0/19.3  
 Project Type: Widening Route 395  
 EA: 0F630  
 RU: 236  
 Program Identification: STIPP

Phase:  PID  PA/ED  PS&E

Regional Water Quality Control Board(s): Lahontan

Is the project required to consider incorporating Treatment BMPs?  Yes  No

If yes, can Treatment BMPs be incorporated into the project?  Yes  No

If No, a Technical Data Report must be submitted to the RWQCB at least 60 days prior to PS&E Submittal. List submittal date: 07/02/2012

Total Disturbed Soil Area: 149 acres

Estimated Construction Start Date: 03/07/13 Construction Completion Date: 03/20/15

Notification of Construction (NOC) Date to be submitted: \_\_\_\_\_

Notification of ADL reuse (if Yes, provide date)  Yes Date: \_\_\_\_\_  No

Separate Dewatering Permit (if Yes, permit number)  Yes Permit #: \_\_\_\_\_  No

*This Report has been prepared under the direction of the following Licensed Person. The Licensed Person attests to the technical information contained herein and the data upon which recommendations, conclusions, and decisions are based. Professional Engineer or Landscape Architect stamp required at PS&E.*

Refaat Elsherif, Registered Project Engineer/Landscape Architect Date: 8/18/09

*I have reviewed the storm water quality design issues and find this report to be complete, current, and accurate:*

8/18/09  
 Jim Robinson, Project Manager Date

8-19-09  
 Cindy Gano, Designated Maintenance Representative Date

10/28/09  
 Ray Deselle, Designated Landscape Architect Representative Date

11/18/09  
 Cathy Jochai, District/Regional SW Coordinator or Designee Date



08-SBd-395 PM R4.0/19.3  
08-236-0F6300  
Widen Highway and  
Improve Intersections  
HE-13 (STIP)  
20.20.025.700

# **ATTACHMENT I**

## **Project Category Assignment**

## Memorandum

*Flex your power!  
Be energy efficient!*

**To:** CHRISTY CONNORS  
DEPUTY DISTRICT DIRECTOR  
DESIGN, MS 1267

**Date:** June 30, 2009

**File:** 08-SBd-395-PM R4.0/19.36  
Widen fr 2 Lanes to 4 Lanes  
& Median Left-Turn  
Channelization  
EA 08236 – 0F6300

**From:** BEN AMIRI  
Office Chief  
Design I, MS 1164


**Subject:** Project Category Assignment


Your approval is requested for assignment of the above-referenced project to Category 4A, in accordance with requirements in Charter 8, Section 5 of the Project Development Procedures Manual (7<sup>th</sup> Edition).

The work consists of widening the existing facility from one lane to two lanes in each direction, providing a left-turn channelization with rumble strip in the median and widening the shoulders. In addition, roadway resurfacing is proposed in both directions and to improve five intersections. This project will require right of way acquisition and utility relocation. The total cost for the proposed improvements, including right of way, is estimated from \$109.2 to \$122.8 million.

This project is eligible for programming in the State Transportation Improvement Program (STIP) under the HE-13 – Highway Widening Program. This project is included in the 2004 Regional Transportation Plan (RTP).

Approved By:

  
\_\_\_\_\_  
CHRISTY CONNORS  
Deputy District Director  
Design

  
\_\_\_\_\_  
Date

c: GMorhig, Design Manager (MS 1164); JRobinson, Project Management (MS 1227); File  
Juan Carlos Alvarez / df

08-SBd-395 PM R4.0/19.3  
08-236-0F6300  
Widen Highway and  
Improve Intersections  
HE-13 (STIP)  
20.20.025.700

# **ATTACHMENT J**

## **Traffic Management Plan**

**Draft TRANSPORTATION MANAGEMENT PLAN (TMP) DATA SHEET for PSR/PDS with DTM requirements for PSE and Construction Phase - This TMP is valid until one year from date of preparation or less if the project changes.**

T:\DTM.TMP\project docs\SBD\395\EA0F630K\080512 TMP Data Sheet (includes signature/background sheet, estimate, table, and DTM requirements)

TEMPLATE: 0 TMP Data Sheet revised 050628.xls.

**EA            08-0F6300            DATE    5/12/2009**

08-SBd-395-R6.41/31.1 KP

08-SBd-395-R4.0/19.3 PM

Location:

Work:                      Widen & Improvements

Documents available:

***Plans, working days per PE***

**BACKGROUND INFORMATION:**

DURATION:                       WORKING DAYS  
 PROJECT COST:                \$109,215,000  
 TMP ESTIMATE:                **\$1,267,620**                      or            1.16%                      OF THE PROJECT COST

Construction period per WPS

EST START DATE	Aug-2010
EST END DATE	Dec-2012

<b>IMPACT</b>	High	Medium	Low	NA	Details:( <i>Explain high impact</i> )
STATE HWY	X				
LOCAL RD	X				
Ramps/connectors		?			

Prepared by    Signature ORIGINAL SIGNED BY Dara Maleki    Date                      5/12/2009

Name    Dara Maleki (909)-383-4464  
 Title    Transportation Engineer  
 Organization                                      Caltrans  
 Telephone/FAX                                    (909)383-4264/6429  
 email    [Dara\\_Maleki@dot.ca.gov](mailto:Dara_Maleki@dot.ca.gov)

**TMP ESTIMATE**

**EA 08-0F6300 DATE 5/12/2009**

<b>1. Public Information</b>	NO	<input checked="" type="checkbox"/> YES	MAYBE	\$220,000
<b>2. Motorist Information Strategies</b>	NO	<input checked="" type="checkbox"/> YES	MAYBE	\$30,000
<b>3. Incident Management</b>	NO	<input checked="" type="checkbox"/> YES	MAYBE	\$997,620
<b>4. Construction Strategies</b>	NO	<input checked="" type="checkbox"/> YES	MAYBE	\$0
<b>5. Demand Management (DM)</b>	NO	YES	<input checked="" type="checkbox"/> MAYBE	\$0
<b>6. Alternate Route Strategies</b>	NO	YES	<input checked="" type="checkbox"/> MAYBE	\$20,000
<b>7. Other Strategies</b>	NO	YES	<input checked="" type="checkbox"/> MAYBE	\$0
<b>TMP TOTAL</b>				<b>\$ 1,267,620</b>

**TMP TABLE**

**EA**

**08-0F6300 DATE 5/12/2009**

An X in the check box means you need to include this in the project unless staging, material, or work hour changes eliminate the need for the item. A ? in the box means TMP anticipates this - please check into this. A blank box means the item is not needed at this time based on the information received.

**1 Public Information/Public Awareness Campaign (PAC) COST**

BEES 066063A PAC Cost to be reduced by Public Affairs (PA) and PA COST CL COST  
Construction Liaison (CL) only. Show in Supplemental Work. 100000 120000

Include Rideshare information in PA/CL project material to encourage vehicles reduction in work area

- 1.1  Brochures and Mailers
- 1.2  Media Releases (& minority media sources)
- 1.3  Paid Advertising
- 1.4  Public Information Center/Kiosk
- 1.5  Public Meetings/PAC Mtgs./Speakers Bureau (show cost also for room rental)
- 1.6  Handdeliver notices to vicinity
- 1.7  Broadcast fax service
- 1.8  Telephone Hotline
- 1.9  1-800-COMMUTE (the telephone number is shown on CS-Info signs) - contact Cyrin Kwong, 383-4256, to place msg into the 1800C telephone system.
- 1.10  Visual Information (videos, slide shows, etc.)
- 1.11  Local cable TV and News
- 1.12  Traveler Information Systems (Internet)
- 1.13  Internet, E-mail
- 1.14 Notification to targeted groups:
  - Revised Transit Schedules/maps
  - Rideshare organizations
  - schools
  - organizations representing people with disabilities
  - bicycle organizations
- 1.15  Include PA/CL/Consultant resources in WPS
- 1.16  Commercial traffic reporters/feeds - e.g. brief Traffic Information people (TIP) group
- 1.17  Others

Subtotals	\$ 100,000	\$ 120,000	
		<b>SUBTOTAL</b>	\$220,000

**2 Traveler Information Strategies**

Project team needs to coordinate with Traffic Design!

2.1  Existing Electronic Message Signs (Stationary) - list locations. See Note 5

New Installation (Stationary) - BEES 860530 CHANGEABLE MESSAGE SIGN SYSTEM  
- list locations. See Note 5

2.2  Portable Changeable Message Signs (PCMS) Rental Lumpsum BEES 128650 in Supplemental Funds

**TMP TABLE**

**EA**

**08-0F6300 DATE 5/12/2009**

These PCMS advise motorists to divert at remote advance decision points - outside the usual work limits. Unlike stationary CMS, you are allowed to use them for advance motorist information - e.g. a week ahead. Their placement may need to be cleared environmentally so that they can be included in plans and SSP later. They may be in addition to Traffic Design's PCMS for regular traffic handling in and next to a work area.

\$30,000

Placement Details:

2.3  Extinguishable Signs (only shown because they are on the TMP Guidelines list. Usually found at Weigh Stations - Weigh Station "open/closed".)

2.4 Ground Mounted Signs / Fabric signs Note 2

C40/40A Double Fine Sign - black and white

Regulatory speed signs

SC6-4 (per MUTCD)

C-SPECIAL w/ SC6-2 PANEL ("Dates/Days/Hours/Expect delay") Use when conventional highways or local roads will be affected for longer periods. Use fabric signs if fast moving operation. To encourage traffic to detour so delay in your work area is less, use at advance location and add "work location".

CS-INFO/1-800-COMMUTE Panel Sign Also see 1.9.

Blue and white Rideshare guide signs, including website (1-800-COMMUTE/www.commutesmart.info). **Need to be installed at the same time as the funding signs.**

2.5  Commercial Traffic Radio (usually only applicable in the Upper desert)

Highway Advisory Radio (HAR) - Fixed. List locations here. They can be obtained from TMC Manager. See Note 5.

Highway Advisory Radio - mobile (signs alerting motorists to the HAR will also be needed) Contact TMC manager for assistance with specifications to include portable HARs as bid item in the contract. To avoid FCC fines, CT Portable HAR cannot be used except for emergencies. See Note 5

List proposed locations here:

2.6  Lane Closure Web Site

2.7  Caltrans Highway Information Network (CHIN)

2.8  Radar Speed Message Sign (Specter sign) BEES 066064 (approx. EA @ \$30,000)

2.9  Bicycle and pedestrian information, e.g. Detour maps

2.10  Others

**SUBTOTAL \$30,000**

**3 Incident Management**

3.1  CHP's Construction or Maintenance Zone Enhanced Enforcement Program – COZEEP or MAZEEP. BEES 066061 - show under "State or Agency furnished" in the Cost Estimate. **SSP 12-225 has been deleted per HQ OE.** See note 1.

Check the LC hours and add CHP driving time to/from their office

Hourly Cozeep overtime loaded rate: \$ 85

COZEEP - to protect active closures

150	12	1	50	8	4	\$289,000
# of days	hours	# of officers (1 per car )	nights	hours	# of officers (Remember - nights require	

**TMP TABLE**

**EA**

**08-0F6300 DATE 5/12/2009**

nights require  
2 per car )

ECOZEEP - to mitigate continuous restrictions. Add weekends days if needed.

						\$0
# of days	hours	# of officers	nights	hours	see above	

(add weekends days as needed)

CHP TRAFFIC HANDLING - reduce delay by keeping traffic flowing and/or to enforce closures - total facility/structure/major traffic shifts/ramps/connectors/local road/extended closures. Freeway closures with local road detours may require 2 officers per intersection to direct traffic.

			50	10	8	\$340,000
days	hours	# of officers	nights	hours	see above	

CHP Officer in TMC during major construction closures

50	8	1	\$34,000
days	hours	# of officers	

CHP Officer for Command Post during regional impact construction closures

			\$0
days	hours	# of officers	

**3.1 Total \$663,000**

**3.2 BLANK**

**3.3**  Freeway Service Patrol (FSP) for Construction (CFSP) \$/hr/truck \$55

BEES 066065 - show under "State or Agency furnished" in the Cost Estimate  
Short duration or remote area CFSP usually is bid w much higher hourly rates. If enhancement of program FSP feasible, CFSP could tie into the lower long-term FSP rates.

**FOR SERVICE WITHIN REGULAR FSP HOURS:**

**A** # of trucks:  days & hrs:   **\$198,000**

**FOR SERVICE OUTSIDE REGULAR FSP HOURS:**

Extend Peak hour coverage  
**B** # of trucks:  days & hrs:   **\$0**

Night support during structure freeway closures and major traffic shifts  
**C** # of trucks:  days & hrs:   **\$66,000**

Weekend support  
**D** # of trucks:  days & hrs:   **\$0**

Local agency (SAFE) support 8% of truck cost **\$21,120**

CFSP CHP support 5% of truck cost **\$9,900**

THIS % ONLY IF WITHIN REGULAR FSP HOURS AND AREA!

CFSP CHP support 20% of truck cost **\$13,200**

% FOR B,C,D WHICH ARE OUTSIDE REGULAR FSP HOURS OR AREA!



**TMP TABLE**

**EA**

**08-0F6300 DATE 5/12/2009**

Equipment/Supplies 10% \$26,400  
% of truck cost unless more detail available

- Cooperative Agreement or Task Order with SAFE
- Task Order with CHP (Statewide Master Agreement for FSP support).  
Contact District FSP Coordinator for task orders.
- Service Contract

**3.3 Total \$334,620**

- 3.4  CHP Helicopter/Airplane
- 3.5  Traffic Surveillance Stations for construction impact mitigation (loop detectors and CCTV)  
**Keep existing operational during construction**

- New CCTV
- New loops

- 3.6 **Call Boxes - also see NOTE 4 in the Revisions & Notes tab**  
 TEMPORARY INSTALLATION to mitigate impact (\$4000/box/move from project funds to SAFE). Project Report/Design PE: Please discuss with the D8 Call box coordinator if it is feasible to keep this motorist aid available during construction. If it is not, please notify TMP, then other mitigation needs to be considered.

- 3.7  911 Cellular Calls
- 3.8  Transportation Management Centers
- 3.9  Traffic Management Teams (TMT) needed to assist w system diversion/impact reduction  
See Note 5

- 3.10  On-site Traffic Advisor
- 3.11  Others

**SUBTOTAL \$ 997,620**

**4 Construction Strategies**

Please contact Saleh Yadegari, 4232, to get Delay Calculations, lane closure charts, Table Z and Special events list. **Please tell him of any concerns/commitments re special LC days, times, season, events; environmental restrictions; if work may be affected by snow and low or high temperatures.** E.g. desert heat may delay AC digout curing which may increase traffic impact when vehicles overheat in the queue; etc. IF traffic volumes vary significantly between seasons, consider including different closure charts to avoid a CCO later.

4.1 This TMP presumes work is planned as below. If different, TMP needs to be revised.

- Off peak
- Night
- Weekend

4.2 Project Engineer is responsible to request closure charts for

- Flagging
- Shoulder
- Lane
- Street
- Ramp
- Connector
- Extended Weekend Closures
- Total Facility Closures

**CAUTION: If the Lane Closure Chart (LCC) for full mainline closures (one or both directions on a highway or freeway) does not show a maximum number of allowable days, the PSE cannot be certified by DTM/TMP.**

**TMP TABLE**

**EA**

**08-0F6300 DATE 5/12/2009**

- 4.3  Project Phasing
  - 4.4  Contra Flow (put traffic into opposing roadbed)
  - 4.5  Reversible Lanes
  - 4.6  K-Rail  
 BEES 152372 - Lateral shifting to open shoulder space early is anticipated. Please include supplemental work funds in the estimate to pay for the extra work. See Standard Specifications 12-4, Measurement and Payment. Discuss w Traffic Design!
  
  - Temporary Traffic Screens
  - 4.7  Movable Barrier
  - 4.8  Truck Traffic Restrictions
  - 4.9  Coordinate with adjacent construction and planned projects - also on detour routes.  
Use SSP 07-850
  - 4.10  BEES 066008 Incentives/Disincentives
  - 4.11  Strictly enforce Constr. Progress Schedule (CPM)
  - 4.12  Specification 12-220  
 Funds for paragraph 11 and 12:  
BEES 066022 (**Traffic**) **Right of Way delay**. Show in supplemental work. If State (or agency) \$ -  
denies an approved closure or orders the contractor to pick it up early, this can be used to pay damages, e.g. for AC cold load, etc.
  - 4.13  **Delay Penalty (DP)**      **Please contact Saleh Yadegari, 4232, regarding Delay Calculations.**  
DP is not related to the R/W Delay shown above!
  - 4.14  Others
- SUBTOTAL \$ -**

**5 Demand Management (DM)**  
**Project team needs to coordinate with RCTC/SANBAG/CVAG**

**Traffic diversion may increase available work hours.**

- 5.1  A coop will be executed
- Instead of a coop, 15% is added to the cost of DM elements since the payment to the local agency will be routed through the contractor.
- Instead of a coop, the local agency will make their own arrangements with RCTC/SANBAG.
- PA/CL need to inform commuters info through RCTC/SANBAG. Funds part of PA/CL.
  
- 5.2  HOV Lanes/Ramps (New or Convert)
- 5.3  Park-and-Ride Lots  
 LEASED SPACES (Are sponsored spaces feasible in exchange for signs and print coverage?)
- 5.4  Parking Management/Pricing (Coordination with local agency required)
- 5.5  BEES 066069 Rideshare Promotion
- 5.6 Rideshare Incentives -  
As far as D8 DTM.TMP knows, incentives to individuals cannot be paid by the State, however, State can pay for Local Transportation agency staff time, postage, cost of extra busses, etc.
  
- Carpool/vanpool
- Transit
- Train
- Light-Rail
- 5.7 BEES 066066  
 Public Transit Support/Improvements/Shuttle Service  
 School Shuttle Service
- 5.8  Variable Work Hours
- 5.9  Telecommute
- 5.10  Ramp Metering (Modify or new)

**TMP TABLE**

**EA**

**08-0F6300 DATE 5/12/2009**

- 5.11  Rideshare signs needed - unless already signed. See 2.4
- 5.12  Others

**SUBTOTAL \$ -**

**6 Alternate Route Strategies**

**Caution - signed detours may require environmental clearance**

Traffic diversion may increase available work hours. Please work with Traffic Design.

- 6.1  Add Capacity to Freeway connector
- 6.2  Ramp Closures
- 6.3  Temporary Highway Lanes or Shoulder Use
- 6.4  Parking Restrictions
- 6.5  Street Improvements
  - State R/W - Signals, Widen, etc.
  - Local R/W - Signals, Widen, etc. Coop or Permit may be needed
- 6.6  Local Street USE - Coop or Permit may be needed
- 6.7  Traffic Control Officers (see 3.1 Cozeep)
- 6.8  Signed detour - using State routes
- 6.9  Signed detour - using local streets and roads
- 6.10  ? Adjust signals
- 6.11  Temporary bicycle or pedestrian facilities
- 6.12  Others

\$ 20,000

**SUBTOTAL \$ 20,000.00**

**7 Other Strategies**

- 7.1  Application of new technology
- 7.2  Innovative products
- 7.3  Others

**SUBTOTAL \$ -**

**TOTAL \$ 1,267,620**

08-SBd-395 PM R4.0/19.3  
08-236-0F6300  
Widen Highway and  
Improve Intersections  
HE-13 (STIP)  
20.20.025.700

# **ATTACHMENT K**

## **Project Initiation Proposal (PIP)**

DATE REC IN PM: Sept 01 E.A. DF6304 PIP NO. 2728

A. Originating Office Pre-Prog./Eng. Studies Date 8/30/2004  
Office Chief Greg Ramirez Telephone Ext. 6309  
Contact Vu Ngo Telephone Ext. 4827

LOCATION: SBD-395-3.98/19.3 (KP 6.41/31.1) In Hesperia, Victorville & Adelanto from I-15/US-395 Sep  
Co-Rte-PM (KP) to 2.8 km south of Desert Flower Rd

ISSUE: Geographic  
In March 2004, PIPs 2659 and 2660 were approved to widen US-395 from two lanes to four lanes with a 4.2-meter two-way left-turn lane and to adjust the vertical alignment where necessary to enhance sight distance. The highway segments to be improved were: SBD-395-3.98/11.18 (KP 6.41/17.99) and SBD-395-11.18/19.3 (KP 17.99/31.1). It is proposed to combine both locations into a single project under one Expenditure Authorization, to facilitate the project development process and improve efficiency.

PROPOSED SOLUTION(S):  
To facilitate the project development process and improve efficiency, combine work under project EAs 08-34041 (PIP # 2659) and 08-34042 (PIP # 2660) as a single project with a new EA. For additional details, see attached PIPs. Draft Contrib. Agreement 8-1250 for EAs 34041 & 43042. SANBAG to fund \$2,000,000 of support costs for PA/ED. State Support \$8,750,000.

AGREEMENT REQUIRED: YES: X NO:       

PERFORMANCE INDICATORS: NO:        DESCRIPTOR: N/A

PRELIMINARY ESTIMATE:					
CONST:	Roadwork	<u>\$39,000,000</u>	Structures	<u>\$1,000,000</u>	Total <u>\$40,000,000</u>
	State Share	<u>\$40,000,000</u>	Local Share	<u>      </u>	
RW:	Acquisition	<u>\$1,000,000</u>	Utilities	<u>\$2,000,000</u>	Total <u>\$3,000,000</u>
	State Share	<u>\$3,000,000</u>	Local Share	<u>      </u>	

TOTAL PROJECT COST: (CONST + RW):       

B. PROGRAM MANAGEMENT: Type 025.700  
Project Type: STIP HE13 Major X Minor        Proposed Funding: FY FND  
Project Manager Gary Wintergerst Functional Manager Greg Ramirez

Comments: This PIP recombines PIPs 2659 and 2660 which were reviewed by District's staff. The Project Manager has advised programming that a state review is not needed since the two PIPs have been reviewed. Date: 9/1/04 JF.

C. REVIEWER COMMENTS: Request Staff Review   
CHARGE TIME TO EA: 987903 SD: 5954395005.9 ACT: 2012

No review is required (see note above). Project Manager to prepare a schedule for the PID.

Reviewer [Signature] Date 9/1/04  
Print Name JOE FENNEMAN P Office Prog. Mgt.

D. FINAL DISPOSITION: Project: Approved as Submitted  Approved With Conditions(See Comments)   
Rejected

COMMENTS:  
DDD Program/Project Management [Signature] Date: 9-16-04

PROJECT DATA SHEET

PROGRAM MANAGEMENT

A. E. A.: DF6306 PPNO: \_\_\_\_\_ PIP NO: 2728

CONSTRUCTION PROGRAM CODES: TRAMS 25.700 PMCS HE11 ELEM FCR

FUND SOURCE: FED ONLY: \_\_\_\_\_ FED/STA: \_\_\_\_\_ STA ONLY: \_\_\_\_\_ OTHER: \_\_\_\_\_

ENVIRONMENTAL DOCUMENT TYPE: \_\_\_\_\_ PID TYPE: \_\_\_\_\_

B. OTHER FUNDED PROJECTS:

TYPE(S): \_\_\_\_\_

AGENCY NAME(S): \_\_\_\_\_ U-FLAG #: \_\_\_\_\_

Percentage of work to be transferred to outside agency identified by phase:

"K" Phase%: \_\_\_\_\_ "0" Phase%: \_\_\_\_\_ "1" Phase%: \_\_\_\_\_ "2" Phase%: \_\_\_\_\_ "4" Phase%: \_\_\_\_\_

C. COST (\$1,000s)	STATE FUNDS	LOCAL FUNDS	TOTAL COST
BRIDGE	_____	_____	_____
ROADWAY	_____	_____	_____
TOTAL CONST	_____	_____	_____
RIGHT OF WAY	_____	_____	_____
TOTAL	_____	_____	_____

D. Enter date PMCS screen was updated:

FUNC TAS _____	TEXT PC _____	MAKE _____
COST FND _____	TEXT ST _____	CLAS _____
COST EST _____	TEXT SF _____	SCAN _____
COST CAP _____	TEXT TI _____	PYRS _____
EVNT CLR _____	COST RW1 _____	(ENTERED BY R/W)
EVNT DTE _____		
EVNT RPT _____		
EVNT ADV _____		

E. FILE MAKER PRO (PROGRAMMING SUMMARY):

Enter date FMP was updated:

1. Project Description \_\_\_\_\_
2. Cost Estimates \_\_\_\_\_
3. Schedule and Record of Estimates \_\_\_\_\_

DATE: 9-26-04

PIP# 2728

EA# CF630B

**DISTRIBUTION OF APPROVED PROJECT INITIATION  
PROPOSAL (PIP)**

<u>TO</u>	<u>MAIL STATION</u>	<u>NAME</u>	<u>DEPARTMENT</u>
X	730	G. Ramirez	PIP INITIATOR
—	1123	R. BOTELLO	BUDGETS (HM PROJECTS)
—	—	—	FUNCTIONAL MANAGER
—	—	—	MAINTENANCE SUPT. (HA21, HA22, HM)
—	1161	J. ROGERS	HYDRAULICS
—	1030	W. LI	LOCAL ASSISTANCE (LOCAL FUNDING INVOLVED)
X	728	P. FAGAN	TRANSPORTATION PLANNING
X	1234	P. GONZALES	ENVIRONMENTAL PROJECT MANAGEMENT
X	730	G. RAMIREZ	PRE PROG/ENG STUDIES - 1 copy only (MAJORS)
X	1229	G. Wintergest	*PROJECT MANAGER (MAJORS, MINORS, HM)
—	1232	—	PROJECT MANAGER (MINORS)
X	645	E. MCGINN	CAPITAL OUTLAY SUPPORT
—	1231	L. SUPERNAW	PROGRAM MANAGEMENT
X	9-2/9G (HQ)	M. DOWNS	STRUCTURES
X	9-5/8F (HQ)	J. COSMEZ	STRUCTURES
X	855	D. PEETERS	R/W PLANNING & MGMT. (OTHER THAN HM)
—	DIST.7 (HQ) (DSMI SOUTH)	S. NAKAO	MAINTENANCE (HA21, HA22)
FROM:	1231	M. CADDELL	PROGRAM MANAGEMENT

\*SEE CORRIDOR ASSIGNMENT