

REVISED ASBESTOS AND LEAD-BASED PAINT SURVEY MOUNT VERNON AVENUE BRIDGE SAN BERNARDINO, CALIFORNIA

PREPARED FOR:

IFC Jones & Stokes 9775 Businesspark Avenue San Diego, California 92131

PREPARED BY:

Ninyo & Moore Geotechnical and Environmental Sciences Consultants 475 Goddard, Suite 200 Irvine, California 92618

> January 13, 2010 Project No. 205732002

475 Goddard, Suite 200 • Irvine, California 92618 • Phone (949) 753-7070 • Fax (949) 753-7071



January 13, 2010 Project No. 205732002

Ms. Jean LaFontaine, Project Manager IFC Jones & Stokes 9775 Businesspark Avenue San Diego, California 92131

Subject: Revised Asbestos and Lead-Based Paint Survey Mount Vernon Avenue Bridge San Bernardino, California

Dear Ms. LaFontaine:

In accordance with your authorization to proceed, Ninyo & Moore has performed an Asbestos and Lead-Based Paint Survey at the Mount Vernon Avenue Bridge in San Bernardino, California. The attached report presents our methodology, findings, conclusions, and recommendations regarding our survey.

We appreciate the opportunity to be of service to you on this important project. Should you have any questions regarding this report, please contact me at your convenience.

Sincerely, NINYO & MOORE

Dana E. Williams Certified Asbestos Consultant No. 93-1168

DEW/GOB/mlc/glw

Beill

Gene Berkland, P.E. Senior Engineer

Distribution: (1) Addressee

- (1) Ms. Alicia, Colburn, AECOM/LAN Engineering
- (1) Mr. Mike Grubbs, City of San Bernardino
- (3) Ms. Julie Lugaro, Caltrans District 8

TABLE OF CONTENTS

Page

1.	INTRODUCTION	1
2.	PURPOSE AND SCOPE OF SERVICES	1
3.	SITE DESCRIPTION	1
4.	PHYSICAL LIMITATIONS	2
5.	SAMPLE COLLECTION	2
6.	LABORATORY ANALYSES AND RESULTS	3
7.	FINDINGS AND OPINIONS 4 7.1. Asbestos 7.2. Paint	4
8.	RECOMMENDATIONS	5
9.	LIMITATIONS	5

<u>Table</u>

 Table 1 – Asbestos Survey Results

Figures

Figure 1 – Site Location Map Figure 2 – Sample Location Map

Appendices

- Appendix A Asbestos Analytical Results and Chain-of-Custody Records
- Appendix B Barr & Clark Lead-Based Paint Survey Report
- Appendix C Lead-Related Construction Certification
- Appendix D South Coast Air Quality Management District Demolition Notification

1. INTRODUCTION

In accordance with your request and authorization to proceed, Ninyo & Moore has performed an asbestos survey and has coordinated the performance of a lead-based paint (LBP) survey at the Mount Vernon Avenue Bridge (bridge) located in San Bernardino, California (Figure 1). This report has been prepared in accordance with generally accepted environmental science and engineering practices. This report is based upon conditions at the bridge at the time of the sampling activities and provides documentation of our findings and recommendations.

2. PURPOSE AND SCOPE OF SERVICES

The purpose of the survey was to evaluate the subject site for the presence of asbestos-containing materials (ACMs) and LBP. The objective of the survey was to gain information regarding site conditions to assist in the possible demolition and/or renovation activities associated with the bridge. Ninyo & Moore performed the following services:

- Performance of a visual reconnaissance of the readily accessible areas of the site to evaluate the possible presence of ACMs.
- Collection of 8 building material samples and submittal of these samples to an independent laboratory for analysis of asbestos content.
- Collection of 53 x-ray fluorescence (XRF) readings of potential LBP.
- Preparation of a site plan showing bulk sample locations.
- Preparation of this report summarizing our field activities, laboratory test results, conclusions, and recommendations.

3. SITE DESCRIPTION

The existing bridge, designated by Caltrans as Bridge No. 54-C0066, and its approaches are along Mount Vernon Avenue, between 2^{nd} and 5^{th} Streets, in San Bernardino, California (Figure 2).

The south bridge approach extends approximately 200 feet to the north from 2nd Street. The north bridge approach extends approximately 100 feet to the south from 4th Street. The bridge is an ap-



proximately 76 feet wide and approximately 1,000 feet long concrete bridge. Pipe insulation was noted on the northern portion of the bridge along the eastern and western sides. The insulation was situated near the lower edges of the bridge bottom.

4. PHYSICAL LIMITATIONS

The bridge extends over a Burlington Northern and Sante Fe (BNSF) Railroad Intermodal Facility. Ninyo & Moore could only access the northern and southern portions of the bridge underside and did not enter the BNSF yard.

5. SAMPLE COLLECTION

On April 26, 2004, Ninyo & Moore personnel conducted an asbestos survey, and Barr & Clark was contracted to conduct a LBP survey of the site. The surveys followed United States Environmental Protection Agency (EPA) guidelines, within the limitations of the scope of this survey. The asbestos survey was performed by a Cal OSHA-Certified Asbestos Consultant and consisted of collecting building materials from the bridge. The LBP survey was conducted by a California Certified Lead Paint Inspector/Assessor.

5.1. Asbestos Survey

A preliminary visual assessment and bulk-sampling survey of suspect ACMs was performed. Representative samples of the suspect ACMs were collected after identification of homogeneous sampling areas (areas in which the materials are uniform in color, texture, construction or application date, and general appearance). Each homogeneous area was observed for material type, location, condition, and friability. Representative samples were collected from each area except areas that were inaccessible, or areas of assumed ACM, within the limitations of the survey. Samples were collected using EPA-recommended sampling procedures. Building materials which were sampled and analyzed for the presence of asbestos are presented in Table 1. The locations of bulk asbestos samples are shown on Figure 2.



5.2. Paint Survey

To assess the painted surfaces portable XRF spectrum analyzer technologies were utilized. The survey was conducted in general accordance with accepted environmental science and engineering practices.

A total of 53 XRF readings were analyzed. The XRF results are in the LBP inspection report in Appendix B.

6. LABORATORY ANALYSES AND RESULTS

6.1. Asbestos Analysis

Eight samples of suspect ACMs were collected and transferred to LA Testing. LA Testing is an accredited laboratory in the National Voluntary Laboratory Accreditation Program (NVLAP) for bulk asbestos fiber analysis. The samples were analyzed using Polarized Light Microscopy with dispersion staining (PLM/Ds), for the presence and quantification of asbestos fibers, in general accordance with EPA Method 600/M4-82-020. The lower limit of reliable detection for asbestos using the PLM method is approximately 1 percent by volume. California regulations now define ACMs as those materials having an asbestos content of greater than one tenth of 1 percent (0.1 percent). Materials in which no asbestos was detected are defined in the laboratory report as "None detected." Materials containing asbestos, but in amounts less than 1 percent are defined as containing "trace" amounts. Building materials with an asbestos concentration greater than trace amounts are listed in Section 7 of this report. Suspect materials sampled and the analytical results are summarized in Table 1. A copy of the laboratory analytical report and chain-of-custody record is presented in Appendix A.

6.2. Paint Analysis

Currently, the State of California and the EPA stipulate what concentrations of lead in nonvolatile components of surface coatings or materials determine a material to be a LBP. The California Department of Public Health (CDPH) stipulates that materials containing an



amount equal to or in excess of 1 milligram per square centimeter (1.0 mg/cm²), or more than half of one percent (0.5 percent) by weight, constitute a LBP. The HUD guideline for designating a painted surface as lead containing is consistent with the DHS. Paint that is chipping or peeling, or that may be removed from surfaces, and has a lead content equal to or greater than 1,000 milligrams per kilogram (mg/kg), would require handling as a California Title 22 hazardous waste.

7. FINDINGS AND OPINIONS

7.1. Asbestos

Based on the analytical results of bulk samples collected during this survey, ACMs located at the site are as follows:

• Approximately 100 linear feet (LF) of pipe insulation, assumed to be asbestoscontaining, located on the east side of the bridge. This material was inaccessible and could not be sampled.

Please note that quantities of ACMs are approximate. These numbers should be confirmed prior to removal or repair activities.

The presence of ACMs does not necessarily mean that the health of the occupants is endangered. If these materials are in good condition and have not been disturbed or deteriorated, exposures are expected to be negligible. However, when ACM deteriorates or is disturbed or is in damaged condition, such as during demolition operations, asbestos fibers may be released creating a potential health hazard for building occupants, maintenance personnel, and contractors.

7.2. Paint

Based on the analytical results of 53 XRF samples collected during our survey, the following painted surfaces contained concentrations of lead greater than 1.0 mg/cm²:

• Metal beams and columns under the bridge.

- Concrete foundations (yellow) on the north side of bridge, under support columns.
- Concrete foundations (red) on the south side of the bridge under support columns.
- Yellow stripes on asphalt and concrete pavement in the middle of Mount Vernon Avenue.
- Red curbs along the northwest and northeast sides of Mount Vernon Avenue.
- Yellow curbs on the north and south center islands.

A copy of the LBP Survey report is presented in Appendix B. A copy of the current Lead-Related Construction Certification is presented in Appendix C.

8. **RECOMMENDATIONS**

Since ACMs and LBPs have been identified at the subject site, the following recommendations and precautions are provided:

- The identified ACMs should not be disturbed. Prior to renovation or demolition work which would disturb identified ACMs, a Cal OSHA-licensed certified asbestos abatement removal contractor should remove the ACMs.
- A Notification should be sent to South Coast Air Quality Management District (SCAQMD) 10 working days prior to any ACM removal or demolition activities as per Rule 1403. In addition the Notification should included applicable fees as per Rule 301. A copy of a SCAQMD Notification with Rule 301 fees is included in Appendix D.
- The identified LBPs should not be disturbed. Any LBPs in a non-intact condition should be abated and the component properly encapsulated. Prior to demolition work which would disturb identified LBPs, a licensed lead abatement removal contractor should remove the LBPs.
- Applicable laws and regulations should be followed, including those provisions requiring notification to building occupants, renovation contractors, and workers of the presence of asbestos and LBP.
- The OSHA regulations for construction found in Title 29 CFR part 1926 include occupational exposure to lead under the standard number 1926.62. Additional requirements are found in the California standard 8 CCR Section 1532.1. Any employer covered by these standards is obligated to initially determine if any employee may be exposed to lead at or above the action level (29 CFR 1926.62(d)(1)(i) and 8 CCR 1532.1(d)). Additionally, the employer is obligated to prepare a project specific Lead Compliance Plan (LCP) in accor-



dance with 29 CFR 1926.62 (e)(2). It is recommended that a LCP be developed and implemented for construction related activities associated with this project site.

• Per Caltrans requirements, projects involving the removal of yellow traffic striping, thermoplastic paint, must be performed in accordance with Caltrans Department Standard Special Provision (SSP) 14-001.

9. LIMITATIONS

Ninyo & Moore's opinions and recommendations regarding environmental conditions, as presented in this report, are based on limited sampling and chemical analysis. Further assessment of potential adverse environmental impacts may be accomplished by a more comprehensive assessment. The samples collected and used for testing, and the observations made, are believed to be representative of the area(s) evaluated. However, if additional suspect ACMs are encountered during demolition activities, these materials should be sampled by qualified personnel, and analyzed for content prior to further disturbance. In addition, please note that quantities of ACMs are approximate. These numbers should be confirmed prior to removal or repair activities.

The environmental services described in this report have been conducted in general accordance with current regulatory guidelines and the standard-of-care exercised by environmental consultants performing similar work in the project area. No warranty, expressed or implied, is made regarding the professional opinions presented in this report. Variations in site conditions may exist and conditions not observed or described in this report may be encountered during subsequent activities. Please also note that this study did not include an evaluation of geotechnical conditions or potential geologic hazards.

This document is intended to be used only in its entirety. No portion of the document, by itself, is designed to completely represent any aspect of the project described herein. Ninyo & Moore should be contacted if the reader requires any additional information, or has questions regarding content, interpretations presented, or completeness of this document.

The environmental interpretations and opinions contained in this report are based on the results of laboratory tests and analyses intended to detect the presence and concentration of specific





chemical or physical constituents in samples collected from the subject site. The testing and analyses have been conducted by an independent laboratory which is certified by the State of California to conduct such tests. Ninyo & Moore has no involvement in, or control over, such testing and analysis. Ninyo & Moore, therefore, disclaims responsibility for any inaccuracy in such laboratory results.

Our conclusions, recommendations and opinions are based on an analysis of the observed site conditions. It should be understood that the conditions of a site can change with time as a result of natural processes or the activities of man at the subject site or nearby sites. In addition, changes to the applicable laws, regulations, codes, and standards of practice may occur due to government action or the broadening of knowledge. The findings of this report may, therefore, be invalidated over time, in part or in whole, by changes over which Ninyo & Moore has no control.

SampleSampleID No.Location		Sample Description	Result	Approximate Quantity (SF/LF/EA)	Condition
01	Northwest on ramp wall	Sealant	None detected	Not applicable	Good
02	Northwest on ramp wall	Sealant	None detected	Not applicable	Good
03	Northwest on ramp wall	Sealant	None detected	Not applicable	Good
04	Northwest wall	Stucco	None detected	Not applicable	Good
05	Northwest wall	Stucco	None detected	Not applicable	Good
06	Southwest wall	Stucco	None detected	Not applicable	Good
07	Southwest wall	Stucco	None detected	Not applicable	Good
08	Southwest wall	Stucco	None detected	Not applicable	Good

 Table 1 – Asbestos Survey Results





APPENDIX A

ASBESTOS ANALYTICAL RESULTS AND CHAIN-OF-CUSTODY RECORDS

~ 7

<u>ر</u> م

159 Pasadena Avenue, South Pasadena, CA 91030

Phone: (323) 254-9960 Fax: (323) 254-9982 Email: pasadenaiab@latesting.com



د ب Attn: Dana Williams Customer ID: 32ninm50 Ninyo & Moore Customer PO: 475 Goddard ٦ ٦ Received: 04/27/04 9:00 AM Suite #200 Irvine, CA 92618 ت ت Fax: (949) 753-7071 Phone: (949) 753-7070 LA Testing Order 320404307 ~ T Project: 205732001/Mt. Vernon LA Testing Proj: Analysis Date: 4/27/2004

Asbestos Analysis of Bulk Materials via EPA 600/R-93/116 Method using Polarized Light Microscopy

					Non-As	sbestos	Asbestos
ample	Location	Appearance	Treatment	%	Fibrous	% Non-Fibrous	% Type
1 320404307-0001	nw side	Gray Non-Fibrous Homogeneous	Crushed			100% Matrix	None Detected
2 320404307-0002	nw side	Gray Non-Fibrous Homogeneous	Crushed			100% Matrix	None Detected
3 320404307-0003	nw side	Gray Non-Fibrous Homogeneous	Crushed			100% Matrix	None Detected
4 320404307-0004	nw side	Gray Non-Fibrous Homogeneous	Crushed	<1%	Celluiose	100% Matrix	None Detected
5 320404307-0005	nw side	Gray Non-Fibrous Homogeneous	Crushed	<1%	Celluiose	100% Matrix	None Detected
5 320404307-0006	sw side	Gray Non-Fibrous Homogeneous	Crushed	<1%	Cellulose	100% Matrix	None Detected
7 320404307-0007	sw side	Gray Non-Fibrous Homogeneous	Crushed	<1%	Cellulose	100% Matrix	None Detected
8	sw side	Gray Non-Fibrous Homogeneous	Crushed			100% Matrix	None Detected

- .

Analyst(s)

Rafik Vartanian, Ph.D (8)

or other approved signatory

Due to magnification limitations inherent in PLM, asbestos fibers in dimensions below the resolution capability of PLM may not be detected. Samples reported as <1% or none detected may require additional testing by TEM to confirm asbestos quantities. The above test report relates only to the items tested and may not be reproduced in any form without the express written approval of EMSL Analytical, Inc. EMSL's liability is limited to the cost of analysis. EMSL bears no responsibility for sample collection activities or analytical method limitations. Interpretation and use of test results are the responsibility of the client.

Analysis performed by LA Testing (NVLAP #200232-0)

THIS IS THE LAST PAGE OF THE REPORT.

ate: bur Name: bur N	LA TESTING - Bill To: Name: Company: Address: City, State Zip:	
one Results To: x Results To: (949) 753-7071	Purchase Order #: LA TESTING SALES REP:	Ray Zarabi
/	05732001	
Requested Analysis: Place (x)		
ASBESTOS RISH 61H	12 HR 24 HR 48 HR 72 HR	5 DAY > 6 DAYS
TEM AIR	and have a second s	an internet internet of a constrained in the second
EPALENELII *** AHERA ***		
NIOSH 7402 ***		
PCM AIR	<u></u>	
NIOSH.OSHA		
PLM BULK	<u> </u>	
ERAVINITARIC		
		MALYSCEP MALYSCEP MG BY
TEM BULK		ALLS CPT
Chattielde Gravimetrie		NG BL
Microvac (ASIM) Microvac (gualitative)		
Wibes/failalitative) Wibes (guapitative)		
TEM -WATER		ŢŢŢŢŢŢŢ
Waste Water, Sludge		
TEAD RUSH 6HR	12 HR 24 HR 48 HR 72 HR	5 DAY > 6 DAYS
LEAD RUSH 6 HR		5 011 × 0 0115
FLAME AA		

yo & Moore Goddard, S ne, CA 9261 (949) 753-7070 (949) 753-7071	uite 200 3		ame: M+, し o.: この57? anager:		3		-	Laboratory しんてとら Tel: Fax:	1		
	OY INFORMATION:		Company	Date	Time⊡(24 hr.)	T	Received By: (sign/prin	nt)	Laboratory		
Hate de	$= \cap i$	(aus	Ninyo&Moore	4/26/0							
20000				<u> </u>			1				
LabID	Sample ID	Building Number		Sample Location	on	Sample Description		Quantity (SF/LF/EA)	Friable (Y/N)	Condition	
			North West Side		de	(Or	Calories				
	2										
	3		F								
	4		North	North West Side			1110				
	5			ł			[S			
	6		South	West 4	ride		14	E DR			
	7			1				KS IN IS			
	B					Ň	₩	116	270		
								By	, D		
									·		

APPENDIX B

BARR & CLARK LEAD-BASED PAINT SURVEY REPORT



~ ~

_ .

ر – ز ـ

<u>ر</u> - ۲

. .

_ _

. . - .

_ _

Έ.

. .

LEAD-BASED PAINT INSPECTION REPORT

OF

MT. VERNON AVENUE BRIDGE SAN BERNARDINO, CA

PROJECT NO. 240473

APRIL 26, 2004

MAY 3 2014

RECEIVED

NINYO & MOONE **ORANGE COUNTY OFFICE**

Prepared For: Ninyo and Moore 475 Goddard, Suite 200 Irvine, CA 92618

Prepared By:

Alex Romani State of California Certified Lead Inspector / Risk Assessor



Reviewed By:

Matt Crochet State of California Certified Lead Inspector / Risk Assessor

22850 Crenshaw Blvd., • Suite 200 • Torrance, California 90505 (310) 517-0805 • Fax: (310) 517-0822

TABLE OF CONTENTS

DESCRIPTION

÷,

бŊ

- 1

ر ب ا

C 3

. .

- -

- -

2.

• •

. .

. .

- .

. .

•

. .

PAGE NO.

1.0	INTRODUCTION
2.0	SCOPE OF WORK
3.0	INSPECTOR'S QUALIFICATIONS
4.0	TESTING PROTOCOL
5.0	METHOD OF TESTING4
6.0	SUMMARY OF RESULTS
7.0	RECOMMENDATIONS
8.0	INSPECTION LIMITATIONS

APPENDICES

APPENDIX A	SUMMARIES
	LEAD CONTAINING COMPONENTS LIST
APPENDIX B	XRF FIELD DATA
APPENDIX C	INSPECTOR'S CERTIFICATE(S)
	EQUIPMENT TRAINING CERTIFICATE(S)
	INSURANCE CERTIFICATE

 \mathbf{i}

١.

Project No. 240473

BARR & CLARK • 22850 Crenshaw Blvd., • Suite 200 • Torrance, California 90505 • (310) 517-0805 • Fax: (310) 517-0822

. .

73

- -

- -

~ Ŋ

e 14

. .

- -

- .

. .

. .

LEAD-BASED PAINT INSPECTION REPORT

1.0 INTRODUCTION

This report presents the results of Barr & Clark Environmental's lead-based paint (LBP) inspection of the Mt. Vernon Avenue Bridge located in San Bernardino, California (Subject Property). This document is prepared for the sole use of Ninyo and Moore, and any regulatory agencies that are directly involved in this project. No other party should rely on the information contained herein without prior written consent of Ninyo and Moore. The scope of services, inspection methodology, and results are presented below.

2.0 SCOPE OF WORK

The purpose of this inspection is to identify and assess the Lead-Based Paint (LBP) present on painted components at the subject property.

On April 26, 2004, Barr & Clark performed an inspection for lead-based paint at the subject property in San Bernardino, California. To comply with EPA and HUD guidelines, painted and varnished surfaces on every accessible surface were sampled for the presence of LBP. The intent was to ascertain the presence of lead-based paint above the federal action level. If LBP was found, the inspection would identify individual architectural components and their respective concentrations of lead in such a manner that this report would be used to characterize the presence of LBP at this property.

3.0 INSPECTOR'S QUALIFICATIONS

Matt Crochet of Barr & Clark performed the inspection at the site using an RMD LPA-1 XRF spectrum analyzer instrument. He has attended the radiation safety course for handling the instrument, and completed an EPA approved curriculum in Lead in Construction Inspector / Risk Assessor Training.

At the time of this report, the California Department of Health Services, Childhood Lead Poisoning Branch, has implemented a State Certification Model Accreditation Plan adopted from the EPA. Matt Crochet has received certification. Personnel certificate(s) have been provided in *Appendix C*.

4.0 TESTING PROTOCOL

XRF Testing: Testing of the painted surfaces was patterned after the inspection protocol in Chapter 7 of the <u>HUD Guidelines for the Evaluation and Control of Lead-Based Paint Hazards in Housing</u>ⁱ. In every "room equivalent" within the tested property, one representative surface of each "testing combination" was tested. Multiple readings were collected to resolve inconsistencies in the test results.

<u>Regulatory Compliance:</u> Several public (government) agencies have a published "regulatory action level" to classify LBP. To further complicate matters, some of the established "levels" are quantified in

ر ۔ ر

~ ٦

. .

ر ب

_ /

- -

- /

. .

different units of measurement. Listed below are the current regulatory agencies that have defined LBP, along with the respective action level:

Agency	Ordinance #	Action level (mg / cm ²)	Action level (ppm ⁱⁱ)
HUD / EPA	24 CFR 35.86 & 40 CFR 745.103	$1.0 \text{ mg} / \text{cm}^2$	5,000 ppm
OSHA / CAL OSHA	29 CFR 1926.62 & Title 8, 1532.1	Not Specified	600 ppm ⁱⁱⁱ

HUD / EPA have recently issued the following guidance regarding units of measurement for paint samples:

"Report lead paint amounts in mg/cm² because this unit of measurement does not depend on the number of layers of non-leadbased paint and can usually be obtained without damaging the painted surface. All measurements of lead in paint should be in mg/cm², unless the surface area cannot be measured or if all paint cannot be removed from the measured surface area. In such cases, concentrations may be reported in weight percent (%) or parts per million by weight (ppm)."^{iv}

Furthermore, EPA has previously issued guidance on lead content classification as follows:

"... The rule, at 24 CFR 35.86 and 40 CFR 745.103 states that a lead-based paint free finding must demonstrate that the building is free of 'paint or other surface coatings that contain lead in excess of 1.0 milligrams per square centimeter $(1.0 \text{ mg} / \text{cm}^2)$ or 0.5 percent by weight (5000 ppm).' The State standards are not applicable, whether more or less stringent, since a State cannot amend Federal requirements."

In recognition of the various action levels the testing results are classified as follows for this report:

- Painted surfaces with readings at or above 1.0 mg / cm² are considered Positive
- Painted surfaces with readings at or below 0.9 mg / cm² are considered Negative

The individual readings have been provided on all field data sheets. Any future change in action levels by one of the regulating agencies may affect the classification of results.

5.0 METHOD OF TESTING

<u>Paint Testing:</u> The method employed was X-ray fluorescence (XRF) using a Radiation Monitoring Device Lead Paint Analyzer (RMD LPA-1). The instrument was operated in "Quick Mode," where the duration for each test result is determined by a combination of:

- the actual reading relative to the designated action level;
- the age of the radioactive source; and
- the substrate on which the test was taken.

The instrument's calibration was verified according to the manufacturer's specifications in compliance with the Performance Characteristic Sheet (PCS) developed for this instrument.

The readings from this instrument produce a 95% confidence level that the "lead" reading accurately reflects the actual level of lead in the tested surfaces, relative to the federal action level.

B

6.0 SUMMARY OF RESULTS

<u>Paint Sampling:</u> Throughout the subject property, several of the painted components indicated the presence of lead-based paint (LBP) at or above the action level. The following summary lists the specific components that tested above the action level and their respective locations:

<u>Bridge Bottom</u>

- -

۲ ک ر _ ک

_ /

ر ب

- 1

د ب

r .

~ .

- -

- -

- Metal beams and columns under the bridge
- Concrete foundations (yellow) on the north side under support columns
- Concrete foundations (red) on the south side under support columns

<u>Bridge Top</u>

• Yellow concrete and asphalt stripes in the middle of the road

)

1

- Red curbs along the street on the northeast and northwest sides
- Yellow curbs on the north and south center islands

Sampling for this inspection was representative and any components that were not tested but similar to those components that tested positive for LBP should be considered and treated as lead laden.

7.0 RECOMMENDATIONS

The greatest potential for lead exposure from lead painted architectural components occurs when:

- the paint has become defective; or
- when the paint is applied to a friction / impact component where the paint is continually disturbed; or
- when the paint is disturbed through routine maintenance or renovation activities.

With this in mind, the following are our recommendations for this property:

- <u>The results from this inspection should be provided to any individuals that may disturb the painted</u> surfaces. It is encouraged to utilize professionals that have experience working with LBP.
- If renovation is scheduled in the near future (less than three months), all lead painted components that have been previously targeted for replacement should be replaced utilizing "lead safe" containment and work practices.
- ALL components that have been identified with defective lead paint should have the paint repaired as soon as possible. Any paint repair should be done utilizing "lead safe" containment, work practices, and clean-up techniques.
- All components with lead painted friction / impact surfaces should be treated to minimize the friction or impact as necessary.
- Lead painted components that have not been targeted for replacement should either be considered for abatement (replacement, enclosure, encapsulation, etc.) or included in an Operations & Management (O & M) Plan that will help to minimize exposures to lead hazards.

240473

• All lead painted surfaces that are not expected to be impacted in the near future (less than three months) should also be included the O & M plan.

Page 5 of 6

BARR & CLARK • 22850 Crenshaw Blvd., • Suite 200 • Torrance, California 90505 • (310) 517-0805 • Fax: (310) 517-0822

8.0 INSPECTION LIMITATIONS

This inspection was planned, developed, and implemented based on Barr & Clark's previous experience in performing lead-based paint inspections. This inspection was patterned after Chapter 7 of the *HUD Guidelines for the Evaluation and Control of Lead-Based Paint Hazards in Housing (1997 Revision)*. Barr & Clark utilized state-of-the-art-practices and techniques in accordance with regulatory standards while performing this inspection. Barr & Clark's evaluation of the relative risk of exposure to lead identified during this inspection is based on conditions observed at the time of the inspection. Barr & Clark cannot be responsible for changing conditions that may alter the relative exposure risk or for future changes in accepted methodology. Enclosed are the diagram(s), actual test results, and all relevant certifications and licenses.

i 1997 Revision

u.J

. . .

iii Applies to construction related activities

iv Chapter 7 of the HUD Guidelines for the Evaluation and Control of Lead-Based Paint Hazards in Housing (1997 Revision).

v Office of Pollution Prevention and Toxics, (August 20, 1996)

ii Parts per million

SUMMARY OF EXTERIOR

Project Name: Mt. Vernon Avenue Bridge Address:

- -

2

- 1 - 1

- 1

- 1

. .

. .

()

Project Number: 240473

.

j

Component		Number Tested	Number Positive	Percent Positive	Number Negative	Percent Negative	
Asphalt Stripe		6	2	33.33%	4	66.67%	
Concrete Column		5			5	100.00%	
Concrete Curb		12	9	75.00%	3	25.00%	
Concrete Foundation		5	5	100.00%		·····	
Concrete Railing		2			2	100.00%	
Concrete Stripe		3	3	100.00%			
Metal Beam		4	4	100.00%			
Metal Column		4	4	100.00%			
Metal Post		4			4	100.00%	
Metal Sign		1			1	100.00%	
Metal Wall		3			3	100.00%	
Stucco Wall	•	4			4	100.00%	
	Totals:	53	27		26		

Testing done in compliance with current HUD guidelines for XRF.

LEAD CONTAINING COMPONENTS LIST

()

1

....

Exterior Lead Containing Components List

Project Name: Mt. Vernon Avenue Bridge Address:

Project ID: 240473

Sample	Side	Testing Combination	Room Equivalent	Lead	Results	Condition	Comments
34	24 25 26 27	AsphaleStupe	Bride rige	s ** 12 -	POSITIME 1	DAMAGEE	PXEIIOW
- 33	2000 2000	AsphalkShipe	Bridge Fog	. 17 J	POSITIVE	DAMAGEE	Yellow
4 1	Ň	Concrete Ourb	aBridge Vop	<u>1.</u> 0	POSITIVE	DAMAGEE	Red Nonthwest
44	Ň	ConcreteCurb	Bridge Top	15	POSITIVE	DAMAGE	Red-Nontwest
45	N	Concrete Curb		 \$.6.	2		Red Northwest
46	Ne:	Concrete:Ourb	Badge 100	16	Cardena and the second second second		Nellow Center Slands
47	Ň	Concrete Curb	Bridge Fog	12.		A STATE OF A STATE OF A	Yellow Center Island
40	Ň	Concrete Curb	Bridge Top	27	POSITIVE	DAMAGEE	Red - Northeast
49	S	Concrete Curb	Bridge Top	22	POSITIVE	Intact	Yellow - Center Island
50	S	Concrete:Curb.	Bidge 1002	1.1.70	POSITIVE	Intact	Yellow - Center Island
51	S	Concrete Curb	Budgestop	44	POSITIVE	Intact	Yellow - Center Island
7	N	Concrete Foundation:	Bridge Bonom	15	ROSITIVES	Intact	Yellow
8	. N	Concrete Foundation	Bridge Bottom	- 20	POSITIVE	Intact	Yellow
9	<u>N</u>	Concretes oundation	Service Bottom Association and Association	16	POSITIVE	Intact	Yellow
20	S.		Bridge Bollom	- 212	POSITIVE		
19***	S	Concrete Foundation	Bridge Bottom	16	POSITIVE	DAMAGEE	Red
		Concrete Stripe	Bidge Pøp	6.9	12 Contraction of the South States	A D. C	Yellow Middle of the Road
26		Concrete Stripe	ere : Stridge Top	9.2	POSITIVE	DAMAGÈE	Pelicw Middle of the Road
. 24		Concrete Stripe	Bridge Top	8.6	POSITIVE	DAMAGEE	Yellow - Middle of the Road

The HUD action level for lead-based paint is 1.0 mg/cm2. Positive is defined as XRF sampling with levels at or above 1.0 mg/cm2.

Metal Beam

MetaPBeam

Rottem

18:0 POSITIVE DAMACED Orange Primer

FIELD DATA REPORT

Project Name: Mt. Vernon Avenue Bridge

Address:

Project Number: 240473 Protocol: HUD

Sample	Unit ID / Location	Room Equivalent	Side	Component	Substrate	Condition	Lead	Results	Comments
1	Bridge	Exterior Bottom	N	Wall	Stucco	Intact	0.7	Negative	Northwest
2			N	Wall	Stucco	Intact	0.3	Negative	Northwest
3			í N	Column	Metal	DAMAGED	46 0×.,	POSITIVE	Orange Brimers
			N	Column	Metal	DAMAGED	5.14:0	POSITIVE	
5			N	Beam	Mejal	DAMAGED	18.0	- ROSITIVE	-Orange Erimet
6	a in frankriger og sinder af s Af sinder af			Beam		DAMAGED	15 0	POSITIVE	Orange Frimer
7			1. South - 1	Foundation:	Concrete	'fftadt 🔅 🦂	P5.	ROSITIVE	Yellow
8		<u> </u>	ST MACHINE STRUCT	H-oundation // ca	of the second second second second second as the second second second second second second second second second	Intacted (1. 1.	2.0	ROSIUVE	22,94
9			power de consecutor	alfoundations at	Mass Concreter	and the second of the second	(16)	CPOSHINE'	254
10			S	Wali	Stucco	DAMAGED	0.6	Negative	Southwest
11			S	Wall	Stucco	DAMAGED	0.7	Negative	Southeast
12			51. 14 S.C.	Cqiumn		DAMAGED	. 12 .04		A Oranse Primer
13			10	Column'	CALLER AND A CONTRACT OF A CON	DAMAGED		POSIRME	ClangePinner
14			S	Beam	Meial	DAMAGED	-18,0		OlangesPrimer
				Beam	Metal	DAMAGED	270	POSITIVE.	The state of the s
16			<u> </u>	Column	Concrete	Intact	0.2	Negative	Grey
17			S	Column	Concrete	Intact	0.1	Negative	Grey
18	a la tra a Maria de Maria de la completa a National de la completa de la completa de la completa de la completa	and a second state of the	S	Column	Concrete	Intact	0.1	Negative	
9			S	Foundation.	INVERTA CONTRACTOR AND A MARCHINE AND A MARCHINE AND THE	THE ALL READER AND ALL DR. THE		PEOSITIVE	
			S. 1. 1. 1. 1. 1. 1. 1. 1. 1. 1. 1. 1. 1.	A STATE OF A	Concrete	The second s	• FZ		Red
21		Exterior Top		Wall	Metal	Intact	0.5	Negative	Metal Plates on Railings - Grey
22				Wall	Metal	Intact	0.2	Negative	Metal Plates on Railings - Grey
23				Wali	Metal	Intact	0.1	Negative	Metal Plates on Railings - Grey
24				Stripe	Conclete*	ANALY AND	8.6	ROSITIME	YellowsMidulefortherRoad
25				Stipe	Concrete	DAMAGED	69	POSITIVE	Yellow-Middle of the Road
26				Stripe	Concrete	DAMAGED	-9.2	ROSINVE	and the second second on the selected second sec
27				Column	Concrete	DAMAGED	0.2	Negative	Grey
28				Column	Concrete	DAMAGED	0.2	Negative	Grey
29				Stripe	Asphalt	DAMAGED	0.3	Negative	Yellow
30				Stripe	Asphalt	DAMAGED	0.5	Negative	White
31				Stripe	Asphalt	DAMAGED	0.4	Negative	White
32				Stripe	Asphalt	DAMAGED	0.5	Negative	White
1999 - 2 39 24				Stripe	COMORAL CONTRACTOR STATES AND A STATES	DAMAGED	21 Z	POSITIVE	
34	And the second second			Stupe	Asphalte	DAMAGED	5 L 2	POSITIVE	Yellow

The HUD action level for lead-based paint is 1.0 mg/cm2. Positive is defined as XRF sampling with levels at or above 1.0 mg/cm2.

FIELD DATA REPORT

Project Name: Mt. Vernon Avenue Bridge

-

Address:

Project Number: 240473 Protocol: HUD

Sample	Unit ID / Location	Room Equivalent	Side	Component	Substrate	Condition	Lead	Results	Comments
35	Bridge	Exterior Top		Post	Metal	Intact	0.2	Negative	Light
36				Post	Metal	Intact	0.4	Negative	Light
37				Post	Metai	Intact	0.4	Negative	Light
38			N	Railing	Concrete	DAMAGED	0.3	Negative	Northwest - 1934
39			N	Railing	Concrete	DAMAGED	0.4	Negative	Northwest - 1934
40			Ň	Curb	Concrete	DAMAGED	27	POSITIVE	Red Montheast
41			N	Cutor	Concrete	DAMAGED	. 10	POSITIME	Red - Northwest
42			Ń	Post	Metal	Intact	0.2	Negative	Sign Post - Green - Northeast
43			N	Sign	Metal	Intact	0.5	Negative	Rediscover Downtown
44			N.	Curb	Concrete: A	DAMAGED	515	ROSHIVE	Reg Northwest Reg Northwest Reg Avenue Reg Northwest Reg Avenue Reg Reg Reg Reg Reg Reg Reg Reg Reg Re
45			† N P	TCUM	Condrete=	DAMAGED	- 116 M	ROSILWE	Red Nothwest The Lite
46			N.	Curb .	Concrete	DAMAGED.	1.6	ROSIUME	Yellow Center/sland
47			2 N	Curb	Concrete	DAMAGED	51.2	POSITIVE	Yellow Center Island.
48			N	Curb	Concrete	DAMAGED	0.4	Negative	White - Center Island
49			S	Curb.	Concrete a second second	intaci 👌	2.2.*	POSITIVE	Yellow - Center Island
50			S	Curb	ser - ser Condictor	Interest ***	7.0	POSITIVE:	Yellow - Center Island
51			S	Curb And A	ss. dz. « Concrete	lintaet See a	4.4	POSITIVE	Yellow - Center Island
52			S	Curb .	Concrete	Intact	0.4	Negative	White - Center Island
53			S	Curb	Concrete	Intact	0.2	Negative	White - Center Island

The HUD action level for lead-based paint is 1.0 mg/cm2. Positive is defined as XRF sampling with levels at or above 1.0 mg/cm2.

UNIVERSITY OF CALIFORNIA UNIVERSITY EXTENSION, DAVIS

Western Regional Lead Training Center

IN RECOGNITION THAT

Matt Crochet

HAS ATTENDED THE FOLLOWING PROGRAM

EPA-Sponsored Lead Inspectors Training March 14 - 16, 1994



Passed final exam Certificate Number 1078

Lead Abatement Program Manager

Pertificate of Achievement

This is to certify that

Matt Crochet

on the 28th day of January 2000 successfully completed the factory training for

RMD's LPA-1 Lead Paint Inspection System

including, but not limited to, the topics of Radiation Safety and the Proper Use of the Instrument.

Jacob Paster, Vice President, RMD 44 Hunt St., Watertown, Massachusetts

Exterior Lead Containing Components List

Project Name: Mt. Vernon Avenue Bridge Address:

Project ID: 240473

Sample	Side	Testing Combination	Room Equivalent	Lead	Results	Condition	Comments
34	24 25 26 27	AsphaleStupe	Bride rige	s ** 12 -	POSITIME 1	DAMAGEE	exellow -
- 33	2000 2000	AsphalkShipe	Bridge Fog	. 17 J	POSITIVE	DAMAGEE	Yellow
41	Ň	Concrete Ourb	aBridge Top	<u>t</u> o	POSITIVE.	DAMAGEE	Red Nonhwest
44	Ň	ConcreteCurb	Bridge Top	15	POSITIVE	DAMAGE	Red-Nontwest
45	N	Concrete Curb		 \$.6.	2		Red Northwest
46	Ne:	Concrete:Ourb	Badge 100	16	Cardena and the second second second		Nellow Center Slands
47	Ň	Concrete Curb	Bridge Fog	12.		A STATE OF A STATE OF A	Yellow Center Island
40	Ň	Concrete Curb	Bridge Top	27	POSITIVE	DAMAGEE	Red - Northeast
49	S	Concrete Curb	Bridge Top	22	POSITIVE	Intact	Yellow - Center Island
50	S	Concrete:Curb.	Bidge 1002	1.1.70	POSITIVE	Intact	Yellow - Center Island
51	S	Concrete Curb	Budgestop	44	POSITIVE	Intact	Yellow - Center Island
7	N	Concrete Foundation:	Bridge Bonom	15	ROSITIVES	Intact	Yellow
8	. N	Concrete Foundation	Bridge Bottom	- 20	POSITIVE	Intact	Yellow
9	<u>N</u>	Concretes oundation	Service Bottom Association and Association	16	POSITIVE	Intact	Yellow
20	S.		Bridge Bollom	- 212	POSITIVE		
19***	S	Concrete Foundation	Bridge Bottom	16	POSITIVE	DAMAGEE	Red
		Concrete Stripe	Bidge Pøp	6.9	12 Contraction of the South States	A D. C	Yellow Middle of the Road
26		Concrete Stripe	ere : Bridge Top	9.2	POSITIVE	DAMAGEE	Pelicw Middle of the Road
. 24		Concrete Stripe	Bridge Top	8.6	POSITIVE	DAMAGEE	Yellow - Middle of the Road

The HUD action level for lead-based paint is 1.0 mg/cm2. Positive is defined as XRF sampling with levels at or above 1.0 mg/cm2.

Metal Beam

MetaPBeam

Rottem

18:0 POSITIVE DAMACED Orange Primer

Exterior Lead Containing Components List

2

. .

Project Name: Mt. Vernon Avenue Bridge Address:

÷

Project ID: 240473

2

Sample	Side	Testing Combination	Room Equivalent	Lead	Results	Condition	Comments
15		Metal Beam	BridgetBottom	27.0	POSITIME	DAMAGED	Orange Primers
	ŝ	Metal Beam	Endge#Bottom	18 0	ROSINVE	DAMAGED	Crange Primer.
3	Ň	Metal Column	Bridge Bottom	16.0	ROSITIVE	DAMAGED	Orange Rumes
<u>a</u>	Ň	Metafcolumn	Bridge Bottom	1/4-0	POSITIVE	DAMAGED	Crange Rumer
<u></u>	ŝ	-Metal Column	- Budge Bottom	12.0	POSITIVE	DAMAGED	
	Č.	Motal Column	Burge Bettern	120	POSITIVE	DAMAGÊD	
		- WASTON SOUTHING					

The HUD action level for lead-based paint is 1.0 mg/cm2. Positive is defined as XRF sampling with levels at or above 1.0 mg/cm2.

FIELD DATA

•

· · · ·

• · · • · • ·

:)

• •

C 3

11

.

FIELD DATA REPORT

Project Name: Mt. Vernon Avenue Bridge

Address:

Project Number: 240473 Protocol: HUD

Sample	Unit ID / Location	Room Equivalent	Side	Component	Substrate	Condition	Lead	Results	Comments
1	Bridge	Exterior Bottom	N	Wall	Stucco	Intact	0.7	Negative	Northwest
2			N	Wall	Stucco	Intact	0.3	Negative	Northwest
			(N	Column	Metal.	DAMAGED	(16 0×.,	NPOSITIVE.	Octore Entries
and a start			N	Column	Metal	DAMAGED	5.14:0	POSENE	The party of the p
5			N	Beam	Mejal .	EDAMAGED R	18.0	POSITIVE	Crange Rrimer
6	a in frank a star a		5-1-1-1-1-1-1-1-1-1-1-1-1-1-1-1-1-1-1-1	Beam	Wetai	DAMAGED	15 0	POSITIVE	Orange Primer
7			1. South - 1	Foundation	Concrete	thtadt	/n¶?5	ROSITIVE	Yellow
			ST HALF HE ST HALF	Proundation 2005	a ser a vers average a state of the second secon	Sintacted as a	2,0	ROSITIVE	25,202
9			power de consecutor	de ourreation de la company	e aconcreter		(16)	SPOSITIVE	22:
10			S	Wali	Stucco	DAMAGED	0.6	Negative	Southwest
11			S	Wall	Stucco	DAMAGED	0.7	Negative	Southeast
12			S	Column	TO DEFENSE THE REPORT OF THE PARTY OF THE PA	DAMAGED	. 12 .04		volance Finter
11 A A A A A A A A A A A A A A A A A A			10	Column'	The second se	DAMAGED		ROSINNER	MolangelRrimer
14			S	Beam	Metal	DAMAGED	-18,0		Orange Enmer
				Beami	Metalway	DAMAGED	270	POSITIVE.	A STATE OF A
16			<u> </u>	Column	Concrete	Intact	0.2	Negative	Grey
17			S	Column	Concrete	Intact	0.1	Negative	Grey
18	and a second	vaneration of the Control of the American State of the Van Van Van State and the State of the State of the State	S	Column	Concrete	Intact	0.1	Negative	
.			S. S.	Foundation	INVERTAL STATE OF THE AREA TO THE PARTY OF THE	a set of the part of the set of the			Red
				A REAL PROPERTY AND A REAL	Concrete	A CONTRACT OF THE OWNER OF	• F2		Rep
21		Exterior Top		Wall	Metal	Intact	0.5	Negative	Metal Plates on Railings - Grey
22				Wall	Metal	Intact	0.2	Negative	Metal Plates on Railings - Grey
23	ada 11 14 1.94 Mar 4.94 - 1964 - 1.966 - 1666 - 1666 - 1666	an an an the second and the second and the second	and the Barrist Institute and a second	Wall	Metal	Intact	0.1	Negative	Metal Plates on Railings - Grey
24				Since	Concrete*	- MARADON - NO CARDENTAL	8.6	ROSINE	Yellow Mittle of the Road
25				Stupe	Concrete	DAMAGED	69	POSHINE	Yellow-Middle of the Road
26				Stripe	Concrete:	DAMAGED	92	ROSHWE	and an exception of the set of the
27				Column	Concrete	DAMAGED	0.2	Negative	Grey
28				Column	Concrete	DAMAGED	0.2	Negative	Grey
29				Stripe	Asphait	DAMAGED	0.3	Negative	Yellow
30				Stripe	Asphalt	DAMAGED	0.5	Negative	White
31				Stripe	Asphalt	DAMAGED	0.4	Negative	White
32	Table 1 and 1 a	1		Stripe	Asphalt	DAMAGED	0.5	Negative	White
38				Stripe	A REAL AND A CASE AND A DECK AND A DECK	DAMAGED	41 7	POSINVE	
34				Stupe	Asphalt	DAMAGED	5 C 2	POSITIVE	Yellow

The HUD action level for lead-based paint is 1.0 mg/cm2. Positive is defined as XRF sampling with levels at or above 1.0 mg/cm2.

FIELD DATA REPORT

Project Name: Mt. Vernon Avenue Bridge

-

Address:

Project Number: 240473 Protocol: HUD

Sample	Unit ID / Location	Room Equivalent	Side	Component	Substrate	Condition	Lead	Results	Comments
35	Bridge	Exterior Top		Post	Metal	Intact	0.2	Negative	Light
36				Post	Metal	Intact	0.4	Negative	Light
37				Post	Metai	Intact	0.4	Negative	Light
38			N	Railing	Concrete	DAMAGED	0.3	Negative	Northwest - 1934
39			N	Railing	Concrete	DAMAGED	0.4	Negative	Northwest - 1934
40			N-	Curb	Concrete	DAMAGED	27	POSITIVE	Red Montheast
41			N	Curpy	Concrete	DAMAGED	. 10	POSITIVE	Red - Northwest
42			Ń	Post	Metal	Intact	0.2	Negative	Sign Post - Green - Northeast
43			N	Sign	Metal	Intact	0.5	Negative	Rediscover Downtown
× 144 ×			ne se NL	Curb	Concrete: Concrete: Max	DAMAGED	515	POSITIVE	Reg Northwest Reg Northwest Reg Avenue Reg Northwest Reg Avenue Reg Reg Reg Reg Reg Reg Reg Reg Reg Re
45			÷N.	ТСОТВ	Concrete	DAMAGED	1.6	S. POSITIVE:	Red Nothwest The Lite
46			N.	Curb	Concrete	ADAMAGED	1.6	POSITIME	Yellow Center/sland
47			N.	Curb : 🐨	Concrete	DAMAGED	-12	POSTIVE	Yellow Center Island.
48			N	Curb	Concrete	DAMAGED	0.4	Negative	White - Center Island
49			S	Cùrb	concrete	lintaci 🔥 👯	2.2	ROSITIVE	Yellow - Center Island
50			Set Set	Cuthanter	sea the Sepheretes set	Intact of the	× 720	POSITIVE	Yellow - Center Island
51			S	Curb Andra A	es als e Concrete	liniaet 🗧 🧃	4.4.	ROSITIVE	Yellow - Center Island
52			S	Curb .	Concrete	Intact	0.4	Negative	White - Center Island
53			S	Curb	Concrete	Intact	0.2	Negative	White - Center Island

The HUD action level for lead-based paint is 1.0 mg/cm2. Positive is defined as XRF sampling with levels at or above 1.0 mg/cm2. STATE OF CALIFORNIA-HEALTH AND HUMAN SERVICES AGENCY

DEPARTMENT OF HEALTH SERVICES CHILDHOOD LEAD POISONING PREVENTION BRANCH 1515 Clay Street, Suite 1801 OAKLAND, CA 94612 (510) 622-5000

May 16, 2001

.1

Mr. Matthew P. Crochet

Dear Mr. Crochet:

Your California Department of Heaith Services (DHS) Lead Certificate(s) has been renewed. <u>Please note that your expiration date(s) changed.</u> From this point forward it will be your date of birth.

Type of Certificate	Certificate ID #	Expiration Date
Project Monitor	M-12	06/13/2002 > SEE 06/13/2002 > BELOW
Inspector/Assessor	I-12	06/13/2002 BELOW

The enclosed certificate card serves as your proof of certification renewal by the Department. Please note that alteration of any information or fraudulent use of your card may result in revocation of your certificate. If your card is lost, stolen or inaccurate please notify DHS immediately. Cut up or destroy your old card when your certificate expires.


To ensure that your certificate is renewed before it expires, please submit your next renewal application to the Department at least 120 days before the expiration date(s) above. Call the Lead Related Construction Information Line at 1-800-597-5323 for renewal forms and instructions. (From outside California, call (510) 622-5072.) You may also obtain forms at our website: www.dhs.ca.gov/childlead.


If you change your home or mailing address, please notify the Department within 30 days by calling 1-800-597-5323 or by writing to us at 1515 Clay Street, Suite 1801, Box C, in Oakland, California, 94612. If you fall to notify us of changes in your address, we will be unable to send your certification materials in the future. Thank you for your cooperation and continued efforts in helping to prevent childhood lead poisoning.

Sincerely,

Varrie L. Lance, Dr/P.H., R.E.A., Chief Lead Hazard Reduction Section Childhood Lead Poisoning Prevention Branch

Enclosure







UNIVERSITY OF CALIFORNIA UNIVERSITY EXTENSION, DAVIS

Western Regional Lead Training Center

IN RECOGNITION THAT

Matt Crochet

HAS ATTENDED THE FOLLOWING PROGRAM

EPA-Sponsored Lead Inspectors Training March 14 - 16, 1994



Passed final exam Certificate Number 1078

Lead Abatement Program Manager

Pertificate of Achievement

This is to certify that

Matt Crochet

on the 28th day of January 2000 successfully completed the factory training for

RMD's LPA-1 Lead Paint Inspection System

including, but not limited to, the topics of Radiation Safety and the Proper Use of the Instrument.


Jacob Paster, Vice President, RMD 44 Hunt St., Watertown, Massachusetts

	MAR-12-04 11:23AM FRO		7		T-217 P.002/00	2 F-588
7	CORD CERIN	FIC/ATRE/O/FILE/ALS/	國國際運動於於	MINANNE		03/10/2004
	DUCER	Serial # A140	60 THIS CER	TIFICATE IS ISS	JED AS A MATTER O	
κΨ ιι	EGENDS ENVIRONMENTAL		I ONLY AN	D CONFERS N	O RIGHTS UPON TH	E CERTIFICAT
1:	305 GENE AUTRY WAY		ALTER TH	e coverage /	ATE DOES NOT AMEN	DLICIES BELO
Å	NAHEIM, CA 92805			CON PANIES	AFFORDING COVER	AGE
Ļ	CENSE #0C79875 14) 634-2683 (714) 634-3	704	COMPANY	UDSON INSUR	ANCE CO, A XII	
•	· · ·	· · · · · · · · · · · · · · · · · · ·		·		
NSI.	BARR & CLARK, IN	IC.	COMPANY			
	22850 CRENSHAW		COMPANY			
	TORRANCE, CA 9		C C			
			COMPANY			
	· ·	· · · · · · · · · · · · · · · · · · ·	D			
<u>_</u>	VERAGESH MAN IS CHARTEN	OLICIES OF INSURANCE LISTED GELOW				
	INDICATED NOTWITHSTANDING	ANY REQUIREMENT. TERM OR CONDIT	ION OF ANY CONTR.	ACT OR OTHER DO	CUMENT WITH RESPECT TO	WHICH THIS
	CERTIFICATE MAY BE ISSUED O EXCLUSIONS AND CONDITIONS	R MAY PERTAIN, THE INSURANCE AFFO OF SUCH POLICIES, LIMITS SHOWN MAY	RDED BY THE POLI	CIES DESCRIBED H CED BY PAID CLAIM	EREIN IS SUBJECT TO ALL ' S.	THE TERMS,
0			POLICY EFFECTIVE	FOLICY EXPIRATION		
R TR	TYPE OF INSURANCE	POLICY NUMBER	DATE (MM/DD/YY)	DATE (MM/DD/YY)	LIMIT	
	GENERAL LIABILITY	FEC610110	03/09/04	03/09/05	GENERAL AGGREGATE	\$ 2,000,0
٩ļ	COMMERCIAL GENERAL LIABILITY	- ·			PRODUCTS - COMP/OP AGG	s 1,000,0
	OWNER'S & CONTRACTOR'S PROT	l.			PERSONAL & ADV INJURY	s 1,000,0 s 1,000,0
	X CONTRACTORS POLL)		EACH OCCURRENCE	s 1,000,0 s 50,0
÷					FIRE DAMAGE (Any one fire) MED EXP (Any one person)	s <u>5,0</u>
Δ.		FEC510110	03/09/04	3/09/05	COMBINED SINGLE LIMIT	\$ 1,00D,0
	ALL OWNED AUTOS					
	SCHEDULED AUTOS	· ·			BODILY INJURY (Perperson)	57 ·
Ī	X HIRED AUTOS		:	· · .	BODILY INJURY	5
ļ	X NON-OWNED AUTOS				(Por scolent)	<u> </u>
					PROPERTY DAMAGE	5.
-	GARAGELIABILITY		+		AUTO ONLY - EA ACCIDENT	\$
	ANY AUTO		ľ		OTHER THAN AUTO ONLY:	
ľ					EAGH ACCIDENT	\$
				· · ·	AGGREGATE	\$
	EXCESS MABILITY				EACH OCCURRENCE	\$
	UMBRELLA FORM				AGGREGATE	5
	OTHER THAN UMBRELLA FORM	······	<u> </u>		WC SIAIG	\$
	Worker's compensation and Employers' liability				EL EACH ACCIDENT	3
		· •	· · .		EL DISEASE - POLICY LIMIT	3
	PARTNERS/EXECUTIVE				EL DISEASE - EA EMPLOYEE	3
,	PROFESSIONAL LIABILITY	EEOE10110	03/00/04	03/00/05		
٩.	CLAIMS MAKE	FEC510110	03/09/04	03/09/05	INCLUDED IN GL LIN CLAIMS MADE	II S ABOVE
			· .		- In June 14 11 114 (m	
			;			·
SC	RIPTION OF OPERATIONS/LOCATIONS/	ERICLES/SPECIAL TIEMS				
			· .			
/EF	REIGATEHOLDER	Neohonen Zaillan der für Alt staller Artiste infertisse kalai film at eden m	CANCEDIAT	ONST Minute Andread T		ANAL STREET, STREET, STORAGE
1.111		NOPPORTS LANDING PRODUCTION OF P			Scribed Policies Be Cân	
			EXPIRATION		e issuing company will e	
					THE CERTIFICATE HOLDER N	
	INFORMATION & B	DDING PURPOSES ONLY			TICE SHARE THPOSE NO OBLIG	
			OF ANY	1 / ~	DMPONY, IT'S AGENTS OR DEFENDENT INSURAINCE AGEN	

APPENDIX C

LEAD-RELATED CONSTRUCTION CERTIFICATION

Lead-Related Construction	Certificate Type	Expiration Date
Certificate	Inspector/Assesso	r 06/13/2010
	Project Monitor	06/13/2010
atthew R. C		



APPENDIX D

SOUTH COAST AIR QUALITY MANAGEMENT DISTRICT

DEMOLITION NOTIFICATION

SCAQMD NOTIFICATION OF DEMOLITION OR ASBESTOS REMOVAL MAIL ORIGINAL TO SCAQMD, ASBESTOS NOTIFICATIONS, FILE # 55641, LOS ANGELES CA 90074-5641

WASTE TRANSPORTER #2			WASTE STORAGE SIT	ſE						
ADDRESS			ADDRESS							
CITY	STATE	ZIP	CITY	STATE	ZIP					
CONTROLS: DESCRIBE WORK PRACTICES AND CONTROLS TO BE USED AT THE RENOVATION AND DEMOLITION SITE. Procedure # 1, 2, 3, 4, 5 or Other.										
For asbestos removals circle the combination of Rule 1403 procedures used. Procedure 4 and 5 submit plans for AQMD prior approval.										
ASBESTOS DETECTION PROCEDURE: CIRCLE THE PROCEDURES AND ANALYTICAL METHODS USED TO DETERMINE ASBESTOS IN THE BUILDING: Bulk Sampling, Inspection, Survey, PLM, PCM, TEM, Assumed as Asbestos, Describe Other:										
FOR DEMOLITIONS GIVE THE CO	MPANY NAME AND DATES O	F THE ASBEST	OS REMOVAL:							
FOR ORDERED DEMOLITION SEN AUTHORIZING PERSON: DATE OF ORDER:	ID A COPY OF THE ORDER A	ND GIVE THE A	GENCY NAME & PHONE TITLE DATE ORDERED TO B							
FOR EMERGENCY ASBESTOS RE EMERGENCY AND DESCRIBE THE SU		PHONE NUMBER	OF THE PERSON DECLAR	RING/AUTHORIZING THE EMERGENCY,	DATE AND HOLIR OF					
EXPLAIN HOW THE EVENT WOULD CA	AUSE UNSAFE CONDITIONS, EQI	UIPMENT DAMAG	E OR UNREASONABLE FIN	NANCIAL BURDEN:						
CONTINGENCY PLAN: DESCRIBE ASBESTOS MATERIAL BECOME CRUN				OS IS FOUND DURING DEMOLITION OF	NONFRIABLE					
TRAINING CERTIFICATION: certif evidence that the required training ha				03 and NESHAP will be on site during og normal business hours.	the removal and					
Company Name	Print name of owner/operator	Signature of ow	/ner/operator	Tittle of owner/operator	Date					
INFORMATION CERTIFICATION: 1	certify that the above informatic	on is correct and	I have enclosed any requ	ired attachments.						
Company Name	Print name of owner/operator	Signature of ow	/ner/operator	Tittle of owner/operator	Date					
	Notifications can not be accepted without the required fee (AQMD Rule 301). Asbestos removals of less than 100 square feet are exempt from notification and fees. Please make checks payable to "SCAQMD". Fees are per notification, not refundable, and vary according to the project size. Fees are as follows:									
DEMOLITION OR ASBESTOS REMOVAL FROM 100 TO 1,000 SQUARE FEET\$ 27.96PROCEDURE 4 OR 5 PLAN\$ 313.72FROM 1,001 TO 5,000 SQUARE FEET\$ 85.47REVISION OF NOTIFICATION\$ 11.31FROM 5,001 TO 10,000 SQUARE FEET\$ 200.07RETURNED CHECK CHARGE\$ 27.74MORE THAN 10,000 SQUARE FEET\$ 313.72CANCELLATION OF NOTIFICATION\$ 0.0DEMOLITION OF LESS THAN 100 SQ FT\$ 27.96ASBESTOS REMOVAL AT owner- occupied, single-unit dwelling\$ 27.96										
ATTENTION: Keep a copy of you demolition permit. For questions call				ion notification to Building and Safety do not hand carry to AQMD.	before issuance of a					

Forms, Instructions, and Rule 1403 can be obtained from web site http://www.aqmd.gov

* Asbestos surveys are required prior to Demolition and Renovation Forms, instructions, and the Rule 1403 can be obtained from AQMD web site http://www.aqmd.gov